

# **WASHTENAW COUNTY ROAD COMMISSION**



## **SPECIFICATIONS AND CONTRACT DOCUMENTS FOR 2018 COUNTY-WIDE GUARDRIAL PROJECT ITEM# 1806 - 001**

**WASHTENAW COUNTY,  
MICHIGAN**

**JUNE 2018**

**Washtenaw County Road Commission  
555 N. Zeeb Road  
Ann Arbor, MI 48103**

## ADVERTISEMENT FOR BID

Bids must be electronically submitted to <https://www.bidexpress.com/>, where they will be downloaded at 11 a.m. Local Time, **Wednesday, June 27, 2018** for constructing the following:

### 2018 COUNTY-WIDE GUARDRAIL PROJECT

Job No. 463-900-4077: contract for removing and installing new guardrail at 5 locations; Stony Creek Rd 1740' S of Whittaker Rd, Platt Rd 1800' S of Willis Rd, Pleasant Lake Rd 1976' E of Schneider Rd, Pleasant Lake Rd 1100' E of Reno Rd and Sager Rd 5400' W of Fletcher Rd.

Prospective bidders shall conform to the Michigan Department of Transportation prequalification requirements. **Net classification required for this project is N9-6L (Guardrail).** All subcontractors shall be required to meet the prequalification class of the particular items that they will be working on as part of this project.


Bids shall be submitted electronically to <https://www.bidexpress.com/>.

An electronic bidder's bond in the sum of not less than five (5%) of the base bid price is required by the instructions to bidders. In lieu of an electronic bond, a paper bond is acceptable, but must be received by the WCRC prior to the electronic bid opening.

The WCRC, in accordance with Title VI of the Civil Rights Act of 1964, 78 Stat. 252, 42 USC 2000d to 2000d-4 and Title 49, Code of Federal Regulations, Department of Federally assisted programs of the Department of Transportation issued pursuant to such Act, hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of gender, disability, race, color, or national origin in consideration for an award.

The Board reserves the right to reject any or all bids or any part of the same; to waive irregularities and/or informalities and to make the award in part or entirety as may appear to be in the best interest of the County of Washtenaw.

BOARD OF COUNTY ROAD COMMISSIONERS  
OF THE COUNTY OF WASHTENAW



Doug E. Fuller  
Chair

## **BIDDING REQUIREMENTS**

WASHTENAW COUNTY ROAD COMMISSION

NOTICE TO BIDDERS

**CONTACT INFORMATION**

2018Guardrail:BMS

1 of 1

04-23-2018

All inquiries concerning the plan or proposal for this project shall be directed to the following individual:

Brent M. Schlack, P.E.  
Assistant Director of Engineering - Traffic & Safety  
Washtenaw County Road Commission  
Phone: 734-327-6670  
Fax: 734-761-3737  
E-mail: [schlackb@wcroads.org](mailto:schlackb@wcroads.org)



WASHTENAW COUNTY ROAD COMMISSION

NOTICE TO BIDDERS

**COORDINATION CLAUSE**

2018Guardrail:BMS

1 of 1

04-23-2018

This Notice to Bidders specifies that the Contractor shall provide a minimum 7 day notice to the Washtenaw County Road Commission (WCRC) prior to starting work. No work shall commence until all signs and applicable temporary traffic control devices are erected as directed and approved by the Engineer.

Additional coordination will be required as the WCRC will be working alongside with the Contractor on items indicated on plans.

Signs scheduled for replacement will be installed at existing locations. Locations for new signs will be staked by WCRC. Stickers for all signs will be provided by the WCRC.

WASHTENAW COUNTY ROAD COMMISSION

NOTICE TO BIDDERS

**UTILITY COORDINATION**

2018Guardrail:BMS

1 of 2

04-23-2018

The contractor shall cooperate and coordinate construction activities with the owners of utilities as stated in Section 104.08 of the 2012 Michigan Department of Transportation (MDOT) Standard Specifications for Construction.

In addition, for the protection of underground utilities, the contractor shall follow the requirements in Section 107.12 of the 2012 MDOT Standard Specifications for Construction. Contractor delay claims, resulting from a utility, will be determined based upon Section 108.09 of the 2012 MDOT Standard Specifications for Construction.

For the protection of underground utilities and in conformance with Public Act 174 of 2013, the Contractor shall contact MISS DIG System, Inc. by phone at 811 or 800-482-7171 or via the web at either [elocate.missdig.org](http://elocate.missdig.org) for single address or [rte.missdig.org](http://rte.missdig.org), a minimum of 3 business days prior to excavating, excluding weekends and holidays. Members will thus be routinely notified. This does not relieve the Contractor of the responsibility of notifying utility owners who may not be a part of the "Miss Dig" alert system.

The owners of existing service facilities that are within grading or structure limits and designated to be moved or removed on the plans, will move them to locations designated by the Engineer or will remove them entirely from the right of way. Owners of public utilities will not be required by the County to move additional poles or structures in order to facilitate the operation of construction equipment unless it is determined by the Engineer that such poles or structures constitute a hazard to the public or are extraordinarily dangerous to the Contractor's operations.

The existing utilities shown on the plans represent the best information available as obtained from survey and existing records. This information does not relieve the Contractor of the responsibility of protecting all existing utilities, in case utilities have been constructed or removed since the survey date or if utilities are encountered in different locations.

The contractor shall be responsible for the protection of all existing utilities during construction of this project. Any utilities damaged by the Contractor shall be repaired in accordance with the related utility specifications at the Contractors expense.

The following Public Utilities have facilities located within the right-of-way (ROW) of this project:

| <u>OWNER'S NAME</u>    | <u>PHONE NUMBER</u> | <u>CONTACT PERSON</u> |
|------------------------|---------------------|-----------------------|
| AT&T                   | (734) 996-5350      | Andy Johnson          |
| Comcast                | (248) 809-2717      | Chris Cyr             |
| DTE-Electric           | (734) 397-4112      | Clay Combee           |
| DTE-Gas                | (313) 389-7261      | Laurie Forrester      |
| Enbridge               | (850) 273-2216      | Michael Johnson       |
| MCI/Verizon Business   | (317) 685-8050      | Chris Fowler          |
| Wolverine Pipeline Co. | (269) 323-2491      | Fred Hipshear         |
| YCUA                   | (734) 484-4600      | Scott Westover        |

WASHTENAW COUNTY ROAD COMMISSION

NOTICE TO BIDDERS

**CONSTRUCTION COORDINATION**

WCRC:BMS

1 of 1

01-29-2018

The Contractor's attention is directed to the requirements for cooperation with others as covered in Subsection 104.08 of the Michigan Department of Transportation (MDOT) 2012 Standard Specification for Construction.

The Contractor shall coordinate its operations with Contractors performing work on other projects within, or adjacent to, the Construction Influence Area (CIA) to avoid conflicts in maintaining traffic, construction signing, and progression of construction activities.

Traffic shall be maintained in accordance with the Special Provision for Maintenance of Traffic.

No claim for extra compensation or adjustments in contract unit prices will be allowed on account of delay or failure of others to complete work units scheduled.

WASHTENAW COUNTY ROAD COMMISSION

NOTICE TO BIDDERS

**RETAINAGE**

WCRC:BMS

1 of 1

05-01-2018

Two and a half percent (2.5%) retainage shall be held on all pay estimates until the contract work has been completed. All retainage shall be paid on the final pay estimate.

## **INSTRUCTION TO BIDDERS**

### **PROPOSALS**

This Proposal shall be electronically submitted to <https://www.bidexpress.com/>. The unit prices as submitted will govern in determining the correct total of the bid.

The proposal shall be electronically signed and the complete address of the Bidder given thereon.

Bids will be electronically downloaded from <https://www.bidexpress.com/> at **11 A.M.**, local time, **Wednesday, June 27, 2018**.

An electronic bid bond in the amount of 5% of the bid price, payable to the Washtenaw County Road Commission, is to accompany each proposal. No bid may be withdrawn for at least ninety (90) days after the scheduled closing time for receiving bids.

### **QUALIFICATIONS OF BIDDERS**

The name and legal status of bidder, that is, as a corporation, partnership or individual, shall be stated in the proposal.

Anyone signing a proposal as an agent of another or others must submit with the proposal legal evidence of its authority to do so.

The place of residence of each bidder, or the office address in the case of a firm or company, with county and state, must be given after its signature.

Prospective bidders shall conform to the Michigan Department of Transportation pre-qualification requirements.

It is the intention of the Washtenaw County Road Commission to award this Contract to a Contractor fully capable, both financially and as regards experience, to perform and complete all work in a satisfactory manner. Evidence of such competency must be furnished, including a list of similar projects elsewhere, which the bidder has satisfactorily undertaken and completed. All bidders shall examine the plans and specifications and make a personal examination of the sites, transportation facilities and the like.

### **CONTRACT CONDITIONS**

The submission of a bid shall be considered prima facie evidence that the bidder has made a thorough examination of the plans, specifications and work sites and is satisfied as to the conditions to be encountered in performing the work. No allowance or extra consideration on behalf of the Contractor will subsequently be allowed by reason of error or oversight on the part of the Contractor.

All requirements and specifications as described in the Michigan Department of Transportation "2012 Standard Specifications for Construction" and "MDOT Road and

Bridge Standard Plans”, or as adopted by the Michigan Department of Transportation, shall be adhered to unless otherwise stated in the proposal or on the plans.

### **LIVING WAGE RATES**

The Washtenaw County Road Commission has passed a Living Wage Regulation that requires employers who provide services to the Road Commission and the public to pay their employees under that contract, a minimum of either \$13.13 per hour with benefits or \$14.65 per hour without benefits. The Contractor agrees to comply with this Ordinance in paying its employees. The Contractor understands and agrees that an adjustment of the living wage amounts, based upon the Health and Human Services poverty guidelines, will be made before April 30, 2018 and annually thereafter which amount shall be automatically incorporated into this contract. The Road Commission agrees to give the Contractor two (2) weeks’ notice of such change. Contractor agrees to post a notice containing the County’s Living Wage requirements at a location at its place of business accessed by its employee. Certified weekly payroll records covering the Contractor’s and all Subcontractors’ work forces shall be completed, and submitted to the Project Engineer.

### **PROGRESS SCHEDULE**

The bidder to whom an award is made will be required to:

1. Enter into a written agreement.
2. Submit a preliminary progress schedule.
3. Commit to attending a pre-construction meeting with Washtenaw County Road Commission representatives to discuss, and work out, a detailed progress schedule and other project-related items and concerns.

In case of failure to comply with these requirements, the bidder may be considered to have abandoned all its rights, interest in the award and its amount of bidder’s bond may be declared to be forfeited to the Washtenaw County Road Commission, and the Contract may be awarded to another.

The Progress Schedule shall include, as a minimum, the starting and completion dates for major items, and the final project completion date specified in the Bidding Proposal.

If the Bidding Proposal specifies other controlling dates, these shall also be included in the Progress Schedule.

Failure on the part of the Contractor to carry out the provisions of the Progress Schedule as established, may be considered sufficient cause to prevent bidding future projects until a satisfactory rate of progress is again established.

The entire project shall be completed on or before **Friday, November 2, 2018.**

## **RESERVATIONS BY THE COUNTY**

The Washtenaw County Road Commission reserves the right to reject any or all proposals or any part of same, to waive irregularities and/or informalities and to make the award in part or entirety as may appear to be in the best interest of the County of Washtenaw.

The Washtenaw County Road Commission reserves the right to make, by work order or authorization, at any time during the work, such changes in quantities as are necessary to satisfactorily complete the project.

## **BONDS**

The successful bidder shall be required to furnish for each set of executed Contract documents and conformed copies thereof an original conformed Performance Bond and Labor and Material Bond.

## **INSURANCE**

The Contractor, prior to execution of the Contract, shall file with the Washtenaw County Road Commission a Certificate or Certificates of Insurance, in form satisfactory to the Road Commission, showing that it has complied with the insurance requirements set forth in Section 107.10 of the Michigan Department of Transportation "2012 Standard Specifications for Construction."

The Contractor shall provide for and in behalf of the Washtenaw County Road Commission as their interest may appear, Owner's Protective Liability Insurance. Such insurance shall provide coverage and limits the same as the Contractors Public Liability Insurance. Contractual Insurance shall be provided as a part of this policy or the Contractual Exclusion shall be removed from the policy by endorsement.



# Washtenaw County Road Commission

## Schedule of Items (Itemized Bid Sheet)

Letting Date: Wednesday, June 27, 2018 11:00 AM

---

**Contract ID:** 1806-001  
**Location:** Countywide Guardrail Project  
**Description:** Upgrading guardrails at five (5) locations countywide

---

|   |  |
|---|--|
| <b>Project Number:</b> 1806-001               | <b>Project Engineer:</b> BMS / Est BLH |
| <b>Estimate Number:</b> 1                     | <b>Date Created:</b> 04/03/2018        |
| <b>Project Type:</b> Miscellaneous            | <b>Fed/State #:</b>                    |
| <b>Location:</b> Countywide Guardrail Project | <b>Fed Item:</b>                       |
|   | <b>Control Section:</b>                |

**Description:** Upgrading guardrails at five (5) locations countywide

---

**Instructions to Bidders:** IMPORTANT NOTICE:  
If the proposal establishes a maximum price for any of the following work items, and if you bid a price higher than that maximum price, your bid will be considered to have quoted the maximum price and your bid total will be adjusted to reflect that maximum price.

If the proposal provides a specified price for any of the following work items, and if you bid a price higher or lower than that specified price, your bid will be adjusted to reflect that specified price.

If your bid is the lowest accepted bid, and if you refuse to accept the award of the contract due to the change in what you quoted as a maximum or specified price, you will forfeit your proposal guaranty.

| Pay Item | Description  | Quantity | Units | Unit Price |     | Bid Amount |     |
|----------|--|----------|-------|------------|-----|------------|-----|
|          |  |          |       | Dollars    | Cts | Dollars    | Cts |
| 1500001  | Mobilization, Max  | 1        | LSUM  |            |     |            |     |
| 2040035  | Guardrail, Rem   | 300      | Ft    |            |     |            |     |
| 2047001  | _ Guardrail, Rem, Rails and Bridge Posts                         | 100      | Ft    |            |     |            |     |
| 2050010  | Embankment, CIP  | 114      | Cyd   |            |     |            |     |
| 2050016  | Excavation, Earth  | 71       | Cyd   |            |     |            |     |
| 3070121  | Shoulder, CI II  | 15       | Ton   |            |     |            |     |
| 7067010  | _ Wingwall Repair  | 78       | Sft   |            |     |            |     |
| 7120007  | Hand Chipping, Other Than Deck                                   | 2        | Cft   |            |     |            |     |
| 7120017  | Patch, Forming   | 20       | Sft   |            |     |            |     |
| 7120112  | Patching Conc, C-L   | 2        | Cyd   |            |     |            |     |
| 8070000  | Guardrail, Type B  | 450      | Ft    |            |     |            |     |
| 8070042  | Guardrail Approach Terminal, Type 2B                             | 15       | Ea    |            |     |            |     |
| 8070080  | Guardrail Reflector  | 44       | Ea    |            |     |            |     |
| 8077001  | _ Guardrail, Type B, 8 Ft Posts, Modified                        | 150      | Ft    |            |     |            |     |
| 8077001  | _ Retaining Wall, Modified                                       | 403      | Ft    |            |     |            |     |
| 8077050  | _ Guardrail, Thrie Beam Backed, Detail B                         | 4        | Ea    |            |     |            |     |
| 8077050  | _ Modified Guardrail Departing Terminal, Type B, 15 Ft Radius    | 1        | Ea    |            |     |            |     |
| 8100403  | Sign, Type III, Rem  | 12       | Ea    |            |     |            |     |
| 8120012  | Barricade, Type III, High Intensity, Double Sided, Lighted, Furn | 6        | Ea    |            |     |            |     |
| 8120013  | Barricade, Type III, High Intensity, Double Sided, Lighted, Oper | 6        | Ea    |            |     |            |     |
| 8120030  | Channelizing Device, 42 inch, Furn                               | 80       | Ea    |            |     |            |     |

| Pay Item          | Description                         | Quantity | Units | Unit Price |     | Bid Amount |     |  |
|-------------------|-------------------------------------|----------|-------|------------|-----|------------|-----|--|
|                   |                                     |          |       | Dollars    | Cts | Dollars    | Cts |  |
| 8120031           | Channelizing Device, 42 inch, Oper  | 80       | Ea    |            |     |            |     |  |
| 8120130           | Lighted Arrow, Type B, Furn         | 8        | Ea    |            |     |            |     |  |
| 8120131           | Lighted Arrow, Type B, Oper         | 8        | Ea    |            |     |            |     |  |
| 8120170           | Minor Traf Devices                  | 1        | LSUM  |            |     |            |     |  |
| 8120350           | Sign, Type B, Temp, Prismatic, Furn | 1,104    | Sft   |            |     |            |     |  |
| 8120351           | Sign, Type B, Temp, Prismatic, Oper | 1,104    | Sft   |            |     |            |     |  |
| 8120370           | Traf Regulator Control              | 1        | LSUM  |            |     |            |     |  |
| <b>Total Bid:</b> |                                     |          |       |            |     |            |     |  |

**Contractor:** \_\_\_\_\_

\_\_\_\_\_  
(Signature)

\_\_\_\_\_  
(Date)

**PROPOSAL FOR THE  
CONSTRUCTION OF HIGHWAY IMPROVEMENTS  
FOR THE  
WASHTENAW COUNTY ROAD COMMISSION, MICHIGAN**

To the Washtenaw County Road Commission, Michigan

The undersigned as bidder hereby declares that this bid is made in good faith, without fraud or collusion with any person or persons bidding on the same Contract; that it has read and examined the advertisement, general conditions, contract, forms of bonds, plans, specifications and the locations of the work described herein and is fully informed as to the nature of the work and the conditions relating to its performance and understands that the quantities shown are approximate only and are subject to either increase or decrease.

The undersigned hereby proposes to furnish all necessary machinery, tools, apparatus and other means of construction, do all the work, furnish all the materials except as otherwise specified herein; and, for the unit prices or lump sums named in the itemized bid, to complete the work herein described in strict accordance with the plans therefore and in strict conformity with the requirements of the 2012 Michigan Department of Transportation Standard Specifications for Construction, and such other special provisions and supplemental specifications as may be a part of this proposal.

The under signed further proposes to do such extra work as may be authorized by the Washtenaw County Road Commission, prices for which are not included in the itemized bid. Compensation shall be made on the basis agreed upon before such extra work is begun.

The undersigned agrees that if the foregoing Proposal shall be accepted by the Washtenaw County Road Commission, it will, within ten (10) days (Sundays and legal holidays excepted) after receiving notice of such acceptance enter into the attached form of Agreement for the Construction of Highway Improvements and perform all related work, ready for use, at the price and within the time stated in this Proposal, and that it will furnish the Washtenaw County Road Commission satisfactory contract bonds and certificates of insurance coverage.

The undersigned further agrees that if the foregoing Proposal shall be accepted, it will commence work immediately and complete the work as per progress schedule.

The undersigned shall provide an electronic or paper bidders bond in the sum of not less than **five percent (5%)** of the Base Bid Price as required by the Advertisement and Instructions to Bidders, and the undersigned agrees that in case it shall fail to fulfill its obligations under the forgoing Proposal and/or shall fail to furnish bonds, as specified, the Washtenaw County Road Commission may, as its option, determine that the undersigned has abandoned it rights and interests in such Contract and that the amount of said bidders bond accompanying its Proposal has been forfeited to the Washtenaw County Road Commission, but otherwise the said bidders bond shall be returned to the undersigned upon the execution of the Contract and acceptance of the bonds.

In submitting this bid, it is understood that the right is reserved by the Washtenaw County Road Commission to reject any or all bids, to waive irregularities and/or informalities and, in general, to make the award in any manner deemed by it, in its sole discretion, to be in the best interest of the County of Washtenaw.

Company: \_\_\_\_\_

Official Address: \_\_\_\_\_

\_\_\_\_\_

Telephone: \_\_\_\_\_

By (signed): \_\_\_\_\_

By (typed or print): \_\_\_\_\_

Title: \_\_\_\_\_ Date: \_\_\_\_\_

**LEGAL STATUS OF BIDDER**

A Corporation duly organized and doing business under the laws of the State of Michigan, for whom \_\_\_\_\_, whose signature is affixed to this Proposal, is duly authorized to execute contracts.

All members of which, with addresses are:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Whose signature is affixed to this Proposal:

\_\_\_\_\_

**SPECIAL PROVISIONS**

WASHTENAW COUNTY ROAD COMMISSION

**PROGRESS CLAUSE**

2018Guardrail:BMS

1 of 1

05-01-2018

**The Contractor shall start work no earlier than September 4, 2018, or on a date agreed upon with the Engineer.** In no case shall any work commence prior to receipt of formal notice of award.

The entire project shall be complete on or before **Friday, November 2, 2018.**

The low bidder for the work covered by this proposal will be required to prepare and submit Form 1130, Progress Schedule to the Project Engineer, for review, comment, and approval at or before the preconstruction meeting.

The Progress Schedule shall include, as a minimum, the starting and completion date for major items, and where specified in the Bidding Proposal the project opened to traffic date, as well as the final project completion date specified in the Bidding Proposal.

The Project Engineer will arrange the time and place for the preconstruction meeting.

The named subcontractors(s) for Specialty and/or Designated Items (if such items are designated in the proposal), which materially affect the work schedule, shall also be present at the scheduled meeting and they will be required to sign the Progress Schedule to indicate their approval of the scheduled dates of work set forth in the Progress Schedule.

Liquidated damages are to be per subsection 108.10 of the MDOT 2012 Standard Specifications for Construction.

No work will be permitted on the dates as specified in the MDOT 2012 Standard Specifications for Construction.

No work shall occur on Saturdays or Sundays unless authorized by the Engineer. If the Bidding Proposal specifies other controlling dates, these shall also be included in the Progress Schedule.

Failure on the part of the Contractor to carry out the provisions of the Progress Schedule, as established, may be considered sufficient cause to prevent bidding future projects until a satisfactory rate of progress is again established.

The starting date, contract time, or completion date for this project may be adjusted by the Washtenaw County Road Commission without imposing liquidated damages upon the receipt of satisfactory documented evidence that unforeseen delayed delivery of critical materials will prevent the orderly prosecution of the work.

WASHTENAW COUNTY ROAD COMMISSION

SPECIAL PROVISION  
FOR  
**MAINTENANCE OF TRAFFIC**

2018Guardrail:BMS

1 of 4

05/2018

**a. General Requirements.** This work shall be in accordance with Sections 104.11 and 812 of the Michigan Department of Transportation (MDOT) 2012 Standard Specifications for Construction including any Supplemental Specifications and Special Provisions, the 2011 Michigan Manual on Uniform Traffic Control Devices (MMUTCD), as shown on the plans, and as specified in the proposal.

The Contractor shall notify the Engineer a minimum of 72 hours prior to the implementation of any lane closures, detours, road closures, or major traffic shifts.

The Washtenaw County Road Commission (WCRC) maintenance crews may perform maintenance work within or adjacent to the construction influence area. Should this occur, WCRC will coordinate their operations with the Engineer to minimize the interference to the Contractor.

**b. Construction Influence Area (CIA).** The construction influence area shall include the Rights-of-Way of the roads at the following locations, within the approximate limits of 500 feet on either side:

1. Stony Creek Rd 1740' S of Whittaker Rd (Ypsilanti Twp, Sections 20,21);
2. Platt Rd 1800' S of Willis Rd (York Twp, Sections 10,11);
3. Pleasant Lake Rd 1976' E of Schneider Rd (Freedom Twp, Section 23);
4. Pleasant Lake Rd 1100' E of Reno Rd (Freedom Twp, Section 21);
5. Sager Rd 5400' W of Fletcher Rd (Lima Twp, Section 30).

In addition, the CIA shall include the Rights-of-Way of any public roads intersecting with either Stony Creek Rd, Platt Rd, and Pleasant Lake Rd within the limits identified in the items above. The CIA within these Rights-of-Way shall be to the point where the construction signing begins/ends.

**c. Maintenance of Traffic.** The Contractor shall maintain traffic at each project location and any adjacent side roads using a flagging operation when traffic interference occurs.

The contractor will be permitted to temporarily close the following roadways:

Stony Creek Road 1740' S of Whittaker Road

Stony Creek Road will be permitted to be closed for a maximum of **7 days**, unless approved by the Engineer. All other work shall be performed with utilizing a daytime traffic regulator. The proposed detour shall utilize Textile Road and Whittaker Road.



Once work is initiated that includes any lane restrictions and/or closures, that work must be continuous until completed.

The Contractor shall be responsible for providing access to all properties and intersecting roads adjacent to the CIA at all times, unless otherwise directed by the Engineer in writing. Interference with traffic at all intersections and driveways within the construction influence area shall be held to a minimum during the time required for construction.

The Contractor shall be responsible for coordinating project work activities with all property owners within the CIA to minimize impacts to businesses and maintain acceptable ingress and egress to their properties.

The Contractor shall furnish, place, and maintain signs, barricades, plastic drums, lights, arrow panels, and minor traffic control devices along the detour route and within the CIA for the maintenance of traffic, and upon completion of the work, remove these items from the project.

The traffic control required by this Special Provision is based on information contained on the plans. The Contractor, subject to review and approval from the Engineer, may use an alternate traffic control plan.

**d. Traffic Control Devices.** All signs shall conform to the 2011 MMUTCD. Warning signs shall be fabricated with prismatic sheeting material.

Tables for 'D', 'B', and 'L' values are shown on attached Typical M0020a. The temporary traffic control devices shall be placed according to Michigan Department of Transportation Traffic and Safety Special Detail WZD-125-E. Distances between construction warning, regulatory and guide signs shown on the plans and on details within the proposal are approximate and may require field adjustment, as directed by the Engineer. Signs should be placed per the Michigan Department of Transportation Traffic and Safety Special Detail WZD-100-A.

During non-work hours, any work site with uncompleted work shall have advance signs and plastic drums with high intensity sheeting, at specific locations, as directed by the Engineer.

All flagging procedure signs shall be laid down or covered when the operation is not in use or at the end of the work day. They shall also be in place prior to commencing a flagging operation.

All existing traffic control devices damaged or lost by the Contractor shall be replaced at the Contractor's expense.

All sign materials and supports must be approved by the FHWA and Michigan Department of Transportation as meeting the most current crash worthy requirements.

Channelizing devices shall be plastic drums with high intensity sheeting. All channelizing devices used on this project will have sufficient ballast to prevent them from moving or tipping. If moving or tipping of channelizing devices occurs as the result of wind generated by traffic or occurring naturally, the Contractor will be required to place additional ballast on the channelizing devices at no additional cost to the WCRC, as directed by the Engineer.

All channelizing devices used within the construction sequence shall be the same type of devices. No intermixing of different types of channelizing devices shall be allowed within a construction sequence of this project.

Upon completion of the work and under direction from the Engineer, all temporary traffic control devices from the project shall be removed within **ten (10) calendar days from the date notified**. If any devices exist 10 calendar days after having been notified, the WCRC shall remove the devices at the Contractor's expense. The devices will be stored at the WCRC main yard. A contract price adjustment to appropriate line items will be made in the amount of \$150 per hour for every hour WCRC forces work to remove the temporary traffic control devices. A \$250 impoundment fee will also be imposed to the Contractor. The Contractor or owner of the devices shall be responsible to pickup the devices from the WCRC main yard. If the devices are not retrieved within 90 days of impoundment, the WCRC reserves the right to dispose the materials.

Storage of equipment within the right-of-way will be at the discretion of the Engineer. Any additional signs or devices required protecting the traveling public from stored equipment or material will be at the Contractor's expense.

The traffic control required by this Special Provision is based on information contained in these specifications and contract documents. The Contractor, subject to review and approval from the Engineer, may use an alternate traffic control plan.

Separate pay items are provided in the contract to compensate for the traffic maintenance outlined in this special provision. All other costs due to traffic maintenance are the responsibility of the Contractor.

Barricades, plastic drums, and traffic cones necessary for traffic control and public safety shall be furnished and erected by the Contractor as shown on the appropriate detail or as directed by the Engineer.

**e. Truck Haul Routes.** Truck haul routes selected by the Contractor must be submitted to the WCRC for approval prior to the start of construction and are subject to regulations of the WCRC.

**f. Emergency Vehicle Access.** Access for ALL types of emergency vehicles shall be maintained within the project limits as described within this provision.

**g. Cleaning Adjacent Streets and Sidewalks.** Dirt, mud, construction materials, or other debris deposited on public sidewalks or streets as the result of spilling, tracking on the wheels of trucks or construction equipment, or by other actions of the Contractor, his employees, or his subcontractors shall be immediately removed by the Contractor.

**h. Other Requirements.** Failure to comply with all stipulations of the above traffic specifications may be cause for complete shutdown of the project.

In the event of an emergency, these requirements are subject to change if traffic conditions indicate such a necessity. At all times on the project during periods of traffic control set up and traffic regulation the Maintenance of Traffic specifications are to be on the person of individual(s) responsible to perform this work for the Contractor.

Should the Contractor, after being notified, fail to provide and maintain adequate traffic control devices, the WCRC forces may be directed to do so. The costs of signs, lights, etc., and placement of the same will be charged to the Contractor.

**i. Measurement and Payment.** The plans specify the temporary traffic control items that have been set up for maintenance of traffic during construction zone operations. Total quantities will be paid once per log project to cover costs associated with mobilization and removal of these traffic devices. The contractor will not be paid extra to move or relocate these devices as directed by the engineer once the devices are mobilized to the job site.

## MINIMUM MERGING TAPER LENGTH "L" (FEET)

| OFFSET<br>FEET | POSTED SPEED LIMIT, MPH (PRIOR TO WORK AREA) |     |     |     |     |     |     |     |     |      |
|----------------|--|-----|-----|-----|-----|-----|-----|-----|-----|------|
|                | 25   | 30  | 35  | 40  | 45  | 50  | 55  | 60  | 65  | 70   |
| 1              | 10   | 15  | 20  | 27  | 45  | 50  | 55  | 60  | 65  | 70   |
| 2              | 21   | 30  | 41  | 53  | 90  | 100 | 110 | 120 | 130 | 140  |
| 3              | 31   | 45  | 61  | 80  | 135 | 150 | 165 | 180 | 195 | 210  |
| 4              | 42   | 60  | 82  | 107 | 180 | 200 | 220 | 240 | 260 | 280  |
| 5              | 52   | 75  | 102 | 133 | 225 | 250 | 275 | 300 | 325 | 350  |
| 6              | 63   | 90  | 123 | 160 | 270 | 300 | 330 | 360 | 390 | 420  |
| 7              | 73   | 105 | 143 | 187 | 315 | 350 | 385 | 420 | 455 | 490  |
| 8              | 83   | 120 | 163 | 213 | 360 | 400 | 440 | 480 | 520 | 560  |
| 9              | 94   | 135 | 184 | 240 | 405 | 450 | 495 | 540 | 585 | 630  |
| 10             | 104  | 150 | 204 | 267 | 450 | 500 | 550 | 600 | 650 | 700  |
| 11             | 115  | 165 | 225 | 293 | 495 | 550 | 605 | 660 | 715 | 770  |
| 12             | 125  | 180 | 245 | 320 | 540 | 600 | 660 | 720 | 780 | 840  |
| 13             | 135  | 195 | 266 | 347 | 585 | 650 | 715 | 780 | 845 | 910  |
| 14             | 146  | 210 | 286 | 374 | 630 | 700 | 770 | 840 | 910 | 980  |
| 15             | 157  | 225 | 307 | 400 | 675 | 750 | 825 | 900 | 975 | 1050 |

TAPER LENGTH "L" IN FEET

THE FORMULAS FOR THE MINIMUM LENGTH OF A MERGING TAPER IN DERIVING THE "L" VALUES SHOWN IN THE ABOVE TABLES ARE AS FOLLOWS:

"L" =  $\frac{W \times S^2}{60}$  WHERE POSTED SPEED PRIOR TO THE WORK AREA IS 40 MPH OR LESS

"L" = S x W WHERE POSTED SPEED PRIOR TO THE WORK AREA IS 45 MPH OR GREATER

- L = MINIMUM LENGTH OF MERGING TAPER
- S = POSTED SPEED LIMIT IN MPH PRIOR TO WORK AREA
- W = WIDTH OF OFFSET

### TYPES OF TAPERS


#### UPSTREAM TAPERS

- MERGING TAPER
- SHIFTING TAPER
- SHOULDER TAPER
- TWO-WAY TRAFFIC TAPER

#### DOWNSTREAM TAPERS (USE IS OPTIONAL)

### TAPER LENGTH

- L - MINIMUM
- 1/2 L - MINIMUM
- 1/3 L - MINIMUM
- 100' - MAXIMUM
- 100' - MINIMUM (PER LANE)

|   |   |                         |        |
|---|---|-------------------------|--------|
| <br>TRAFFIC AND SAFETY<br>MAINTAINING TRAFFIC<br>TYPICAL | TABLES FOR "L", "D" AND "B" VALUES      |                         |        |
|   | DRAWN BY: CON:AE:djf<br>CHECKED BY: BMM | JUNE 2006<br>PLAN DATE: | M0020a |
| FILE: K:/DGN/TSR/STDS/ENGLISH/MNTTRF/M0020a.dgn REV. 08/21/2006   |   |                         |        |

DISTANCE BETWEEN TRAFFIC CONTROL DEVICES "D"  
AND LENGTH OF LONGITUDINAL BUFFER SPACE ON  
"WHERE WORKERS PRESENT" SEQUENCES


| "D"<br>DISTANCES | POSTED SPEED LIMIT, MPH (PRIOR TO WORK AREA) |     |     |     |     |     |     |     |     |     |
|------------------|--|-----|-----|-----|-----|-----|-----|-----|-----|-----|
|                  | 25   | 30  | 35  | 40  | 45  | 50  | 55  | 60  | 65  | 70  |
| D (FEET)         | 250  | 300 | 350 | 400 | 450 | 500 | 550 | 600 | 650 | 700 |

GUIDELINES FOR LENGTH OF  
LONGITUDINAL BUFFER SPACE "B"


| SPEED*<br>MPH | LENGTH<br>FEET |
|---------------|----------------|
| 20            | 33             |
| 25            | 50             |
| 30            | 83             |
| 35            | 132            |
| 40            | 181            |
| 45            | 230            |
| 50            | 279            |
| 55            | 329            |
| 60            | 411            |
| 65            | 476            |
| 70            | 542            |

\* POSTED SPEED, OFF PEAK 85TH PERCENTILE SPEED PRIOR TO WORK STARTING, OR THE ANTICIPATED OPERATING SPEED

1 BASED UPON AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO) BRAKING DISTANCE PORTION OF STOPPING SIGHT DISTANCE FOR WET AND LEVEL PAVEMENTS (A POLICY ON GEOMETRIC DESIGN OF HIGHWAY AND STREETS), AASHTO. THIS AASHTO DOCUMENT ALSO RECOMMENDS ADJUSTMENTS FOR THE EFFECT OF GRADE ON STOPPING AND VARIATION FOR TRUCKS.

|  |   |                         |        |
|--|---|-------------------------|--------|
| <br>Michigan Department of Transportation<br>TRAFFIC AND SAFETY<br>MAINTAINING TRAFFIC<br>TYPICAL | TABLES FOR "L", "D" AND "B" VALUES      |                         |        |
|  | DRAWN BY: CON:AE:djf<br>CHECKED BY: BMM | JUNE 2006<br>PLAN DATE: | M0020a |
| FILE: K:/DGN/TSR/STDS/ENGLISH/MNTTRF/M0020a.dgn      REV. 08/21/2006   |   |                         |        |

SIGN PLACEMENT IS THE SAME FOR BOTH DIRECTIONS



SIGN = 68 f+2 - TYPE B  
FOR ONE DIRECTION OF TRAFFIC  
W20-1 QUANTITY INCLUDED  
WITH APPROPRIATE TYPICAL  
FOR SEQUENCE SIGNING

**MDOT**  
Michigan Department of Transportation  
TRAFFIC AND SAFETY  
MAINTAINING TRAFFIC  
TYPICAL

TYPICAL ADVANCE SIGNING TREATMENT FOR LONG, INTERMEDIATE AND SHORT TERM STATIONARY WORK ZONE OPERATIONS OF LESS THAN TWO MILES IN LENGTH WHERE TRAFFIC CONTROL DEVICES MAY REMAIN AT END OF WORK DAY ON AN UNDIVIDED TWO-WAY ROADWAY

DRAWN BY: CON:AE:djf  
CHECKED BY: BMM:CRB

OCTOBER 2011  
PLAN DATE:

M0040a

25 SHEET  
1 OF 2

NOT TO SCALE


FILE: PW RD/TS/Typicals/Signs/MT NON FWY/M0040a.dgn REV. 10/13/2011

## NOTES

- 30. THE APPROPRIATE ADVANCE SIGNING SEQUENCE(S), (M0030a THROUGH M0080a) SHALL BE USED ON ALL PROJECTS.
- 32. THESE SIGNS SHALL BE LEFT IN PLACE AT THEIR PRESCRIBED LOCATIONS FOR THE DURATION OF THE PROJECT AND UNTIL ALL TEMPORARY TRAFFIC CONTROL HAS BEEN REMOVED.
- 35. THESE SIGNS ARE INTENDED TO BE USED WITHIN THE LIMITS OF THE TEMPORARY SEQUENCE SIGNING AS IS SHOWN ON 1 OF 2. THESE SIGNS ARE NOT TO BE INTERMINGLED WITH ANY OTHER TEMPORARY SEQUENCE SIGNING EXCEPT AS SHOWN.



## SIGN SIZES

|        |   |           |
|--------|---|-----------|
| G20-2  | - | 48" x 24" |
| R5-18a | - | 96" x 60" |
| R5-18b | - | 48" x 60" |
| W20-1  | - | 48" x 48" |


|   |  |              |        |
|---|--|--------------|--------|
| <br>TRAFFIC AND SAFETY<br>MAINTAINING TRAFFIC<br>TYPICAL | TYPICAL ADVANCE SIGNING TREATMENT FOR LONG, INTERMEDIATE AND SHORT TERM STATIONARY WORK ZONE OPERATIONS OF LESS THAN TWO MILES IN LENGTH WHERE TRAFFIC CONTROL DEVICES MAY REMAIN AT END OF WORK DAY ON AN UNDIVIDED TWO-WAY ROADWAY |              |        |
|   | DRAWN BY: CON:AE:djf   | OCTOBER 2011 | M0040a |
| CHECKED BY: BMM:CRB   | PLAN DATE:   | 26           | 2 OF 2 |
| FILE: PW RD/TS/Typicals/Signs/MT NON FWY/M0040a.dgn REV. 10/13/2011   |  |              |        |

NOT TO SCALE

**KEY**

- • • CHANNELIZING DEVICES
-  LIGHTED ARROW PANEL (CAUTION MODE)
-  TRAFFIC FLOW
- REFLECTS EXISTING SPEED LIMIT
- \* USE THE "NEXT -- MILES" SIGN WHEN SHOULDER CLOSURE EXCEEDS 1 MILE IN LENGTH

SIGN = 120 ft± - TYPE B  
 W/PLAQUE = 132 ft± - TYPE B  
 PLUS ADDITIONAL R2-1's  
 THROUGHOUT WORK AREA



PLACE THROUGHOUT WORK AREA AS INDICATED AND AFTER ALL MAJOR CROSSROADS IF PERMANENT SIGNS ARE NOT IN PLACE.

PLACE THROUGHOUT WORK AREA AS INDICATED AND AFTER ALL MAJOR CROSSROADS IF PERMANENT SIGNS ARE NOT IN PLACE.

PLACE THIS SIGN ALONG WITH THE ADVANCE WORK ZONE SIGNING AS DEPICTED ON THE APPROPRIATE TYPICAL M0030a-M0080a.

PLACE THIS SIGN ALONG WITH THE ADVANCE WORK ZONE SIGNING AS DEPICTED ON THE APPROPRIATE TYPICAL M0030a-M0080a.

**MDOT**  
 Michigan Department of Transportation  
 TRAFFIC AND SAFETY  
 MAINTAINING TRAFFIC  
 TYPICAL

TYPICAL TEMPORARY TRAFFIC CONTROL  
 FOR A SHOULDER CLOSURE ON A TWO  
 LANE TWO-WAY ROADWAY  
 NO SPEED REDUCTION

|   |              |        |    |       |
|---|--------------|--------|----|-------|
| DRAWN BY: CON:AE:djf  | OCTOBER 2011 | M0110a | 27 | SHEET |
| CHECKED BY: BMM:CRB   | PLAN DATE:   |        | 1  | OF 2  |
| FILE: PW RD/TS/Typicals/Signs/MT NON FWY/M0110a.dgn REV. 10/04/2011 |              |        |    |       |

NOT TO SCALE




## NOTES

1. D = DISTANCE BETWEEN TRAFFIC CONTROL DEVICES  
 $1/3 L$  = MINIMUM LENGTH OF TAPER  
 B = LENGTH OF LONGITUDINAL BUFFER  
 SEE **M0020a** FOR "D," "L," AND "B" VALUES
2. ALL NON-APPLICABLE SIGNING WITHIN THE CIA SHALL BE MODIFIED TO FIT CONDITIONS, COVERED OR REMOVED.
3. DISTANCES BETWEEN SIGNS, THE VALUES FOR WHICH ARE SHOWN IN TABLE D, ARE APPROXIMATE AND MAY NEED ADJUSTING AS DIRECTED BY THE ENGINEER.
- 3A. THE "WORK ZONE BEGINS" (R5-18c) SIGN SHALL BE USED ONLY IN THE INITIAL SIGNING SEQUENCE IN THE WORK ZONE. SUBSEQUENT SEQUENCES IN THE SAME WORK ZONE SHALL OMIT THIS SIGN AND THE QUANTITIES SHALL BE ADJUSTED APPROPRIATELY.
- 4E. THE MAXIMUM RECOMMENDED DISTANCE(S) BETWEEN CHANNELIZING DEVICES SHOULD BE EQUAL IN FEET TO THE POSTED SPEED IN MILES PER HOUR ON TAPER(S) AND TWICE THE POSTED SPEED IN THE PARALLEL AREA(S).
5. FOR OVERNIGHT CLOSURES, TYPE III BARRICADES SHALL BE LIGHTED.
6. WHEN CALLED FOR IN THE FHWA ACCEPTANCE LETTER FOR THE SIGN SYSTEM SELECTED, THE TYPE A WARNING FLASHER, SHOWN ON THE WARNING SIGNS, SHALL BE POSITIONED ON THE SIDE OF THE SIGN NEAREST THE ROADWAY.
7. ALL TEMPORARY SIGNS, TYPE III BARRICADES, THEIR SUPPORT SYSTEMS AND LIGHTING REQUIREMENTS SHALL MEET NCHRP 350 CRASHWORTHLY REQUIREMENTS STIPULATED IN THE CURRENT EDITION OF THE MICHIGAN MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, THE CURRENT EDITION OF THE STANDARD SPECIFICATIONS FOR CONSTRUCTION, THE STANDARD PLANS AND APPLICABLE SPECIAL PROVISIONS. ONLY DESIGNS AND MATERIALS APPROVED BY MDOT WILL BE ALLOWED.
8. WHEN BUFFER AREAS ARE ESTABLISHED, THERE SHALL BE NO EQUIPMENT OR MATERIALS STORED OR WORK CONDUCTED IN THE BUFFER AREA.
- 29A. THE TYPE OF REFLECTIVE SHEETING USED FOR THE W20-1a PLAQUE SHALL BE THE SAME AS THE TYPE USED FOR THE PARENT SIGN.

### SIGN SIZES

|                   |             |
|-------------------|-------------|
| DIAMOND WARNING   | - 48" x 48" |
| W20-1a PLAQUE     | - 48" x 36" |
| R2-1 REGULATORY   | - 48" x 60" |
| R5-18c REGULATORY | - 48" x 48" |

NOT TO SCALE

|   |  |              |        |
|---|--|--------------|--------|
| <br>TRAFFIC AND SAFETY<br>MAINTAINING TRAFFIC<br>TYPICAL | TYPICAL TEMPORARY TRAFFIC CONTROL<br>FOR A SHOULDER CLOSURE ON A TWO<br>LANE TWO-WAY ROADWAY<br>NO SPEED REDUCTION |              |        |
|   | DRAWN BY: CON:AE:djf   | OCTOBER 2011 | M0110a |
| CHECKED BY: BMM:CRB   | PLAN DATE:   | 2 OF 2       |        |
| FILE: PW RD/TS/Typicals/Signs/MT NON FWY/M0110a.dgn REV. 10/04/2011   |  |              |        |






PLACE THROUGHOUT WORK AREA AS INDICATED AND AFTER ALL MAJOR CROSSROADS IF PERMANENT SIGNS ARE NOT IN PLACE.

PLACE THIS SIGN ALONG WITH THE ADVANCE WORK ZONE SIGNING AS DEPICTED ON THE APPROPRIATE TYPICAL M0030a-M0080a.


PLACE THROUGHOUT WORK AREA AS INDICATED AND AFTER ALL MAJOR CROSSROADS IF PERMANENT SIGNS ARE NOT IN PLACE.

PLACE THIS SIGN ALONG WITH THE ADVANCE WORK ZONE SIGNING AS DEPICTED ON THE APPROPRIATE TYPICAL M0030a-M0080a.


**KEY**

-  TRAFFIC REGULATOR
-  CHANNELIZING DEVICES
-  LIGHTED ARROW PANEL (CAUTION MODE)
-  TRAFFIC FLOW
-  REFLECTS EXISTING SPEED LIMIT

SIGN = 200 ft± - TYPE B PLUS ADDITIONAL R2-1's THROUGHOUT WORK AREA



NOT TO SCALE

|  |                            |   |                 |
|--|----------------------------|---|-----------------|
| <br>Michigan Department of Transportation<br>TRAFFIC AND SAFETY<br>MAINTAINING TRAFFIC<br>TYPICAL |                            | TYPICAL TEMPORARY TRAFFIC CONTROL FOR<br>A TWO-LANE TWO-WAY ROADWAY WHERE ONE<br>LANE IS CLOSED UTILIZING TRAFFIC<br>REGULATORS, NO SPEED REDUCTION |                 |
| DRAWN BY: CON:AE:djf<br>CHECKED BY: BMM:CRB  | OCTOBER 2011<br>PLAN DATE: | M0140a 29   | SHEET<br>1 OF 2 |
| FILE: PW RD/TS/Typicals/Signs/MT NON Fwy/M0140a.dgn REV. 10/04/2011  |                            |   |                 |


## NOTES

- 1H. D = DISTANCE BETWEEN TRAFFIC CONTROL DEVICES AND LENGTH OF LONGITUDINAL BUFFERS  
SEE **M0020a** FOR "D" VALUES.
2. ALL NON-APPLICABLE SIGNING WITHIN THE CIA SHALL BE MODIFIED TO FIT CONDITIONS, COVERED OR REMOVED.
3. DISTANCES BETWEEN SIGNS, THE VALUES FOR WHICH ARE SHOWN IN TABLE D, ARE APPROXIMATE AND MAY NEED ADJUSTING AS DIRECTED BY THE ENGINEER.
- 3A. THE "WORK ZONE BEGINS" (R5-18c) SIGN SHALL BE USED ONLY IN THE INITIAL SIGNING SEQUENCE IN THE WORK ZONE. SUBSEQUENT SEQUENCES IN THE SAME WORK ZONE SHALL OMIT THIS SIGN AND THE QUANTITIES SHALL BE ADJUSTED APPROPRIATELY.
- 4A. THE MAXIMUM RECOMMENDED DISTANCE(S) BETWEEN CHANNELIZING DEVICES IN THE TAPER AREA(S) SHOULD BE 15 FEET AND SHOULD BE EQUAL IN FEET TO TWICE THE POSTED SPEED IN MILES PER HOUR IN THE PARALLEL AREA(S).
5. FOR OVERNIGHT CLOSURES, TYPE III BARRICADES SHALL BE LIGHTED.
6. WHEN CALLED FOR IN THE FHWA ACCEPTANCE LETTER FOR THE SIGN SYSTEM SELECTED, THE TYPE A WARNING FLASHER, SHOWN ON THE WARNING SIGNS, SHALL BE POSITIONED ON THE SIDE OF THE SIGN NEAREST THE ROADWAY.
7. ALL TEMPORARY SIGNS, TYPE III BARRICADES, THEIR SUPPORT SYSTEMS AND LIGHTING REQUIREMENTS SHALL MEET NCHRP 350 CRASHWORTHLY REQUIREMENTS STIPULATED IN THE CURRENT EDITION OF THE MICHIGAN MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, THE CURRENT EDITION OF THE STANDARD SPECIFICATIONS FOR CONSTRUCTION, THE STANDARD PLANS AND APPLICABLE SPECIAL PROVISIONS. ONLY DESIGNS AND MATERIALS APPROVED BY MDOT WILL BE ALLOWED.
9. ALL TRAFFIC REGULATORS SHALL BE PROPERLY TRAINED AND SUPERVISED.
- 9A. IN ANY OPERATION INVOLVING MORE THAN ONE TRAFFIC REGULATOR, ONE PERSON SHOULD BE DESIGNATED AS HEAD TRAFFIC REGULATOR.
10. ALL TRAFFIC REGULATORS' CONDUCT, THEIR EQUIPMENT, AND TRAFFIC REGULATING PROCEDURES SHALL CONFORM TO THE CURRENT EDITION OF THE MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MMUTCD) AND THE CURRENT EDITION OF THE MDOT HANDBOOK ENTITLED "TRAFFIC REGULATORS INSTRUCTION MANUAL."
11. WHEN TRAFFIC REGULATING IS ALLOWED DURING THE HOURS OF DARKNESS, APPROPRIATE LIGHTING SHALL BE PROVIDED TO SUFFICIENTLY ILLUMINATE THE TRAFFIC REGULATOR'S STATIONS.
- 12E. THE MAXIMUM DISTANCE BETWEEN THE TRAFFIC REGULATORS SHALL BE NO MORE THAN 2 MILES IN LENGTH UNLESS RESTRICTED FURTHER IN THE SPECIAL PROVISIONS FOR MAINTAINING TRAFFIC. ALL SEQUENCES OF MORE THAN 2 MILES IN LENGTH WILL REQUIRE WRITTEN PERMISSION FROM THE ENGINEER BEFORE PROCEEDING.
13. WHEN INTERSECTING ROADS OR SIGNIFICANT TRAFFIC GENERATORS (SHOPPING CENTERS, MOBILE HOME PARKS, ETC.) OCCUR WITHIN THE ONE-LANE TWO-WAY OPERATION, INTERMEDIATE TRAFFIC REGULATORS AND APPROPRIATE SIGNING SHALL BE PLACED AT THESE LOCATIONS.
14. ADDITIONAL SIGNING AND/OR ELONGATED SIGNING SEQUENCES SHOULD BE USED WHEN TRAFFIC VOLUMES ARE SIGNIFICANT ENOUGH TO CREATE BACKUPS BEYOND THE W3-4 SIGNS.
15. THE HAND HELD (PADDLE) SIGNS REQUIRED BY THE MMUTCD TO CONTROL TRAFFIC WILL BE PAID FOR AS PART OF FLAG CONTROL.
- 28E. THE TRAFFIC REGULATORS SHOULD BE POSITIONED AT OR NEAR THE SIDE OF THE ROAD SO THAT THEY ARE SEEN CLEARLY AT A MINIMUM DISTANCE OF 500 FEET. THIS MAY REQUIRE EXTENDING THE BEGINNING OF THE LANE CLOSURE TO OVERCOME VIEWING PROBLEMS CAUSED BY HILLS AND CURVES.

### SIGN SIZES

DIAMOND WARNING - 48" x 48"  
R2-1 REGULATORY - 48" x 60"  
R5-18c REGULATORY - 48" x 48"

NOT TO SCALE

|  |  |        |          |
|--|--|--------|----------|
| <br><b>MDOT</b><br>Michigan Department of Transportation<br>TRAFFIC AND SAFETY<br><b>MAINTAINING TRAFFIC</b><br>TYPICAL | <b>TYPICAL TEMPORARY TRAFFIC CONTROL FOR<br/> A TWO-LANE TWO-WAY ROADWAY WHERE ONE<br/> LANE IS CLOSED UTILIZING TRAFFIC<br/> REGULATORS, NO SPEED REDUCTION</b> |        |          |
| DRAWN BY: CON:AE:djf   | OCTOBER 2011   | M0140a | SHEET 30 |
| CHECKED BY: BMM:CRB  | PLAN DATE:   |        | 2 OF 2   |
| FILE: PW RD/TS/Typicals/Signs/MT NON FWY/M0140a.dgn REV. 10/04/2011  |  |        |          |

## SIGN MATERIAL SELECTION TABLE

| SIGN SIZE                | SIGN MATERIAL TYPE |         |          |
|--------------------------|--------------------|---------|----------|
|                          | TYPE I             | TYPE II | TYPE III |
| ≤ 36" X 36"              |                    | X       | X        |
| >36" X 36" ≤ 96" TO WIDE |                    | X       |          |
| > 96" WIDE TO 144" WIDE  | X                  | X       |          |
| > 144" WIDE              | X                  |         |          |


TYPE I           ALUMINUM EXTRUSION  
 TYPE II          PLYWOOD  
 TYPE III         ALUMINUM SHEET

ROUNDING OF CORNERS IS NOT REQUIRED FOR TYPE I OR II SIGNS.  
 VERTICAL JOINTS ARE NOT PERMITTED.  
 HORIZONTAL JOINTS THROUGH SIGN LEGEND OR SYMBOLS ARE NOT PERMITTED.


## POST SIZE REQUIREMENTS TABLE

| SIGN AREA<br>(ft <sup>2</sup> ) | POST TYPE       |                      |              |
|---------------------------------|-----------------|----------------------|--------------|
|                                 | U-CHANNEL STEEL | SQUARE TUBULAR STEEL | WOOD         |
| ≤ 9                             | 1 - 3 lb/ft*    | 1 - 2" 12 or 14 GA*  | N/A          |
| 9 ≤ 20                          | 2 - 3 lb/ft     | 2 - 2" 12 or 14 GA   | 1 - 4" X 6"* |
| > 20 ≤ 30                       | N/A             | N/A                  | 2 - 4" X 6"  |
| > 30 ≤ 60                       | N/A             | N/A                  | 2 - 6" X 8"  |
| > 60 ≤ 84                       | N/A             | N/A                  | 3 - 6" X 8"  |


\*SIGNS 4 FEET AND GREATER IN WIDTH REQUIRE 2 POSTS.  
 SIGNS GREATER THAN 8 FEET IN WIDTH REQUIRE 2 OR 3 WOOD  
 POSTS DEPENDING ON AREA OF SIGN.  
 A MAXIMUM OF 2 POSTS WITHIN A 7' PATH IS PERMITTED.

|  |  |   |                            |                               |
|--|--|---|----------------------------|-------------------------------|
| <br><br>PREPARED<br>BY<br>DESIGN DIVISION | DEPARTMENT DIRECTOR<br>Kirk T. Steudle<br><br>APPROVED BY: _____<br>DIRECTOR, BUREAU OF FIELD SERVICES | MICHIGAN DEPARTMENT OF TRANSPORTATION<br>BUREAU OF DEVELOPMENT STANDARD PLAN FOR<br><br><b>GROUND DRIVEN SIGN<br/>SUPPORTS FOR TEMP SIGNS</b> |                            |                               |
|  | DRAWN BY: <u>CON/ECH</u><br>CHECKED BY: <u>AUG</u>   | APPROVED BY: _____<br>DIRECTOR, BUREAU OF DEVELOPMENT   | _____<br>F.H.W.A. APPROVAL | <u>11/2/2017</u><br>PLAN DATE |

## 2 POST SIGN SUPPORT SPACING



## 3 POST SIGN SUPPORT SPACING



\* FOR ALL 11' AND 12' LONG SIGNS ON 3 WOOD SUPPORTS, SPREAD POSTS SO AS TO HAVE A 8' MIN. TO 9' MAX. DISTANCE BETWEEN OUTSIDE POSTS.

NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION  
BUREAU OF DEVELOPMENT STANDARD PLAN


F.H.W.A. APPROVAL

11/2/2017  
PLAN DATE


WZD-100-A

SHEET  
2 OF 11


NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.




RURAL



RURAL WITH ADVISORY SPEED PLATE



(CURBED AREAS OR WHERE WALKWAYS ARE PRESENT)



(CURBED AREAS OR WHERE WALKWAYS ARE PRESENT)

BOTTOM HEIGHT AND OFFSET

NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION  
BUREAU OF DEVELOPMENT STANDARD PLAN




F.H.W.A. APPROVAL

11/2/2017  
PLAN DATE

WZD-100-A

SHEET  
3 OF 11

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



WEIGHT = 3 lbs/ft  
 SECT. MOD. X.-X. = 0.31 CUBIC INCHES MIN.


**3 lb. U - CHANNEL STEEL POST**  
 (NO SPLICE)

MOUNT SIGN ON OPEN FACE OF  
 U - CHANNEL STEEL POST

NOT TO SCALE

|  |                   |                        |           |                  |
|--|-------------------|------------------------|-----------|------------------|
| MICHIGAN DEPARTMENT OF TRANSPORTATION<br>BUREAU OF DEVELOPMENT STANDARD PLAN | F.H.W.A. APPROVAL | 11/2/2017<br>PLAN DATE | WZD-100-A | SHEET<br>4 OF 11 |
|--|-------------------|------------------------|-----------|------------------|

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



3 lb. U - CHANNEL STEEL POST  
(WITH SPLICE)


MOUNT SIGN ON OPEN FACE OF  
UPPER U - CHANNEL STEEL POST

NOT TO SCALE

|  |                   |                        |           |                  |
|--|-------------------|------------------------|-----------|------------------|
| MICHIGAN DEPARTMENT OF TRANSPORTATION<br>BUREAU OF DEVELOPMENT STANDARD PLAN | F.H.W.A. APPROVAL | 11/2/2017<br>PLAN DATE | WZD-100-A | SHEET<br>5 OF 11 |
|--|-------------------|------------------------|-----------|------------------|


NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.





SECTION A-A

7/16" SPACER  
 REQUIRED FOR ALL BOLTS  
 O.D. 3/4" MIN., I.D. 3/8" MAX.



NOTES:


1. THE SPACER THICKNESS SHALL BE 1/16" LESS THAN THE GAP BETWEEN THE POST WHEN POSITIONED IN THE UNBOLTED CONFIGURATION.
2. THE EXTERIOR BOLT (CLOSEST TO LAP), SPACER, WASHER, AND NUT SHALL BE INSTALLED IN A PREPUNCHED HOLE 1" TO 2" FROM THE END OF THE LAP.
3. THE INTERIOR BOLT (FARTHEST FROM LAP), SPACER, WASHER, AND NUT SHALL BE INSTALLED IN THE NEXT PREPUNCHED HOLE.
4. THE DRIVEN POST SHALL ALWAYS BE MOUNTED IN FRONT OF THE UPPER POST WITH RESPECT TO THE ADJACENT ONCOMING TRAFFIC, REGARDLESS OF THE DIRECTION THE SIGN IS FACING.
5. THE SPLICE LAP SHALL BE FASTENED BY FOUR-5/16" DIA. GALVANIZED A449 BOLTS (SAE J429 GRADE 5) OR GALVANIZED A325 BOLTS.

3 lb. U - CHANNEL STEEL POST  
 (WITH SPLICE)


NOT TO SCALE

|  |                   |                        |           |                  |
|--|-------------------|------------------------|-----------|------------------|
| MICHIGAN DEPARTMENT OF TRANSPORTATION<br>BUREAU OF DEVELOPMENT STANDARD PLAN | F.H.W.A. APPROVAL | 11/2/2017<br>PLAN DATE | WZD-100-A | SHEET<br>6 OF 11 |
|--|-------------------|------------------------|-----------|------------------|

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



SIGN TO 3 lb. POST CONNECTION



NOTES: (FOR STEEL SIGN REINF' PLATE)

1. MATERIAL: 12 GAUGE CARBON STEEL.
2. TOLERANCE ON ALL DIMENSIONS  $\pm 0.0625"$
3. FINISH-AFTER STAMPING AND PUNCHING, GALVANIZE ACCORDING TO CURRENT SPECIFICATIONS FOR ZINC (HOT GALVANIZE) COATINGS ON PRODUCTS FABRICATED FROM PLATES OR STRIPS

STEEL SIGN REINFORCING PLATE  
REQUIRED FOR TYPE III SIGNS ONLY

3 lb. U - CHANNEL STEEL POST SIGN CONNECTION

NOT TO SCALE


MICHIGAN DEPARTMENT OF TRANSPORTATION  
BUREAU OF DEVELOPMENT STANDARD PLAN

F.H.W.A. APPROVAL


11/2/2017  
PLAN DATE

WZD-100-A

SHEET  
7 OF 11



**WOOD POST BREAKAWAY HOLES/  
 DIRECT EMBEDMENT DETAILS**



**SAW CUT DETAIL  
 (MULTIPLE POST INSTALLATIONS)**

**WOOD POST DETAILS**

NOT TO SCALE


MICHIGAN DEPARTMENT OF TRANSPORTATION  
 BUREAU OF DEVELOPMENT STANDARD PLAN

F.H.W.A. APPROVAL


11/2/2017  
 PLAN DATE

WZD-100-A


SHEET  
 8 OF 11



**TYPE II AND TYPE III SIGNS**



**TOP VIEW  
TYPE I SIGN**



**TYPE I SIGN - ERECTION DETAILS**

**WOOD POST CONNECTIONS**

NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION  
BUREAU OF DEVELOPMENT STANDARD PLAN


F.H.W.A. APPROVAL

11/2/2017  
PLAN DATE

WZD-100-A

SHEET  
9 OF 11

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



SQUARE TUBULAR STEEL POST

NOT TO SCALE

|  |                   |                        |           |                   |
|--|-------------------|------------------------|-----------|-------------------|
| MICHIGAN DEPARTMENT OF TRANSPORTATION<br>BUREAU OF DEVELOPMENT STANDARD PLAN | F.H.W.A. APPROVAL | 11/2/2017<br>PLAN DATE | WZD-100-A | SHEET<br>10 OF 11 |
|--|-------------------|------------------------|-----------|-------------------|

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.


GENERAL NOTES:

1. A MAXIMUM OF TWO POSTS WITHIN A 7 FOOT PATH IS PERMITTED.
2. ALL SIGN POSTS SHALL COMPLY WITH NCHRP 350.
3. ALL POSTS SHALL BE EMBEDDED A MINIMUM OF 42".
4. BRACING OF POST IS NOT PERMITTED.
5. SIGN SHALL BE LEVEL, AND UPRIGHT FOR THE DURATION OF INSTALLATION.
6. ERECT POSTS SO THE SIGN FACE AND SUPPORTS DO NOT VARY FROM PLUMB BY MORE THAN 3/16" IN 3'. PROVIDE A CENTER-TO-CENTER DISTANCE BETWEEN POSTS WITHIN 2 PERCENT OF PLAN DISTANCE.
7. NO MORE THAN ONE SPLICE PER POST, AS SHOWN, WILL BE PERMITTED.
8. POST TYPES SHALL NOT BE MIXED WITHIN A SIGN SUPPORT INSTALLATION.
9. NO VERTICAL JOINTS ARE PERMITTED IN SIGN. NO HORIZONTAL JOINTS THROUGH SIGN LEGEND OR SYMBOLS ARE PERMITTED IN SIGN
10. REMOVE SIGN POSTS AND/OR POST STUBS IN THEIR ENTIRETY WHEN NO LONGER REQUIRED.
11. ALL LABOR, MATERIALS, AND EQUIPMENT, INCLUDING TEMPORARY SUPPORTS REQUIRED TO INSTALL, MAINTAIN, RELOCATE, AND/OR REMOVE THE TEMPORARY SIGN, INCLUDING SUPPORTS, ARE CONSIDERED TO BE INCLUDED IN THE COST OF THE TEMPORARY SIGN.
12. SAW CUTS IN WOOD POSTS ARE TO BE PARALLEL TO THE BOTTOM OF THE SIGN.
13. POSTS SHALL NOT EXTEND MORE THAN 4" ABOVE TOP OF SIGN.
14. TEMPORARY WOOD SUPPORTS DO NOT REQUIRE PRESERVATIVE TREATMENT.

NOT TO SCALE

|  |                   |                        |           |                   |
|--|-------------------|------------------------|-----------|-------------------|
| MICHIGAN DEPARTMENT OF TRANSPORTATION<br>BUREAU OF DEVELOPMENT STANDARD PLAN | F.H.W.A. APPROVAL | 11/2/2017<br>PLAN DATE | WZD-100-A | SHEET<br>11 OF 11 |
|--|-------------------|------------------------|-----------|-------------------|


NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



FRONT ELEVATION

SIDE VIEW


PERFORATED SQUARE STEEL TUBE OPTION



FRONT ELEVATION

SIDE VIEW

ANGLE IRON OPTION



LEFT DIRECTIONAL

BI-DIRECTIONAL

RIGHT DIRECTIONAL

CLOSURES

BARRICADE RAIL SHEETING OPTIONS  
TYPE III BARRICADES

Other Type III Barricades meeting current NCHRP crash worthy criteria can be found on the FHWA Safety website at [http://safety.fhwa.dot.gov/roadway\\_dept/road\\_hardware/wzd.htm](http://safety.fhwa.dot.gov/roadway_dept/road_hardware/wzd.htm)



PREPARED BY  
DESIGN DIVISION

DRAWN BY: ECH

CHECKED BY: MWB

DEPARTMENT DIRECTOR  
Kirk T. Steudle

APPROVED BY: \_\_\_\_\_  
DIRECTOR, BUREAU OF FIELD SERVICES  
ENGINEER OF DEVELOPMENT

APPROVED BY: \_\_\_\_\_  
(SPECIAL DETAIL)  
DIRECTOR, BUREAU OF DEVELOPMENT

MICHIGAN DEPARTMENT OF TRANSPORTATION  
BUREAU OF DEVELOPMENT STANDARD PLAN FOR


Temporary  
Traffic Control Devices

F.H.W.A. APPROVAL

1/18/11  
PLAN DATE



WZD-125-E

SHEET  
1 OF 3



**TEMPORARY SIGN SUPPORT**

(WARNING LIGHT PLACED ON SIDE CLOSEST TO TRAFFIC)  
 \* SIGN STAND IS BALLASTED WITH FOUR OR MORE 35 LB SANDBAGS. A MINIMUM OF ONE ON EACH END.  
 UPRIGHTS SHALL NOT EXTEND ABOVE THE SIGN PANEL.



Other temporary sign supports meeting current NCHRP crash worthy criteria can be found on the FHWA Safety website at [http://safety.fhwa.dot.gov/roadway\\_dept/road\\_hardware/wzd.htm](http://safety.fhwa.dot.gov/roadway_dept/road_hardware/wzd.htm)

NOT TO SCALE


|  |                                     |                      |           |                 |
|--|-------------------------------------|----------------------|-----------|-----------------|
| MICHIGAN DEPARTMENT OF TRANSPORTATION<br>BUREAU OF DEVELOPMENT STANDARD PLAN | SPECIAL DETAIL<br>F.H.W.A. APPROVAL | 1/18/11<br>PLAN DATE | WZD-125-E | SHEET<br>2 OF 3 |
|--|-------------------------------------|----------------------|-----------|-----------------|

NOTE: THE ORIGINAL SIGNED COPY IS KEPT ON FILE AT THE MICHIGAN DEPARTMENT OF TRANSPORTATION.



- PLASTIC DRUM
- ▲▲▲ PROPOSED TYPE III BARRICADE
- △△△ EXISTING TYPE III BARRICADE

**SYMBOLS TO BE USED ON PLANS**



- REFLECTORIZED ORANGE
- REFLECTORIZED WHITE
- NON REFLECTORIZED ORANGE

**NOTE:**  
 DRUMS SHALL HAVE AT LEAST 4 HORIZONTAL REFLECTORIZED STRIPES (2 ORANGE AND 2 WHITE) OF 6" UNIFORM WIDTH, ALTERNATING IN COLOR WITH THE TOPMOST REFLECTORIZED STRIPE BEING ORANGE. NON REFLECTORIZED SPACES BETWEEN THE HORIZONTAL REFLECTORIZED ORANGE AND WHITE STRIPES SHALL BE ORANGE IN COLOR AND EQUAL IN WIDTH.

**PLASTIC DRUM**

**NOTES:**

2" PERFORATED SQUARE STEEL TUBES MAY BE USED TO FABRICATE THE HORIZONTAL BASE OF THE TYPE III BARRICADE.

WARNING LIGHTS SHALL BE PLACED ACCORDING TO THE CURRENT STANDARD SPECIFICATIONS FOR CONSTRUCTION AND ALL OTHER PROVISIONS IN THE CONTRACT ON TYPE III BARRICADES.

SEE ROAD STANDARD PLANS R-113-SERIES FOR TEMPORARY CROSSOVERS FOR DIVIDED ROADWAY, AND R-126-SERIES FOR TYPICAL LOCATION AND SPACING OF PLASTIC DRUMS FOR PLACEMENT OF TEMPORARY CONCRETE BARRIER.

SIGNS, BARRICADES, AND PLASTIC DRUMS SHALL BE FACED WITH PRESSURE-SENSITIVE REFLECTIVE SHEETING ACCORDING TO THE CURRENT STANDARD SPECIFICATIONS FOR CONSTRUCTION.

SANDBAGS SHALL BE USED WHEN SUPPLEMENTAL WEIGHTS ARE REQUIRED TO ACHIEVE STABILITY OF THE BARRICADE. THE SANDBAGS SHALL BE PLACED SO THEY WILL NOT COVER OR OBSTRUCT ANY REFLECTIVE PORTION OF THE TRAFFIC CONTROL DEVICE.

NOT TO SCALE

MICHIGAN DEPARTMENT OF TRANSPORTATION  
 BUREAU OF DEVELOPMENT STANDARD PLAN

(SPECIAL DETAIL)  
 F.H.W.A. APPROVAL

1/18/11  
 PLAN DATE

WZD-125-E

SHEET  
 344  
 OF 3

WASHTENAW COUNTY ROAD COMMISSION

SPECIAL PROVISION  
FOR  
**PROJECT DOCUMENTATION SUBMITTAL COMPLIANCE**

WCRC:KRJ

1 of 1

10-18-2016

**a. Description.** This work consists of submitting all project documentation to the Engineer within 45 calendar days from the final acceptance of the punch list work and provides for a negative adjustment for failure to submit final project documentation. The time requirement may be extended as requested by the Contractor and approved by the Engineer for claim or dispute issues. The Contractor will be assessed \$250.00 for each calendar day or portion of a calendar day that project documentation is not submitted after the 45 day period. Penalties will continue until all project documentation has been submitted by the Contractor and approved by the Engineer.

**b. Materials.** None specified.

**c. Construction.** None specified.

**d. Measurement and Payment.** The Engineer will assess a negative adjustment to the contract based on the number of calendar days or partial calendar days the Contractor fails to submit final project documentation, including but not limited to MDOT forms (1386, 2124, etc.), certifications, certified payrolls, and material source lists (MSLs).

WASHTENAW COUNTY ROAD COMMISSION

SPECIAL PROVISION  
FOR  
**WINGWALL REPAIR**

2018Guardrail:BMS

1 of 2

5/2018

**a. Description.** This work consists of repairing the existing wingwalls on Stony Creek Rd, Platt Rd, Pleasant Lake Rd and Sager Rd for upgrading guardrails. This work consists of placing bags of Ready-Mix Concrete along and adjacent to the existing wingwalls, to a height sufficient enough to stabilize the guardrail posts.

**b. Materials.** The materials specified in Sections 706, 901, and 905 of the Michigan Department of Transportation (MDOT) 2012 Standard Specifications for Construction apply unless modified by this special provision or otherwise directed by the Engineer.

1. 60 lb. Ready Mix Concrete bags, with a minimum compressive strength of 4000 PSI.
2. No. 4 Steel Reinforcing bar (minimum size).
3. Non-Woven Geotextile Separator per 12SP-910A-01
4. Embankment material for backfilling of repaired wingwalls.

**c. Construction.** Construction methods shall be in accordance to Sections 206 and 706 of the MDOT 2012 Standard Specifications for Construction. It may be necessary, as directed by the Engineer, to place materials by hand.

The Contractor shall stack Ready Mix Concrete bags in an overlapping, locking pattern from the existing wingwalls to a height necessary to provide a suitable base for guardrail posts. No. 4 or larger Steel Reinforcing bar shall then be driven into the bags to aide in lateral stabilization.

Backfill the structure with suitable embankment material or granular material CI II, in accordance with Section 206 of the MDOT 2012 Standard Specifications for Construction, to provide a stable earth surface for the installation of guardrail posts.

**d. Measurement and Payment.** The completed work as described will be paid for at the contract unit price for the following contract item (pay item):

| <b>Pay Item</b>      | <b>Pay Unit</b> |
|----------------------|-----------------|
| Wingwall Repair..... | Square Foot     |

All materials, labor and equipment required to install **Wingwall Repair**, which includes subgrade undercutting and earth excavation if necessary, Ready Mix concrete bags, No. 4 or larger steel reinforcing bar, non-woven geotextile separator, and embankment material for backfilling structure, shall be included in the contract unit price bid for **Wingwall Repair**.



SPECIAL PROVISION  
FOR  
Wingwall Repair  
2 of 2

2018GUARDRAIL:BMS

5/2018

WINGWALL REPAIR  
SPECIAL PROVISION DETAIL

QUANTITY WILL BE MEASURED AND PAID IN SFT OF THE SLOPE FACE IN PLACE.



555 N. ZEEB RD.  
ANN ARBOR, MI 48103  
734-761-1500  
FAX 734-761-3239

| ACTIVITY    | INITIALS | DATE     |
|-------------|----------|----------|
| DRAWN BY    | EY       | OCT 2015 |
| CHECKED BY  | BMS      | OCT 2015 |
| APPROVED BY | BMS      | OCT 2015 |

SCALES  
HORIZONTAL: NONE  
VERTICAL: NONE

29 OCT 2015

2018 COUNTYWIDE  
GUARDRAIL PROJECT  
SPECIAL PROVISION

WASHTENAW COUNTY ROAD COMMISSION  
SPECIAL PROVISION  
FOR  
**GUARDRAIL, REM, RAILS AND BRIDGE POSTS**

2018Guardrail:BMS

1 of 1

05/2018

**a. Description.** Guardrail, Rem, Rails and Bridge Posts shall be performed as shown in the plans, directed by the Engineer, and as specified in Section 204 of the Michigan Department of Transportation (MDOT) 2012 Standard Specifications for Construction.

**b. Materials.** The materials shall meet the requirements specified in Section 204 of the MDOT 2012 Standard Specifications for Construction.

**c. Construction.** Remove rails and bridge posts including cutting attachment bolts flush with beam when necessary while preserving the integrity of the bridge, as shown on plans and in accordance with Section 204 of the MDOT 2012 Standard Specifications for Construction.

**d. Measurement and Payment.** The completed work for Guardrail, Rem, Rails and Bridge Posts will be paid for at the contract unit price for the following:

| <b>Pay Item</b>                             | <b>Pay Unit</b> |
|---|-----------------|
| Guardrail, Rem, Rails and Bridge Posts..... | Foot            |

**Guardrail, Rem, Rails and Bridge Posts** will be measured in place and paid for at the contract unit price per foot, which price shall be payment in full for all labor, materials and equipment needed to accomplish this work.

WASHTENAW COUNTY ROAD COMMISSION  
 SPECIAL PROVISION  
 FOR  
**GUARDRAIL, TYPE B, 8 FT POSTS, MODIFIED**

2018Guardrail:BMS

1 of 1

5/2018

**a. Description.** Guardrail, Type B, 8 Ft Posts, Modified shall be constructed as shown in the plans, as specified in Section 807 of the Michigan Department of Transportation (MDOT) 2012 Standard Specifications for Construction and applicable MDOT Standard Plans with the following exceptions and additions:

**b. Materials.** For this installation 8 Ft steel posts shall be used. The materials for Guardrail, Type B, 8 Ft Posts, Modified shall meet the requirements specified in Section 807 of the MDOT 2012 Standard Specifications for Construction.

**c. Construction.** Install the guardrail per plan, in accordance with Section 807 of the MDOT 2012 Standard Specifications for Construction and the following MDOT Special Details:

R-60-Series

**d. Measurement and Payment.** The completed work as described will be paid for at the contract unit price for the following:

| <b>Pay Item</b>                              | <b>Pay Unit</b> |
|--|-----------------|
| Guardrail, Type B, 8 Ft Posts, Modified..... | Foot            |

**Guardrail, Type B, 8 Ft Posts, Modified** will be measured in place by the unit foot and paid for at the contract unit price per foot, which price shall be payment in full for all labor, materials, and equipment needed to accomplish this work.

WASHTENAW COUNTY ROAD COMMISSION

SPECIAL PROVISION  
FOR  
**RETAINING WALL, MODIFIED**

2018Guardrail:BMS

1 of 1

5/2018

**a. Description.** Retaining Wall, Modified shall be constructed as shown in the plans, directed by the Engineer, as specified in Section 807 of the Michigan Department of Transportation (MDOT) 2012 Standard Specifications for Construction and applicable MDOT Standard Plans with the following exceptions and additions:

**b. Materials.** The materials for Retaining Wall, Modified shall meet the requirements specified in Section 807 of the MDOT 2012 Standard Specifications for Construction.

1. W6x9x10' steel posts;
2. Treated wallboards or used guardrails;
3. Non-woven geotextile separator per 12SP-910A-01;

**c. Construction.** Install Retaining Wall, Modified per plan, in accordance with Section 807 of the MDOT 2012 Standard Specifications for Construction.

**d. Measurement and Payment.** The completed work as described will be paid for at the contract unit price for the following contract item (pay item):

| <b>Pay Item</b>                | <b>Pay Unit</b> |
|--------------------------------|-----------------|
| Retaining Wall, Modified ..... | Foot            |

Retaining Wall, Modified will be measured in place and paid for at the contract unit price per foot, which price shall be payment in full for all labor, materials and equipment needed to accomplish this work.

WASHTENAW COUNTY ROAD COMMISSION  
SPECIAL PROVISION  
FOR  
**GUARDRAIL, THRIE BEAM BACKED, DETAIL B**

2018Guardrail:BMS

1 of 1

5/2018

**a. Description.** Guardrail, Thrie Beam Backed, Detail B shall be constructed as shown in the plans, directed by the Engineer, as specified in Section 807 of the Michigan Department of Transportation (MDOT) 2012 Standard Specifications for Construction and applicable MDOT Standard Plans with the following exceptions and additions:

**b. Materials.** The materials for Guardrail, Thrie Beam Backed, Detail B shall meet the requirements specified in Section 807 of the MDOT 2012 Standard Specifications for Construction.

**c. Construction.** Install new steel guardrail posts on bridge and attach the thrie beam with w-beam backed guardrail to the new steel guardrail posts per plans, in accordance with Section 807 of the MDOT 2012 Standard Specifications for Construction and the following MDOT Standard Plans:

R-72-Series

**d. Measurement and Payment.** The completed work for Guardrail, Thrie Beam Backed, Detail B will be paid for at the contract unit price for the following:

| <b>Pay Item</b>                             | <b>Pay Unit</b> |
|---|-----------------|
| Guardrail, Thrie Beam Backed, Detail B..... | Each            |

New steel guardrail posts shall be included as part of Guardrail, Thrie Beam Backed, Detail B pay item and will not be paid separately.

**Guardrail, Thrie Beam Backed, Detail B** will be measured in place and paid for at the contract unit price per each, which price shall be payment in full for all labor, materials and equipment needed to accomplish this work.



WASHTENAW COUNTY ROAD COMMISSION

SPECIAL PROVISION  
FOR  
**MODIFIED GUARDRAIL DEPARTING TERMINAL, TYPE B, 20 FT RADIUS**

2018Guardrail:BMS

1 of 1

5 /18

**a. Description.** Construct guardrail bridge anchorages and departing terminals according to the details shown on the plans and conform to the Michigan Department of Transportation (MDOT) 2012 Standard Specifications for Construction, except as modified herein.

**b. Materials.** Materials used to construct the guardrail bridge anchorage and departing terminals shall meet the Section 807 of the MDOT 2012 Standard Specifications for Construction.

**c. Construction.** Install the guardrail departing terminals in accordance with Section 807 of the MDOT 2012 Standard Specifications for Construction and the MDOT Standard Plan R-66 Series and Road Special Detail 21 except as modified in the plans. Install guardrail terminals to the radii specified on the plans.

**d. Measurement and Payment.** The completed work as measured for this work will be paid for at the contract unit price for the following Contract Items (Pay Items).

| <b>Pay Item</b>  | <b>Pay Unit</b> |
|--|-----------------|
| Modified Guardrail Departing Terminal, Type B, 20 Ft Radius..... | Each            |

The guardrail pay items will be measured by Each, which will be payment in full for all labor, equipment and materials needed to accomplish this work at the location shown on the plans.

Payment for **Modified Guardrail Departing Terminal, Type B, 20 Ft Radius** includes the cost of furnishing and placing the modified guardrail bridge anchorage/terminal, guardrail posts, blocks and all hardware.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**PROGRESS SCHEDULE**

CFS:JJG

1 of 1

APPR:MB:LFS:01-09-18  
FHWA:APPR:03-01-18

**Delete the definition for Progress Schedule in subsection 101.03, on page 12 of the Standard Specifications for Construction, in its entirety and replace with the following:**

**Progress Schedule.** A sequential listing of all the controlling operations and the estimated time the operations will remain controlling. The progress schedule is submitted by the Contractor after award and prior to starting work and is reviewed and approved by the Department. When approved, the progress schedule, or updated progress schedule, will become part of the contract.

**Delete subsection 102.14, on page 22 of the Standard Specifications for Construction, in its entirety.**

**Delete the first sentence in the second paragraph of subsection 108.05, on page 74 of the Standard Specifications for Construction, in its entirety and replace with the following.**

Submit a critical path method (CPM) schedule if required in the contract documents. Submittal of a progress schedule will not be required as the CPM schedule will replace the progress schedule.

**Add the following paragraphs directly below the first paragraph of subsection 108.05.A.1, on page 74 of the Standard Specifications for Construction.**

The progress schedule is to be submitted by the Contractor to the Engineer within 7 calendar days of award and prior to starting work.

The Engineer will provide documented approval, comments, or rejection within 7 calendar days of receipt of the Contractor's submittal, resubmittal, or responses.

The Contractor must resolve all responses within 7 calendar days of receipt of any Engineer requests or rejections.

If the progress schedule is not approved within 30 calendar days of contract award, the Engineer may withhold all or part of contract payments until the progress schedule is approved.

**Delete the last sentence in the first paragraph of subsection 108.05.A.2, on page 74 of the Standard Specifications for Construction in its entirety.**

MICHIGAN  
DEPARTMENT OF TRANSPORTATION  
  
SPECIAL PROVISION  
FOR  
**CONTRACTOR PERFORMANCE EVALUATIONS**

CFS:MB

1 of 2

APPR:JGG:DBP:06-07-17  
FHWA:APPR:06-07-17

**a. Description.** Project management staff will evaluate the Contractor's performance on this project and the evaluation may be used as a basis for modifying the prequalification ratings of the Contractor. An evaluation may be issued during the course of a project (interim) and will be issued after completion of a project (final). The criteria used for the evaluation will be provided by the Engineer upon written request at the preconstruction meeting or found on the MDOT web site. Any action to modify the Contractor's prequalification ratings will be taken in accordance with the duly promulgated prequalification rules.

If an interim contractor performance evaluation is issued and regardless of whether the Contractor requests a meeting to discuss a Contractor Performance Evaluation, project management staff may require the Contractor to submit a performance improvement plan to address needs identified in the Contractor Performance Evaluation and to attend a meeting to discuss the improvement plan. After the meeting is held, the project management staff may approve the plan or require changes to the plan. Resubmit the plan if changes are required. Performance improvement plans must be implemented per the time frame in the plan as approved by the Engineer. If the Contractor does not implement the plan as approved, MDOT will consider the Contractor to be in non-compliance and will take action as described under section c of this special provision.

Within 21 days of the receipt of a Contractor Performance Evaluation, the Contractor may make a written request to meet with project management staff to review the evaluation. As a result of this meeting, the evaluation may be left unchanged or revised as deemed appropriate by the Engineer. The Engineer will then give the Contractor written notice with the final Contractor Performance Evaluation. If the meeting is not requested within the 21-day period, the original evaluation becomes the final and will not be subject to later contest or appeal.

**b. Appeals.**

1. Appeal of Evaluation. Within 14 days after the date a performance evaluation becomes final and is received by a Contractor, they may file a written appeal of any rating of seven or below to the Engineer. The written appeal must contain documentation supporting the Contractor's position that the rating is not warranted. The appeal will be considered by a Contractor Performance Evaluation Appeal Panel. If no appeal is filed within the 14-day period, the evaluation becomes final and will not be subject to later contest or appeal. Interim Contractor Performance Evaluations cannot be appealed.

2. Appeal of Performance Improvement Plan. Within 14 days after the date that a performance improvement plan is approved and sent to the Contractor, the Contractor may file a written appeal of that plan to the Engineer and request to appear before a Performance Evaluation Appeal Panel. Documentation must include the reasons for the appeal. If a timely

written appeal is not filed, the performance improvement plan becomes final and will not be subject to later contest or appeal.

An appeal filed by a Contractor will be considered by a Contractor Performance Evaluation Appeal Panel. The panel will be composed of three licensed professional Engineers from the Department (following the format of a Central Office Review Panel) who were not directly involved in the management of the project. This panel will review appeals on all Contractor Performance Evaluations for this project. The Contractor and the Engineer will be required to submit supporting documentation relevant to the appeal and will attend a formal appeal hearing. Upon concluding its review, the panel will confirm or modify the Contractor Performance Evaluation. The panel will, within 30 days, send the Contractor and Engineer written notice of its decision along with a copy of the modified Contractor Performance Evaluation if applicable. The original or modified Contractor Performance Evaluation is final and constitutes the Department's decision; it is not subject to further contest or appeal.

**c. Non-Compliance.** If a Contractor fails to honor a request by project management staff to submit a performance improvement plan or to meet to discuss it, or if a Contractor fails to carry out an approved performance improvement plan, that failure may be used as a basis for modifying the prequalification ratings of the Contractor. Any action to modify the Contractor's prequalification ratings will be taken in accordance with the duly promulgated prequalification rules.

**d. Subcontractors.** For purposes of this special provision, the word "Contractor" includes subcontractors. Project management staff will evaluate the performance of subcontractors in accordance with this special provision.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**LOW BID WITHDRAWAL PRIOR TO CONTRACT AWARD**

CSD:JDM

1 of 1

APPR:JJG:DBP:07-02-13

FHWA:APPR:07-10-13

**Add the following sentence to the end of the last paragraph in subsection 102.17, on page 24 of the Standard Specifications for Construction:**

A determined low bidder whose bid is withdrawn prior to contract award cannot participate as a subcontractor, supplier, or trucker on the project.

**Add the following sentence to the end of the fifth paragraph in subsection 108.01. on page 72 of the Standard Specifications for Construction:**

The Contractor may not hire, a determined low bidder on a project who has withdrawn a bid prior to award, as a subcontractor, supplier, or trucker on the same project.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**DEBRIS OR MATERIALS IN TRAFFIC LANES**

CFS:BRZ

1 of 1

APPR:EMB:DAJ:01-10-08  
FHWA:APPR:06-01-11

**Delete Subsection 104.07.B.2 on page 36 of the Standard Specifications for Construction, in its entirety and replace it with the following:**

- 2. Construction Safety Program.** Before beginning work on the project, the Contractor must submit a written "Construction Safety Program" that outlines the plan and procedures for preventing and mitigating accidents and fires on the project and meeting all health and safety requirements of the contract. Also in the program include provisions for meeting the requirements of subsection 812.03 and details for the materials and equipment that will be used to prevent construction related debris or materials from entering the open lanes of traffic and what actions, including traffic control measures, will be taken to immediately and safely remove the debris or material from the roadway. The Contractor must meet with the Engineer to discuss the "Construction Safety Program" and to develop mutual understandings to govern the administration and enforcement of the program.

**Replace the second sentence in the first paragraph of Subsection 104.07.C.3 on page 37 of the Standard Specifications for Construction with the following:**

The Contractor is responsible, at the Contractor's expense, to provide the necessary materials and equipment to prevent construction related debris or materials from entering the open lanes of traffic. This includes protection of traffic controls, removal of spilled materials or debris from the roadbed or drainage courses, and repair of damaged facilities necessary for public travel and safety.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**HIGH VISIBILITY CLOTHING**

SSA:JDG

1 of 1

APPR:MWB:CRB:06-18-14  
FHWA:APPR:06-27-14

**Add the following, to the end, of subsection 104.07.B, Safety and Health Requirements, on page 36 of the Standard Specification for Construction:**

4. **Worker Visibility.** Effective November 24, 2008, all workers within the right-of-way who are exposed to traffic or to construction equipment within the work area, must wear high visibility clothing.

High visibility clothing or high visibility safety apparel is personal protective safety clothing that is intended to provide conspicuity during both daytime and nighttime usage. High Visibility safety apparel must meet the Performance Class 2 or 3 requirements of the American National Standards Institute/International Safety Equipment Association (ANSI/ISEA) 107-2004 for High-Visibility Safety Apparel and subsequent revisions thereof.

Costs incurred to comply with this requirement will be the responsibility of the Contractor.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**SOURCE OF STEEL AND IRON (BUY AMERICA)**

CFS:JJG

1 of 3

APPR:RJC:DBP:01-28-16  
FHWA:APPR:01-31-16

**Delete subsection 105.10, on page 53 of the 2012 Standard Specifications for Construction, in its entirety and replace with the following:**

**105.10. Source of Steel and Iron.** Provide steel and iron materials and products for permanent incorporation into the work that were produced only in the United States per Title 23 of the Federal Code of Regulations (CFR) Section 635.410, Buy America Requirements.

All steel and iron products and manufacturing processes of the steel and iron material in a product, including but not limited to the following steps; smelting, melting, rolling, extruding, machining, bending, grinding, drilling, welding, galvanizing, and coating, must occur within the United States.

Examples of products that are subject to Buy America coverage include, but are not limited to, the following:

- A. Steel or iron products used in pavements, bridges, tunnels or other structures, which include, but are not limited to, the following: fabricated structural steel, reinforcing steel, piling, high strength bolts, anchor bolts, dowel bars, permanently incorporated sheet piling, bridge bearings, cable wire/strand, pre-stressing/post-tensioning wire, motor/machinery brakes and other equipment for moveable structures.
- B. Guardrail, guardrail posts, end sections, terminals, cable guardrail.
- C. Steel fencing material, fence posts.
- D. Steel or iron pipe, conduit, grates, manhole covers, risers.
- E. Mast arms, poles, standards, trusses, supporting structural members for signs, luminaires, or traffic control systems.
- F. Steel or iron components of precast concrete products, such as reinforcing steel, wire mesh and pre-stressing or post-tensioning strands or cables.

Provide step certification for all steel and iron related pay items, materials, products, and components as specified on the Department website. The Department will maintain a list of these pay items, materials, products, and/or components on the following website.

[http://www.michigan.gov/mdot/0,1607,7-151-9622\\_11044\\_11367---,00.html](http://www.michigan.gov/mdot/0,1607,7-151-9622_11044_11367---,00.html)



Step certification is defined as the certification by the respective manufacturer or fabricator for their specific process (step) that the product, material, or component was fabricated, manufactured, and/or processed in the United States. The step certification documentation for these pre-defined pay items, materials, products, and/or components is to be submitted to the Engineer in a package covering each step prior to delivery or concurrent with material delivery on-site. Approved certification is required prior to incorporation of the materials into the project.

Buy America certification documentation for products and materials designated as fully compliant with the Buy America requirements on the Qualified Products List (QPL), Approved Manufacturers, and Tested Stock Suppliers Lists will be maintained by the MDOT Construction Field Services (CFS) Division. Buy America certification for these fully compliant items does not need to be submitted by the Contractor, but a bill of lading, product label, or shipping record to document that the products are from the respective source is to be provided to the Engineer. Buy America certification documentation for items that are partially compliant will be required to be submitted prior to delivery or concurrent with material delivery and prior to incorporation, noting the value of foreign steel/iron. The use of the Department maintained Buy America lists and notations does not relieve the Contractor from responsibility of ensuring Buy America compliance. The Contractor is ultimately responsible for Buy America compliance.

The Buy America lists maintained by the Department are solely for the benefit of the Department and may not be relied upon by the Contractor. The Contractor is solely responsible for the Buy America requirements for steel and iron as set forth in the CFR.

The above requirements do not preclude a minimal use of foreign steel and iron, provided the total invoice cost of foreign material permanently incorporated into the project does not exceed 0.1 percent of the total contract amount or \$2,500 whichever is greater. The Department defines the total invoice cost as the total value of the foreign steel and iron materials delivered to the project. The Department defines the total contract amount to be the total of the contract unit prices for items of road work and bridge work, any adjustments as provided for in the contract, and any assessment of incentive, disincentive or liquidated damages as provided for in the contract.

MDOT/Consultant fabrication facility inspectors are not responsible for approving the incorporation of foreign steel/iron prior to fabrication. It is the responsibility of the fabricator to notify and coordinate with the Contractor for all potential inclusion of foreign steel/iron in fabricated products.

For each item subject to meeting Buy America requirements, that doesn't fully meet Buy America requirements, the following documentation must be provided by the Contractor to verify the foreign steel value. This documentation is to be placed in the project files to ensure that the threshold is not exceeded:

- Pay Item,
- Description of associated foreign steel/iron material, product, or component,
- Cost of associated foreign steel/iron material, product or component, and
- Cumulative list of all non-compliant Buy America items with the total dollar amount.

The minimal use of foreign steel/iron under the minimal usage amount will be approved by the Engineer. The use of foreign steel/iron under the minimal usage amount does not

need to be approved by the FHWA. This amount is not considered a waiver to the Buy America requirements. The Contractor must ensure that the minimal usage amount is not exceeded.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**OPEN TO TRAFFIC**

CFS:JJG

1 of 1

APPR:MB:DBP:07-07-17  
FHWA:APPR:07-10-17

**Delete subsection 107.21, on page 69 of the Standard Specifications for Construction, in its entirety and replace with the following:**

**107.21. Open to Traffic.** The Contractor must not open the project or sections thereof to traffic until approved by the Engineer. Whenever the project or section thereof is in a condition suitable for traffic, the Engineer will determine if it is approved for traffic before project completion and the Contractor must open the project or section thereof to traffic as directed by the Engineer. To determine whether the project or section thereof is approved for traffic, the Engineer will verify that the surfacing material, shoulders, guardrails, signs, and other appurtenances are completed as required by the contract. The Engineer's approval of the project or section thereof for traffic does not constitute partial or final acceptance of the project or any part of it, or a waiver of any provision of the contract. The Contractor is not responsible for the costs of maintaining the section of the project opened for traffic.

If the Engineer approves the entire project or any section of it for traffic and the Contractor opens it to traffic before final acceptance and final payment, the Contractor must perform the remainder of the work in a manner that causes the least obstruction to traffic. The Contractor must make provisions for the safety of traffic as required by the contract. Legal weight restrictions, established by 1949 PA 300 as amended, local ordinances, or legal posting, apply to sections of the project opened to traffic.

Before the seasonal suspension, the Engineer will determine the work the Contractor must complete to bring the project to an acceptable condition for traffic and winter maintenance, including necessary traffic and erosion control measures. Until the Contractor completes this work, the Engineer will not designate the project as approved for traffic. On sections of the project opened to traffic, the Contractor must correct damage due to defective materials, to faulty workmanship, to operations of the Contractor, and to natural causes (except as provided in subsection 107.11 of the Standard Specifications for Construction), at no additional cost to the Department.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION  
  
SPECIAL PROVISION  
FOR  
**TIMELY PROJECT COMPLETION AND CLOSEOUT**

DET:VJ

1 of 2

APPR:KB:DBP:05-29-07  
FHWA:APPR:06-01-11

**a. Description.** This special provision establishes the required procedures and schedule for the completion of “deficient” work and timely close out of the project. The Contractor and Engineer should coordinate the evaluation of completed work and correct any defects during the general progress of the work. This special provision does not revise any schedule constraints established in the contract documents.

**b. Procedure.**

1. The Contractor must submit the written notification that the work is complete in accordance with subsection 109.07 of the Standard Specifications for Construction. The Engineer and Contractor will conduct the final inspection within the project closures or as agreed with the Contractor to mitigate the Contractor costs to conduct the inspection(s). The Engineer will provide the Contractor the preliminary defects (punch) list within 15 days of receipt of the Contractor’s written notification that work is complete.

2. The Contractor must complete the preliminary defects list work and notify the Engineer in writing that all the work has been completed, within 30 days of receiving the preliminary defects list. The Engineer may grant an extension of this time period if the Contractor provides justification.

The Engineer will inspect the completed work and provide the Contractor the final defects list within 10 days of receipt of the written notification from the Contractor that all preliminary defects list work has been completed. Failure to complete all preliminary defects list work within the schedule described above will result in the Contractor being assessed 50 percent of the liquidated damages in accordance with the Schedule of Liquidated Damages for a maximum of 30 calendar days.

Failure to complete all incomplete preliminary defects list work within the maximum liquidated damage period of 30 calendar days may result in the Engineer placing the Contractor in default in accordance with subsection 108.11 of the Standard Specifications for Construction.

3. The Contractor must complete all final defects list work and notify the Engineer in writing that all the work has been completed, within 30 days of receiving the final defects list. The Engineer may grant an extension of this time period if justification is provided by the Contractor. The Engineer will provide written documentation of the status of the final defects list work within 10 days of receipt of the Contractor’s written notification of completion of the final defect list work.

Failure to complete all final defects list work within the schedule described above will result in the Contractor being assessed 50 percent of the liquidated damages in accordance with the

Schedule of Liquidated Damages and for a maximum of 30 calendar days. Failure to complete all incomplete final defects list work within the maximum liquidated damage period of 30 calendar days may result in the Engineer placing the Contractor in default in accordance with subsection 108.11 of the Standard Specifications for Construction.

4. After the work is accepted, the Engineer will have 30 days to meet with the Contractor and finalize quantities for all pay items. Within 30 days of the meeting, the Engineer will then provide a list of final quantities to the Contractor. The Contractor will have 30 days from receipt of the final quantities list to provide a written response to the agreement or disagreement to the final quantities. If the Contractor fails to provide the timely written response, the Engineer will proceed with preparing the final estimate in accordance with subsection 109.07 of the Standard Specifications for Construction.

The Liquidated Damage provisions in this special provision and any other applicable provisions of the contract are cumulative so multiple assessments may be made.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**SCHEDULE OF LIQUIDATED DAMAGES FOR OVERSIGHT**

CFS:BED

1 of 1

APPR:MB:JJG: 07-15-16  
FHWA:APPR:07-29-16

**Delete Table 108-1 in subsection 108.10.C.1, on page 83 of the Standard Specifications for Construction, in its entirety and replace with the following.**

| <b>Table 108-1</b>                                  |                             |                                    |
|---|-----------------------------|------------------------------------|
| <b>Schedule of Liquidated Damages for Oversight</b> |                             |                                    |
| <b>Original Contract Amount</b>                     |                             | <b>Amount per Calendar Day, \$</b> |
| <b>From more than, \$</b>                           | <b>To and including, \$</b> |                                    |
| 0   | 100,000                     | 400                                |
| 100,000   | 500,000                     | 700                                |
| 500,000   | 1,000,000                   | 950                                |
| 1,000,000   | 5,000,000                   | 1,350                              |
| 5,000,000   | 15,000,000                  | 2,300                              |
| Over 15,000,000                                     |                             | 3,900                              |

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**PROMPT PAYMENT**

CFS:JJG

1 of 4

APPR:JDM:DBP:06-29-15  
FHWA:APPR:07-16-15

**Add the following subsection to section 109, on page 106, of the Standard Specifications for Construction:**

**109.08 Prompt Payment.**

**A. Definitions.**

**Lower-tier subcontract.** An agreement between a subcontractor of any tier and any individual or legal entity to perform a part of the subcontract work.

**Lower-tier subcontractor.** The individual or legal entity that performs part of the subcontract work through a lower-tier subcontract with a subcontractor.

**Supplier.** The individual or legal entity that agrees to provide materials or services to the prime Contractor, a subcontractor, or a lower-tier subcontractor for the performance of their contract work.

**Sworn Statement.** A written verification under oath reflecting all persons or entities, which have furnished labor, equipment, services or materials to a subcontractor or lower-tier subcontractor for performance of work on the project. The written verification includes union fringe benefit funds, original contract amount, current amount due, amounts paid to date and balance to finish the work for each person or entity.

**Waiver of Lien.** A written release and waiver of any claim or right to payment for payments actually received for labor, equipment, services or materials furnished for performance of work on the project.

The sworn statement and waiver of lien documents are used by the prime Contractor and its subcontractors for verifying payments made to lower-tier subcontractors/suppliers and are not to be submitted to the Engineer unless requested as an aid in determining an alleged prompt payment violation. These documents can be found at the following website under the Construction Field Services - Forms heading:

[http://www.michigan.gov/mdot/0,1607,7-151-9622\\_11044\\_11367---,00.html](http://www.michigan.gov/mdot/0,1607,7-151-9622_11044_11367---,00.html)

**B. Progress Payments.** For the first payment, or for a one time payment, the prime Contractor agrees to pay each subcontractor for the work associated with their subcontract no later than 10 calendar days from the date the prime Contractor receives payment from the Department.

For the second and subsequent payments, the prime Contractor agrees to pay each

subcontractor for the work associated with their subcontract no later than 10 calendar days from the date the prime Contractor receives payment from the Department.

The Contractor is required to provide payment information for previous payments made to all first tier subcontractors and all DBE companies (sub-subcontractors, suppliers, truckers, etc.) at any tier before the Engineer will release the third and subsequent estimates. For all subsequent progress pay estimates if 1) the Engineer payment does not include any first tier subcontractors or any DBE company payments at any tier, and 2) the previously submitted payment reporting information remains unchanged, then payment reporting in the system is not required. Reporting is required when the prime contractor makes payments to any first tier subcontractors and any DBE companies at any tier. The payment information is provided through submittal of the information via the 2124A reporting system (MERS). System information can be found at the following web link.

[http://www.michigan.gov/documents/mdot/Prompt\\_Payment\\_2124A\\_Instructions\\_MERS\\_366314\\_7.pdf](http://www.michigan.gov/documents/mdot/Prompt_Payment_2124A_Instructions_MERS_366314_7.pdf)

The prime Contractor must bring any concerns about the satisfactory completion of subcontractor or lower-tier subcontractor work items, to the Engineer's attention as soon as the concern is discovered. If the work meets the requirements of satisfactory completion and the prime Contractor has been paid for that work, the Engineer must determine whether:

1. The prime Contractor has demonstrated a valid reason for withholding payment from the subcontractor or supplier, or
2. The subcontractor has demonstrated a valid reason for withholding payment from the lower-tier subcontractor or supplier.

If the Engineer determines the reason for withholding payment is valid, the Engineer will process a negative estimate to withdraw the amount involved in the complaint. If payment has not been made for the work related to the complaint, the Engineer will not include those items of work on an estimate until the issue has been resolved.

The prime Contractor remains responsible to make prompt payments on this project to their subcontractors and suppliers except as noted in subsection 109.08.D of this special provision, even if the prime Contractor is in violation of other contractual obligations and the Department is withholding payment from the prime Contractor for those violations.

The prime Contractor must include language in all subcontracts that the Department prohibits prime Contractors from holding retainage from subcontractors. All provisions of this prompt payment subsection apply to all subcontracts, lower-tier subcontracts, and supplier agreements and must be included in each subcontract for the contract, including all lower-tier subcontracts and agreements.

This prompt payment provision is a requirement of 49 CFR 26.29 and does not confer third-party beneficiary rights or other direct rights to a subcontractor against the Department. This provision applies to both DBE and non-DBE subcontractors/suppliers at all tiers.

**C. Satisfactory Completion.** Progress and partial payments for contract work are issued based on the satisfactory completion of work. Satisfactory completion, for purposes of this prompt payment provision, is defined as:



1. Upon preliminary review, the Engineer finds the work completed in accordance with the contract, plans, and specifications; and,
2. Required documentation, including material certifications, payrolls, submission of 2124A, etc., has been received and reviewed and found to be acceptable by the Engineer; and,
3. Required subcontractor sworn statements and waivers of lien have been provided to the prime Contractor. The prime Contractor must provide notice to the Engineer if sworn statements and waivers of lien have not been received for completed work.

The Engineer will determine if the work meets the standards of satisfactory completion.

**D. Less than full payment release.** The Engineer may give written approval to:

1. Delay or postpone payment from the time frames specified herein,
2. Process partial payment from the prime Contractor to a subcontractor or supplier,
3. Process partial payment from a subcontractor to a lower-tier subcontractor or supplier.

The unpaid portion will be held by the Department.

The parties may initiate whatever dispute resolution procedure is specified in their agreement or is available under Michigan law. If dispute resolution or litigation is selected, the actions by both parties must proceed in a timely manner. The result of the dispute resolution proceeding or litigation must be provided to the Engineer promptly upon the conclusion of the proceeding. The Engineer will release the disputed payment being held by the Department in accordance with the outcome of the proceedings.

**E. Non-Payment Claims.** The prime Contractor, subcontractor, lower-tier subcontractor or supplier must notify the alleged offending party in writing of any prompt payment violations within 30 calendar days of the date the payment was to be received. Copies of the notifications must be provided to the Engineer and the prime Contractor (only if the prime Contractor is not the offending party).

The alleged offending party must respond in writing to the claimant within 10 calendar days of receipt of the notification of failure to meet prompt payment provisions. Provide copies of the response to the Engineer, the prime Contractor (only if the prime Contractor is not the offending party), and the Engineer of Construction Field Services. The prime Contractor, subcontractor, or supplier must also provide the required sworn statements and waivers of lien from the affected subcontractor or supplier to the Engineer within 10 days of receipt of the notification. The Department will consider the failure of the alleged offending party to respond to the notification from the claimant as an admission of the prompt pay violation which may result in sanctions.

The Engineer will review the written notice and response and will verify in writing if there is a valid prompt pay violation.

Independent of all procedures and requirements in this special provision the non-payment claimant has the additional option of submitting a lien claim to the MDOT Contract Services Division. MDOT will notify the project surety of the non-payment issue. It is the responsibility of

the surety to ensure that all legitimately due payments are made. The submission of a lien claim will not nullify or affect any other requirements, obligations or procedures in this special provision.

**F. Remedies.** When the Engineer verifies a prompt payment violation, the prime Contractor within 5 days must propose one or a combination of any of the following actions items for review and approval by the Engineer:

1. Issue payment to the subcontractor.
2. Issue payments to a subcontractor in the form of joint checks to the subcontractor and the subcontractor's lower-tier subcontractors and/or suppliers.
3. Issue payment directly to the subcontractor's lower-tier subcontractors or suppliers.
4. Request a negative estimate to withdraw the amount confirmed in the prompt payment violation.

If the prime Contractor fails to submit a timely remedy request or obtain an approved course of action within the 5 day time period, the Engineer will direct a course of action or issue a negative estimate to withdraw the amount confirmed in the prompt payment violation.

If the prime Contractor fails to fulfill the approved or directed course of action the Engineer will impose sanctions until such time as the approved or directed course of action is completed.

Any payments to a subcontractor's lower-tier subcontractor or supplier will be issued in the amounts reflected upon the subcontractor's sworn statements or in amounts independently verified by the Engineer as being due the subcontractor's lower-tier subcontractors and suppliers for work completed. Payments to a lower-tier subcontractor or supplier will be considered payment to the subcontractor directly so that payment for the same work cannot be claimed.

Any other use of joint checks must follow current Department procedures.

**G. Sanctions.** Failure to comply with any of the prompt payment requirements by the prime Contractor, subcontractor, lower-tier subcontractor, or supplier may result in sanctions against the offending party. These sanctions may include, but are not limited to: withholding of estimates on projects where prompt payment violations are confirmed; reduction or removal of prequalification; and/or suspension of bidding privileges.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**DELAY COSTS**

CFS:JJG

1 of 1

APPR:RJC:MB:02-22-17  
FHWA:APPR:02-27-17

**Delete subsections 109.05.E.1.a through 109.05.E.1.e, on page 102 of the Standard Specifications for Construction, in their entirety and replace with the following:**

- a. Proof of cost of project staff salaries, wages, payroll taxes and insurance.
- b. Proof of escalated cost for labor, equipment, and material.
- c. Proof of material storage costs.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**QUALITY CONTROL AND ACCEPTANCE OF PORTLAND CEMENT CONCRETE  
(FOR LOCAL AGENCY PROJECTS ONLY)**

CFS:JFS

1 of 20

APPR:TES:DBP:06-30-17  
FHWA:APPR:07-11-17

**a. Description.** The Contractor must administer quality control (QC) and the Department will administer quality assurance (QA) procedures that will be used for acceptance of and payment for all Portland cement concrete (PCC) for the project. Except as explicitly modified by this special provision, all materials, test methods, and PCC mixture requirements of the standard specifications and the contract apply.

Do not place concrete until the Engineer's daily startup testing verifies that the fresh concrete properties have been met, in accordance with subsection d.2 of this special provision.

Provide the Engineer a minimum 24 hours notification prior to each concrete placement.

1. Terminology.

**Air Content of Fresh Concrete.** The recorded total air content of fresh concrete sampled and tested according to this special provision.

**Air Content Test Results.** The recorded air content of fresh concrete corresponding to the strength test specimens that were molded for acceptance.

**Alkali-Silica Reactivity (ASR).** A chemical reaction which occurs over time within concrete between high alkaline cement paste and reactive forms of silica found in some aggregates. In the presence of moisture, an expansive ASR gel is formed which can exert pressure within the concrete, causing random cracking and premature deterioration of the concrete. See subsection c.5.A of this special provision.

**Base Price.** Price established by the Department to be used in calculating incentives or adjustments to pay items and shown in the contract.

**Concrete Mix Design.** The process, by which the concrete mixture performance characteristics are defined, based on selected materials, performance requirements, environmental exposure considerations, placement methods, and other factors that control the plastic and hardened properties of the concrete in efforts to produce an economical and durable product.

**Job Mix Formula (JMF).** The actual batch quantities (mixture proportions) of each constituent included in the concrete mixture, based on adjustments to the target weights attained from the mix design process, necessary to optimize the concrete mixture properties.

**Pay Factor (PF).** The factor that is determined according to subsections d.3 of this special provision, used to calculate the price adjustment for a discrete quantity of concrete relative

to its respective level of quality. Pay factor will not exceed 1.00. Therefore, there will never be a positive pay adjustment.

**Price Adjustment (ADJ).** The price adjustment applied to the quantity of concrete represented by the respective quality index analysis described in subsections d.3 of this special provision.

**Production Lot.** A discrete cubic yard quantity of concrete containing the same JMF and used for the same application, as described in subsection d.2 of this special provision.

**Quality Assurance (QA).** Activities administered by the Engineer dealing with acceptance of the product, including, but not limited to, materials selection, sampling, testing, construction inspection, and review of Contractor QC documentation. All concrete QA sampling and testing will be administered by the Department. Department administered QA is described in section d of this special provision.

**Quality Control (QC).** All activities administered by the Contractor to monitor, assess, and adjust production and placement processes to ensure the final product will meet the specified levels of quality, including, but not limited to, training, materials selection, sampling, testing, project oversight and documentation. Contractor administered QC is described in section c of this special provision.

**QC Action Limits.** A range of values established by the Contractor in the QC plan that, if exceeded, requires that corrective action be taken by the Contractor to restore the continuity and uniformity of the mixture and methods in conformance with specification requirements. The QC action limits must not exceed the QC suspension limits.

**QC Plan.** The project-specific plan developed by the Contractor describing, in detail, all aspects of production and construction for the project to ensure consistent control of quality to meet specification requirements.

**QC Plan Administrator.** An employee of, or consultant engaged by the Contractor, responsible for developing and overseeing all aspects of QC for the project. This includes, but is not limited to preparing the QC plan, managing the Contractor QC personnel, communicating routinely with the production personnel to ensure quality, initiating corrective action and suspending operations when the process is found to be producing non-conforming materials, and preparing and submitting all necessary QC documentation to the Engineer within the specified time period.

**QC Suspension Limits.** A range of values defined in Table 1 that, if exceeded on a single QC test, requires that the Contractor suspend operations and determine, correct, and document the deficiencies before resuming production. The QC suspension limit must not exceed specification requirement thresholds.

**Sample.** A representative quantity of concrete taken during production which is used to measure the quality characteristics for the concrete.

**Sampling Rate.** The number of times the fresh concrete is sampled, as described in subsection d.2 of this special provision.

**Small Incidental Quantity.** A single day's placement of less than 20 cubic yards of concrete used for non-structural or non-pavement related applications, including, but not limited to:

curb and gutter, sidewalks and sidewalk ramps (excluding driveways and driveway ramps), installing sign or fence posts, guard rail or cable rail foundations (excluding end anchorage foundations), or other contract items where the small quantity of concrete is not paid for separately, as approved by the Engineer. Requirements for small incidental quantity consideration are described in subsections c.5.G, d.2.B and d.3 of this special provision. The corresponding weekly QA test results must meet specification limits defined in Table 3.

**Specification Limits.** The threshold values placed on a quality characteristic used to evaluate the quality of the material.

**Strength Sample Test Result.** The average of the two companion 28-day compressive strength test specimens taken from the same sample of concrete is considered a strength sample test result.

**Strength Test Specimen.** A strength test specimen is an individual 6-inch by 12-inch strength test cylinder or 4-inch by 8-inch strength test cylinder molded and cured according to *AASHTO T23/ASTM C 31* and tested according to *AASHTO T22/ASTM C 39*. All respective QC or QA strength test specimens must be the same nominal size. Strength test specimen cylinder size of 4-inch by 8-inch is permitted only if the nominal maximum coarse aggregate particle size, as specified for the coarse aggregate in the concrete mixture, is 1-inch, or less.

**Sublot.** A portion of a production lot, represented by a complete set of QA tests, as described in subsection d.2.A of this special provision. The Engineer and the Contractor may agree to reduce the typical subplot size based on project staging or other project conditions.

**Supplementary Cementitious Materials (SCM).** A mineral admixture (slag cement, fly ash) used to replace a portion of the Portland cement, either individually or as a blended cement, in the concrete mixture. SCM requirements are described in subsection c.5 of this special provision.

**b. Materials.** Mixture requirements must be in accordance with the contract.

**c. Contractor Administered Quality Control (QC).**

1. Contractor Quality Control Plan (QC plan). Prepare, implement, and maintain a QC plan specific to the project for concrete that will provide quality oversight for production, testing, and control of construction processes. The QC plan must be in conformance with the contract and must identify all procedures used to control production and placement including when to initiate corrective action necessary to maintain the quality and uniformity of the work.

Develop concrete mix designs and JMFs, as specified, and conduct QC sampling, testing, and inspection during all phases of the concrete work at the minimum frequency, or at an increased frequency sufficient to ensure that the work conforms to specification requirements.

Project-specific items required in the QC plan include (where applicable), but are not limited to the following:

A. Organization chart.

- B. QC Plan Administrator and contact information.
- C. The name(s) and credentials of the QC staff.
- D. Methods for interaction between production and QC personnel to engage timely corrective action, including suspension of work.
- E. Coordination of activities.
- F. Documentation, procedures, and submittals.
- G. Project and plant specifics.
- H. Concrete production facilities inspections and certifications.
- I. Current testing equipment calibration documentation including calibration factor.
- J. Testing and initial field curing facilities for QC and QA strength test specimens (AASHTO T23/ASTM C 31).
- K. Stockpile management plan.
- L. Corrective action plan.
- M. Mixing time and transportation, including time from batching to completion of delivery and batch placement rate (batches per hour), along with the manufacturer's documentation relative to the batching equipment's capabilities in terms of maximum mixing capacity and minimum mixing time (*ASTM C 94*).
- N. Placement and consolidation methods including monitoring of vibration, depth checks, and verification of pavement dowel bar alignment.
- O. Process for monitoring stability of air content of fresh concrete during concrete production and placement.
- P. Hot and cold weather protection considerations and methods.
- Q. Control charts with action and suspension limits.
- R. Verification for non-deleterious alkali-silica reactivity (see subsection c.5.A of this special provision).
- S. Mix design and JMFs.
- T. Proposed production lot size and location for use of each JMF on the project.
- U. The frequency of sampling and testing.
- V. Handling, protection, initial curing, and transporting of strength test specimens (*AASHTO T23/ASTM C31*).

- W. Methods to monitor construction equipment loading and open-to-traffic strengths.
- X. Finishing and curing procedure.
- Y. Ride quality control.
- Z. List of QC records to be submitted to the Engineer in accordance with subsection c.2 of this special provision.

Submit the QC plan, for the appropriate items of work, to the Engineer for review a minimum of 10 working days before the start of related work. The Engineer will notify the Contractor of any objections relative to the content of the QC plan within 5 working days of receipt of the QC plan. Do not begin concrete placement before acceptance of the QC plan by the Engineer. If the approved QC plan fails to provide acceptable work, or acceptable control of the work, the Engineer may require the Contractor to revise the QC plan. Revisions to the QC plan must be approved by the Engineer prior to resuming work.

2. QC Records. Maintain complete records of all QC tests and inspections. Document what action was taken to correct deficiencies. Include sufficient information to allow the test results to be correlated with the items of work represented.

Furnish one copy of all QC records, including test reports for the fresh concrete placement, to the Engineer within 24 hours after the date covered by the record in a format acceptable to the Engineer. The Engineer will withhold acceptance of the concrete for failure to provide properly documented and timely QC records and reports.

If the Engineer is performing QA sampling and testing at the same time the Contractor is performing QC sampling and testing, all associated QC records must include the appropriate production lot identification number that correlates with the Department's QA production lot identification number.

3. Personnel Requirements. The QC Plan Administrator must have full authority and responsibility to take all actions necessary for the successful implementation of the QC plan, including but not limited to, the following:

A. Monitoring and utilizing QC tests, control charts, and other QC practices to ensure that delivered materials and proportioning meets specification requirements.

B. Monitoring materials shipped to the project, prior to their use, to ensure their continued compatibility toward producing consistent quality.

C. Periodically inspecting all equipment utilized in transporting, proportioning, mixing, placing, consolidating, finishing, and curing to ensure proper operation.

D. Monitoring materials stockpile management, concrete batching, mixing, transporting, placement, consolidation, finishing, and curing to ensure conformance with specification requirements.

E. Maintaining and submitting all QC records and reports.

F. Directing the necessary corrective action to ensure continual conformance within



the QC action limits.

G. Suspending production for the project when suspension limits are exceeded.

H. Conducting or monitoring adjustments to the JMF.

Individuals performing QC tests must demonstrate that they are proficient and capable of sampling and testing concrete or aggregate, where applicable, in accordance with the associated test procedures and Department requirements prior to commencement of related work. Any adjustments to the JMF must be made by a certified concrete technician (Michigan Concrete Association (MCA) Michigan Level II).

4. QC Laboratory Requirements. Laboratories, including field laboratories and all associated testing equipment that prepare concrete mixes or perform QC testing, must demonstrate to the Engineer that they are equipped, staffed, calibrated, and managed so as to be capable of batching, and testing PCC in accordance with the applicable test methods and procedures. Mix designs and their accompanying JMFs must include a statement, signed by a certified concrete technician (MCA Michigan Level II), that all applicable standard test methods have been followed in verifying the mix design and JMF.

5. Mix Design and Documentation. Design concrete mixtures meeting the requirements specified in Table 1. Provide the grade of concrete for the section number reference application specified in Table 1, or as specified in the contract. Request variance in writing when proposing a mix design that exhibits temperature, slump or air content other than those specified. Include the proposed mix design, JMF, and associated trial batch verification test data. Do not use a grade of concrete with a lower specification limit (LSL) 28-day compressive strength greater than what is designated for the application.

Blended cement meeting the requirements of *ASTM C 595 Type II* is permitted.

Ensure supplementary cementitious materials are from an MDOT Approved Manufacturer. Slag cement must meet the requirements of subsection 901.06 of the Standard Specifications for Construction. Fly ash must meet the requirements of subsection 901.07 of the Standard Specifications for Construction.

Secure prior approval from the Engineer to use concrete intended for early opening to traffic to facilitate driveway gaps or other features necessary for required local access.

Unless otherwise specified in the contract, set accelerating admixtures are prohibited.

Unless otherwise specified in the contract, provide either concrete Grade P1 or Grade D for bridge approach slab applications.

Unless otherwise specified in the contract, do not exceed 40 percent replacement of the Portland cement in the concrete mixture with a supplementary cementitious material. Do not exceed 40 percent total replacement of the Portland cement if more than one supplementary cementitious material is used in the concrete mixture.

Use the combined weight of all cementitious materials to determine compliance with the maximum water-cementitious ratio and cementitious material content requirements specified in Table 1.

For night casting, where applicable, a water-reducing admixture may be used in lieu of a water-reducing and retarding admixture, provided the concrete can be placed and finished in the sequence specified on the plans prior to initial set, is not subjected to residual vibration, or is not within the areas influenced by dead load deflections as a result of adjacent concrete placement operations. When the maximum air temperature is not forecast to exceed 60 degrees F for the day, the Contractor may use a water-reducing admixture or a water-reducing retarding admixture.

**Table 1: Minimum Mix Design Requirements for Concrete**

| Mix Design Parameter  | Grade of Concrete |                                    |   |          |           |  |  |
|---|-------------------|------------------------------------|---|----------|-----------|--|--|
|   | P1M<br>(a,b,e)    | P1<br>(a,b)                        | D,DM<br>(a,b,e)   | T        | S1<br>(a) | S2,S2M<br>(a,b,e)  | S3/P2<br>(a)   |
| Lower Specification Limit (LSL)<br>(28-day compressive, psi)  | 3500              | 3500                               | 4500  | 3500     | 4000      | 3500   | 3000   |
| Rejection Limit for an Individual<br>Strength Sample Test Result  | 3000              | 3000                               | 4000  | 3000     | 3500      | 3000   | 2500   |
| Maximum Water/Cementitious Ratio<br>(lb/lb) (c)   | 0.45              |                                    |   |          |           |  |  |
| Cementitious Material Content<br>(lb/yd <sup>3</sup> ) (d)  | 470-564           | 517-611                            | 517-658   | 517-611  | 517-611   | 517-611  | 489-517  |
| Air Content (percent) (f)   | 5.5-8.5           |                                    |   |          |           |  |  |
| Slump (inch) (max.)   | (g)               |                                    |   |          |           |  |  |
| Section Number Reference (h)  | 602, 603          | 602, 603,<br>801, 802,<br>803, 810 | 706, 711,<br>712  | 706, 718 | 705       | 401, 706,<br>712, 713,<br>718, 801,<br>802, 803,<br>810, 819 | 402, 403,<br>602, 803,<br>804, 806,<br>808, 810,<br>813, 814 |
| <p>a. If the local average minimum temperature in the next 10 consecutive days is forecast to be below 40 degrees F, submit a revised QC plan for the Engineer's approval, addressing in detail changes in materials, concrete batching and mixing processes, construction methods, curing, and protection of the in situ concrete to ensure that the necessary quality characteristics of the hardened concrete product will not be compromised as a result of the cold weather. The revised QC plan must be approved by the Engineer prior to cold weather concrete placement. Do not remove supplementary cementitious material from the concrete mixture.</p> <p>b. Use aggregates from only geologically natural sources for pavement, shoulder, miscellaneous pavement (including ramps), concrete pavement overlay, bridge approach slab, structural concrete, drilled shaft, bridge railing, and bridge sidewalk applications.</p> <p>c. Use admixtures as listed in the Qualified Products Lists to reduce mixing water. Ensure concrete in concrete diaphragms contains a water-reducing admixture, or a water-reducing retarding admixture.</p> <p>d. Type III cement is not permitted.</p> <p>e. For grades of concrete requiring optimized gradation, aggregates must meet the physical requirements specified in subsection 902.03.C of the Standard Specifications for Construction. Optimized aggregate gradation is required for pumped concrete.</p> <p>f. For action, suspension, and specification limits, see Tables 2 and 3, where applicable.</p> <p>g. The maximum slump for Grades P1, P1M, and P2 concrete is 3 inches or as documented on the approved JMF. All other grades of concrete will be according to Table 701-1 of the Standard Specifications for Construction.</p> |                   |                                    |   |          |           |  |  |
| h. Section Number Reference:  |                   |                                    | <p>402 Storm Sewers</p> <p>602 Concrete Pavement Construction</p> <p>705 Foundation Piling</p> <p>711 Bridge Railings</p> <p>713 Bridge Rehabilitation-Steel</p> <p>801 Concrete Driveways</p> <p>803 Concrete Sidewalk, Sidewalk Ramps, and Steps</p> <p>806 Shared Use Paths</p> <p>810 Permanent Traffic Signs and Supports</p> <p>814 Paved Ditches</p> |          |           |  |  |
| <p>401 Pipe Culverts</p> <p>403 Drainage Structures</p> <p>603 Concrete Pavement Restoration</p> <p>706 Structural Concrete Construction</p> <p>712 Bridge Rehabilitation-Concrete</p> <p>718 Drilled Shafts</p> <p>802 Concrete Curb, Gutter and Dividers</p> <p>804 Concrete Barriers and Glare Screens</p> <p>808 Fencing</p> <p>813 Slope Protection</p> <p>819 Electrical and Lighting</p>   |                   |                                    |   |          |           |  |  |

A. Alkali-Silica Reactivity. Provide documentation to the Engineer that the concrete mixture does not present the potential for deleterious expansion caused by alkali-silica reactivity (ASR). Provide current ASR test results (valid for 2 years from completion of testing), for the fine aggregate that is proposed to be used in the concrete, from an independent testing laboratory proficient in ASR testing. The independent testing laboratory must certify in writing, including a signed statement that all testing was conducted in accordance with the designated standard test procedures, described herein. Test results must conform to the specified criterion for one of the following standard test methods. ASR testing is not required for concrete pavement repairs and temporary concrete pavements. Use the Rounding Method described in *ASTM E 29* when determining significant digits for reporting expansion test results.

(1) Method 1. *ASTM C 1293*. Concrete Prism Test. If the expansion of concrete prisms is not greater than 0.040 percent (rounded to the nearest 0.001 percent) after 1 year, the fine aggregate is considered non-deleterious to ASR and may be used in the JMF.

(2) Method 2. *ASTM C 1567*. Mortar Bar Test. If no previous test data are available for the fine aggregate that shows it is resistant to ASR using Method 1, above, replace 25 to 40 percent of the Portland cement in the concrete mixture with a supplementary cementitious material. A blended cement meeting the requirements of *ASTM C 595* containing the above Portland cement and supplementary cementitious material proportions may also be used.

Demonstrate the ability of the supplementary cementitious material to control the deleterious expansion caused by ASR by molding and testing mortar bars according to the standard test method described in *ASTM C 1567* using the mix proportions and constituent sources for both the aggregates and the cementitious materials that will be used for the project. Make at least three test specimens for each cementitious materials-aggregate combination. If the average of three mortar bars for a given cementitious materials-aggregate combination produces an expansion less than 0.10 percent (rounded to the nearest 0.01 percent) at 14 days of immersion, the JMF associated with that combination will be considered non-deleterious to ASR. If the average expansion is 0.10 percent (rounded to the nearest 0.01 percent) or greater, the JMF associated with that combination will be considered not sufficient to control the deleterious expansion caused by ASR and the JMF will be rejected.

The Engineer will not approve the use of the JMF if the expansion exceeds the respective threshold limits for the respective ASTM test method used.

B. Contractor Provided Mixes. Provide mix design and accompanying JMFs using the methods of verification included in this special provision. Include sufficient information on constituent materials and admixtures along with trial batch verified physical properties of the fresh concrete, mix proportions per cubic yard for all constituents and compressive strength test results necessary to allow the Engineer to fully evaluate the expected performance of the concrete mixture.

(1) Mix Documentation. Prepare mix designs for each grade of concrete required on the project. Submit JMF for each mix design, including all required documentation, to the Engineer for review 10 working days before the anticipated

date of placement. The Engineer will notify the Contractor of any objections within 5 working days of receipt of the mix documentation. Number or otherwise identify each JMF and reference all accompanying documentation to this identification. Reference each JMF to the appropriate method of verification. Mix design and JMF submittals that do not include all required documentation will be considered incomplete and the Engineer will return them without review.

Mix documentation is valid for 2 years.

All mix designs and accompanying JMFs must be traceable to a laboratory meeting the requirements of this special provision.

Submit mix design and JMF on the MDOT Job Mix Formula (JMF) Concrete Field Communication form (MDOT Form Number 1976); include accompanying documentation. List the source of materials, bulk density (unit weight) of coarse aggregate (rodding procedure or shoveling procedure), absorption of aggregates, relative density (specific gravity) of aggregates, aggregate correction factors, batch weights, and project specific or historical laboratory test data. Include the recorded air content of fresh concrete using the same admixture and cementitious material sources to be used in the production of the concrete for the project. A JMF will be approved only if all of the minimum mix design requirements specified in the contract have been met.

(2) Job Mix Formula (JMF). Select proportions for concrete mixtures according to *ACI Standard 211.1*. The volume (oven-dry-rodded) of coarse aggregate per unit volume of concrete must be 65 percent, minimum.

Four methods of verification of proposed JMF are acceptable.

(a) Method 1. Trial Batches. Verification of JMF is based on trial batches with the same materials and proportions proposed for use on the project. Prepare at least one trial batch for each mix design in sufficient time before starting concrete placement to allow for review according to subsection c.5.B.(1) of this special provision. Provide the results of temperature, slump, density (unit weight), air content of fresh concrete, 28-day compressive strength, and age of concrete at the time of strength testing, for a minimum of three independent samples. All samples may be taken from a single trial batch for a mix design provided the trial batch is at least four cubic yards in volume. For JMF trial batch verification purposes only, 7-day compressive strength test results which report at least 70 percent of the specified 28-day lower specification limit (LSL) will be sufficient documentation in lieu of 28-day compressive strengths. The average of at least two strength test specimens represents one compressive strength sample test result for each independent sample. Provide the necessary ASR documentation as described in subsection c.5.A of this special provision.

(b) Method 2. Same Mix. Verification of JMF is based on the concrete producer's experience with the same mix design, JMF, and the same materials. Provide the results of temperature, slump, density (unit weight), air content of fresh concrete, 28-day compressive strength, and age of concrete at the time of strength testing, for a minimum of three independent samples. The average of at least two strength test specimens represents one compressive strength

sample test result for each independent sample. Do not substitute material types or sources, including admixtures or cementitious materials, nor change mix proportions in the JMF. Provide the necessary ASR documentation as described in subsection c.5.A of this special provision.

(c) Method 3. Similar Mix. Verification of JMF is based on requirements described in Method 2, in subsection c.5.B.(2).(b) of this special provision. Substitution of coarse aggregate source is permitted if the new source is of the same geologic type as the original aggregate, and conforms to the specification requirements for the application. Substitution of fine aggregate is permitted only if the new source has been tested for ASR. Provide the necessary ASR documentation as described in subsection c.5.A of this special provision.

Provide the supporting laboratory trial batch documentation and accompanying calculations showing how the mix proportions in the JMF were adjusted, based on the documented differences in relative density (specific gravity), bulk density (unit weight) and absorption of the substituted aggregate sources, to produce a theoretical yield of 100 percent and the required fresh concrete properties.

(d) Method 4. Annual Verification. At the Engineer's option, verification may be accepted annually for a concrete producer rather than on a project basis provided the sources and proportions of the constituent materials, including cementitious materials and source and types admixtures, do not change. If the project is the continuation of work in progress during the previous construction season and written certification is submitted to the Engineer that materials from the same source and with the same mixture properties are to be used, the Engineer may waive the requirement for annual renewal verification of the JMF for the project. Provide the necessary ASR documentation as described in subsection c.5.A of this special provision.

C. Department Provided Mixes. Unless otherwise specified in the contract or approved by the Engineer, the Engineer will provide the concrete JMF for the following types of concrete regardless of the total quantity for the project.

- (1) Structural concrete patching mixtures, mortar and grout.
- (2) Bridge deck overlay concrete mixtures.
- (3) Project-specific concrete mixtures and grades not defined in Table 1.

Provide all other mix designs and accompanying JMF's according to subsection c.5.B of this special provision.

The ASR documentation for the fine aggregate described in subsection c.5.A of this special provision must accompany the Contractor's request for the concrete JMF.

D. Changes in Materials and Proportions. Any changing from one approved JMF to another for the same grade of concrete must have prior approval by the Engineer.

Prior to batching, verify that the proposed JMF changes will not affect the properties of the fresh concrete (slump, temperature, air content, density (unit weight), workability),

nor result in deleterious mortar bar expansion as a result of ASR, as described in subsection c.5.A of this special provision.

Record all changes to JMF in the QC records along with the rationale for the change.

E. QC Sampling and Testing. Conduct startup sampling and testing for temperature, slump, density (unit weight), and air content on the first load. Do not place concrete until testing verifies that the fresh concrete properties have not exceeded the QC action and suspension limit thresholds specified in Table 2 and the testing correlation requirements of subsection d.1.B of this special provision have been met. Continue testing subsequent loads as described in the QC plan, for each grade of concrete delivered to the work site each day. The QC sampling and testing must be random and independent from the Agencies QA sampling and testing.

Provide the curing facilities in accordance with subsection d.2.C of this special provision prior to start of concrete production.

Perform QC sampling and testing for air content of fresh concrete that is either slipformed or pumped, as described in the QC plan. Sample and test a representative haul unit of concrete immediately after its discharge but before the slipform paver or pump hopper, where applicable. Sample and test the concrete representing the same haul unit, again, after the slipform paver or after discharge from the pump (without interruption or alteration of the pumping operation), where applicable. If the difference in measured air content between the two test locations for the same concrete is greater than 1.5 percent air by volume of concrete, suspend operations and administer corrective action. Resume concrete placement only after taking the necessary corrective action to reduce the loss in air content of fresh concrete between the two test locations, as approved by the Engineer. Document the corrective action to be taken in the QC records and make the necessary changes to the QC plan, where applicable.

Concrete exceeding the maximum specification limits for slump or temperature must be rejected regardless of the total mixing time at the time of arrival to the project.

The Engineer may require the Contractor to administer additional QC sampling and testing if the Engineer determines the Contractor's current QC sampling and testing methodology is shown to be insufficient to ensure continual control of the quality of the concrete.

Take the appropriate corrective action, as described in the QC plan, when QC testing shows the QC action limits for any quality characteristic are exceeded. Suspend production if any of the QC suspension limits are exceeded or if the corrective action is not sufficient to restore the quality to acceptable levels.

Resume production only after making all necessary adjustments to bring the mixture into conformance with all applicable specifications and receiving approval to resume work from the Engineer. Document these adjustments in the QC records.

**Table 2: QC Action and Suspension Limits**

| Quality Characteristic   | Action Limits                        | Suspension Limits                 |
|--|--------------------------------------|-----------------------------------|
| Air Content (percent)  | See Note Below                       | < 5.0 or > 9.0                    |
| Air Content Loss (percent)   | As Defined in the Contractor QC plan | Greater than 1.5                  |
| Conc. Temp. (Deg. F)   |                                      | < 45 or > 90 at time of placement |
| Slump (max.) (inch)  |                                      | See Table 1, footnote (g)         |
| Density (unit weight)  |                                      | N/A                               |
| Note: Action limits must be defined in the Contractor QC plan and cannot be < 5.5 or > 8.5. Suspend work if air content is < 5.0 or > 9.0 percent after pump or paver, regardless of the air content loss. |                                      |                                   |

F. Work Progress Test Specimens. Determine the strength of concrete for opening to construction traffic or regular traffic, for removing shoring and forms, or for similar purposes in accordance with subsections 104.11, 601.03.H and 701.03.D of the Standard Specifications for Construction, and as approved by the Engineer. Cure work progress test specimens in the same manner as the in-situ concrete. Allow the Engineer to witness testing of work progress test specimens.

The maturity method may be used to determine the in-place, opening-to-traffic flexural strength, provided the necessary preliminary flexural strength versus time-temperature factor correlation, using the same materials and JMF, is established according to Department procedures and approved by the Engineer before placing the concrete.

G. Reduced QC for Small Incidental Quantities. If approved by the Engineer, reduced levels of on-site QC testing for concrete may be considered for small incidental quantities defined in subsection a.1 of this special provision.

Unless approved by the Engineer, multiple small incidental quantities, including ones that are consecutively placed throughout the project on the same day, are not eligible for reduced QC consideration if the total plan quantity of concrete for the item exceeds 100 cubic yards in volume. Include details for reduced QC testing and oversight in the approved QC plan, and in accordance with following:

- (1) The small incidental quantity of concrete will be limited to a single day's concrete placement of a maximum 20 cubic yards in volume.
- (2) The small incidental quantity of concrete is not an integral part of a structural load bearing element.
- (3) The Engineer received written certification from the Contractor that the concrete supplier has a current QC plan in place and available for review upon request by the Engineer.
- (4) The concrete supplier employs a certified concrete technician (MCA Michigan Level II) available at the plant or on call during concrete placement to validate and authorize modifications to the concrete JMF, as necessary.
- (5) Prior to the first concreting operation, concrete representing the JMF for the small incidental quantity has been sampled and tested by a certified concrete technician (MCA Michigan Level I or II) to verify that, historically, the JMF produced a

concrete mixture meeting the minimum requirements for density (unit weight), slump, air content, and strength. Annual verification may be acceptable provided there are no changes to the material types or sources, including the cementitious materials and admixtures.

(6) The Engineer verified that the temperature, slump, and air content conform to specification requirements at the start of the day's concreting operation associated with the small incidental quantity.

(7) The Engineer is notified and provided sufficient opportunity to witness concrete placement.

**d. Department Administered Quality Assurance (Acceptance).**

1. Department Quality Assurance Plan (QA plan). The Engineer will be responsible for administering the quality-based acceptance and will institute any actions necessary toward its successful implementation.

Acceptance of concrete pavement repair mixtures and concrete mixtures not included in Table 1 will be in accordance with the contract.

The Engineer will develop and follow a QA plan. The Engineer will provide the QA plan to the QC Plan Administrator a minimum of 5 working days prior to the pre-production meeting. The QA plan will be reviewed at the pre-production meeting and any proposed changes will be documented.

The nominal QA strength test specimen size, defined in subsection a.1 of this special provision will be noted in the QA plan.

A. Personnel Requirements. The personnel responsible for field inspection and for obtaining QA samples will possess the required qualifications to collect QA samples. Sampling will be performed by a certified concrete technician (MCA Michigan Level I or II) or (MCAT) certified aggregate technician, where applicable.

B. Testing Correlation. Prior to initial concrete placement, the testing personnel for both the Engineer's QA and Contractor's QC will use the equipment they have assigned to the project to conduct side by side correlation testing of the same concrete used on the project to verify correlation of both the Department's and the Contractor's test results for temperature and air content of fresh concrete. Additional side by side correlation testing will be conducted whenever there is a change in QC or QA equipment and/or testing personnel for the project, or as directed by the Engineer. The temperature measuring devices used for QC and QA must correlate with each other within 2 degrees F. If the air content results of the side by side tests conducted by the QC and QA testers and equipment differ by more than 0.8 percent air by volume of concrete, a referee air content test of fresh concrete must be conducted by a third party, designated by the Engineer but independent of the project, prior to commencement or continuation of concrete placement in efforts to resolve issues associated with non-correlation.

C. Laboratory Facilities. The testing laboratory with responsibility for acceptance testing on this project is the Department testing laboratory, or a qualified facility under the authority of the Engineer.



2. QA Sampling and Testing. The Engineer will verify the Contractor's daily startup sampling and testing of temperature, slump, and air content of fresh concrete on the first load; conduct QA sampling and testing; monitor Contractor adherence to the QC plan; and inspect field placed materials in such a manner as to ensure that all concrete for the project is represented. The testing correlation requirements of subsection d.1.B of this special provision must be met prior to concrete placement.

The following *ASTM* test methods will apply. The Department's established procedures for sampling and testing are acceptable alternatives.

C 31 Practice for Making and Curing Concrete Test Specimens in the Field

C 39 Test Method for Compressive Strength of Cylindrical Concrete Specimens

C 78 Test Method for Flexural Strength of Concrete (Using Simple Beam with Third-Point Loading)

C 138 Test Method for Density (Unit Weight), Yield and Air Content (Gravimetric) of Concrete

C 143 Test Method for Slump of Hydraulic-Cement Concrete

C 172 Practice for Sampling Freshly Mixed Concrete

C 173 Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method

C 231 Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method

C 293 Test Method for Flexural Strength of Concrete (Using Simple Beam with Center-Point Loading)

A. Lot Size and Make Up. A production lot will not include more than one grade of concrete, concrete of the same grade having different specified slump or air content, or concrete of the same grade having different mix designs, or JMFs. Lot size and makeup will be determined by the Engineer, based on site conditions. A production lot may consist of a single day's production, individual concrete structural elements (eg. footing, column, pier cap, deck, bridge approach slab), or any combination thereof, provided they are of the same JMF. Each production lot will be divided into sublots of approximately equal size, as determined by the Engineer. The minimum number of sublots will be one per production lot, with the maximum number of sublots based on the anticipated total quantity of concrete to be placed and site conditions. A minimum of one subplot will be required for each day of production.

B. Sampling. QA sampling and testing will be conducted by the Engineer during concrete placement. Where practical, the random number method (as described in the "Random Sampling for Quality Control/Quality Assurance Projects" section of the Materials Quality Assurance Procedures Manual) will be used to determine the sampling locations. The sampling rate will be determined by the Engineer, based on the anticipated total quantity of concrete to be placed and site conditions, with a minimum of one sampling for each day of production.

At the option of the Engineer, small incidental quantities as defined in subsection a.1 of this special provision may be accepted (visually inspected and noted on the Inspector's Daily Report) without daily 28-day compressive strength QA test specimens provided there is a current acceptable strength test history of the JMF for the project prior to placement of the small incidental quantity. One set of compressive strength QA test specimens will then be molded for each small incidental quantity JMF at least once per week during production, thereafter, as determined by the Engineer (note the test results or identification number for the corresponding weekly QA compressive strength test result on the Inspector's Daily Report for each small incidental quantity). Quality control testing and daily QA testing for temperature, slump, and air content of fresh concrete are still required. Reduced QC for small incidental quantities, as described in subsection c.5.G of this special provision, may be considered.

The QA sampling rate and sample location will be based on cubic yard quantities.

Samples for acceptance will be taken at the point of discharge from the haul unit, at approximately the middle one-third of the load. Mix adjustments to the concrete contained within the haul unit selected for QA sampling and testing (beyond normal QC) will not be permitted prior to QA sampling and testing. QA sampling will be random and without prior notification.

The Engineer will perform QA sampling and testing for air content loss of fresh concrete that is either slipformed or pumped, (1) at least once during each day of production, (2) whenever the concrete pump is relocated, where applicable, or (3) whenever there is a significant change in the boom configuration or operation of the concrete pump, or there is a significant change in the characteristics of the paving operation during concrete placement. Concrete will be sampled from a representative haul unit immediately after its discharge but before the slipform paver or pump hopper, where applicable. The concrete representing the same haul unit will then be sampled and tested after the slipform paver or after discharge from the pump (without interruption or alteration of the pumping operation), where applicable. If the difference in measured air content between the two test locations for the same concrete is greater than 1.5 percent air by volume of concrete, the Engineer will issue a Notice of Non-Compliance with Contract Requirements (Form 1165), as described in subsection d.2.D of this special provision. The Contractor may resume concrete placement only after the necessary corrective action is taken to reduce the loss in air content of fresh concrete between the two test locations, as approved by the Engineer. Document the corrective action that was taken by the Contractor.

C. Testing. The location(s) within the project limits for QA testing of the fresh concrete and placement of curing facilities for initial curing of the 28-day compressive strength QA test cylinders will be determined by the Engineer in conformance with the following criteria:

(1) The elapsed time between obtaining the first and the final portion of the composite sample must not exceed 15 minutes.

(2) Testing for slump, temperature, and air content of fresh concrete must begin within 5 minutes after obtaining the final portion of the composite sample.

(3) Molding of the 28-day compressive strength QA test cylinders must begin within 15 minutes after obtaining the final portion of the composite sample.

(4) The concrete sample must be protected from the sun, wind, and other sources of rapid evaporation, and from contamination.

Two QA concrete strength test specimens per sample will be molded for 28-day compressive strength QA testing.

The Contractor will provide curing facilities equipped to ensure the proper environment for the Agencies QA concrete strength test specimens during initial cure. Each initial cure facility must provide ventilation or insulation, where applicable, to ensure the ambient temperature surrounding the specimens is maintained according to *AASHTO T23/ASTM C 31*. Failure by the Contractor to maintain the proper curing environment during initial cure will not be basis for rejection of samples or claims against the Department. Each initial curing facility must be capable of being locked, using an Department provided padlock. The Contractor will ensure that all initial curing facilities are accounted for at all time, and protected against theft and damage. The Contractor will place and secure each initial cure facility throughout the project limits in such a manner so as to minimize excessive transport of the test specimens prior to initial cure, as follows:

(5) Immediately after finishing molded specimens, the Engineer will move the QA concrete strength test specimens to the closest initial cure facility provided by the Contractor.

(6) Immediately after all QA concrete strength test specimens are placed into the cure facility and the proper initial curing conditions have been established, the Engineer will secure the facility using the Department provided padlock. Access to the QA concrete strength test specimens, thereafter, must be coordinated with the Engineer and will only be permitted in the presence of the Engineer.

(7) The Engineer will transport the QA concrete strength test specimens within 48 hours after molding, but not prior to 8 hours after final set of the concrete, from the initial curing facility to the Department's designated testing laboratory for final curing and strength testing. The specimens will be protected with a suitable cushioning material to prevent damage from jarring during transport. The total transportation time must not exceed 4 hours prior to commencement of final curing.

D. QA Stop Production Criteria. The Engineer will issue a Notice of Non-Compliance with Contract Requirements (Form 1165) and concrete production must stop when one or more of the following are observed.

(1) The QA testing shows that one or more of the suspension limits for quality characteristics defined in Table 2 are in non-compliance.

(2) The QC plan is not being followed.

(3) Segregation, excessive slumping of unsupported slipformed edges, or other notable changes in the fresh concrete properties is observed that may prevent proper placement, consolidation and finishing, or compromise the performance or long-term durability of the finished product.

(4) The required curing system is not being applied in a timely manner, as specified by the contract.

(5) If the measured air content loss between the two testing locations for the same concrete is greater than 1.5 percent air by volume of concrete as described in subsections c.5.E and d.2.B of this special provision.

(6) If the air content of fresh concrete is less than 5.0 or greater than 9.0 percent after pump or paver, regardless of the recorded QC or QA air content loss through the pump or paver.

The Engineer will issue a Notice to Resume Work (Form 1165) only after all necessary adjustments are made to restore conformance with all applicable specifications, and the appropriate documentation is made in the QC records.

E. QA Records. The Engineer will maintain a complete record of all QA tests and inspections. The records will contain, as a minimum, signed originals of all QA test results and raw data, random numbers used (where applicable) and resulting calculations. The QA test results will not be provided to the Contractor until the corresponding QC test results are received by the Engineer.

3. Quality Index Analysis. The Engineer's QA test results will be used to determine the pay factor (PF) and price adjustment (ADJ). The Contractor's QC test results will not be used for pay factor and price adjustment analysis. The Engineer will complete pay factor and price adjustment analysis within 7 working days after completion of all 28-day compressive strength testing for the representative production lot or quantity of concrete. The quality index parameter specification limits are defined in Table 3. Unless otherwise specified in the contract, concrete not conforming to the requirements specified in Table 3 is rejectable and subject to further evaluation. All values of PF and OLPF in these formulae are decimal, not percent. All values of PF and OLPF are rounded to two decimal places.

Price adjustment for 28-day compressive strength deficiencies will be based on test results for the corresponding weekly QA test specimens and the pay factor (PFs) calculated according to the formula defined in subsection d.3.A. The price adjustment (ADJ) = (PFs – 1)(Price).

**Table 3: Quality Index Parameter Specification Limits**

| Quality Characteristic                           | Specification Limits         |
|--|------------------------------|
| Air Content of Fresh Concrete (percent)          | 5.5 – 8.5                    |
| Rejection Limit (percent)                        | <5.0 or >9.0                 |
| Conc. Temp. (deg. F)                             | 45 - 90 at time of placement |
| Slump (max.) (inch)                              | See Table 1, footnote (g)    |
| 28-day Compressive Strength (psi)                | For LSL see Table 1          |
| Rejection Limit -<br>28-day Compressive Strength | See Table 1                  |

A. Pay Factor for 28-Day Compressive Strength (PFs).

$$PFs = \frac{\text{Tested Strength}}{LSL}$$

Where:

PFs = Pay Factor for 28-day compressive strength (not to exceed 1.00)

Tested Strength = QA 28-day compressive strength sample test result

LSL = Lower specification limit (see Table 1)

If the tested strength does not meet the rejection limit specified in Table 1, the Engineer will require additional evaluation as described in subsection d.4 of this special provision.

B. Pay Factor for Air Content of Fresh Concrete (PFac). The pay factor for air content of fresh concrete (PFac) will be according to Table 4.

**Table 4: Air Content of Fresh Concrete Pay Factor (PFac)**

| Air Content of Fresh Concrete (percent) | Pay Factor (PFac) |
|---|-------------------|
| 5.5 – 8.5                               | 1.00              |
| 5.0 – 5.4                               | 0.50              |
| Below 5.0                               | Rejection         |
| 8.75 – 9.0                              | 0.75              |
| Above 9.0                               | Rejection         |

If the air content of fresh concrete is below 5.0 or above 9.0 percent, the Engineer will elect to do one of the following.

(1) Require removal and replacement of the entire quantity of concrete represented by the test with new testing conducted on the replacement concrete and repeat the evaluation procedure.

(2) Allow submittal of a corrective action plan for the Engineer's approval. If the Engineer does not approve the plan for corrective action, subsection d.3.B.(1) of this special provision will be applied. All costs associated with plan submittal and corrective action under this subsection will be borne by the Contractor.

C. Overall Lot Pay Factor (OLPF). The following formulae are used to calculate the OLPF and ADJ. The OLPF will not exceed 1.00.

$$\text{OLPF} = (0.60 \times \text{PFs}) + (0.40 \times \text{PFac})$$

$$\text{ADJ} = (\text{OLPF} - 1)(\text{Price})$$

ADJ = Price adjustment per pay unit to be applied to the quantity represented by the QA test

Price = Base price established for the pay item

4. Evaluation of Rejectable Concrete. The Engineer will require additional evaluation to decide what further action may be warranted, as described below. Acceptance for air content of fresh concrete will be based on QA test results reported at the time of concrete placement.

If the Engineer determines that non-destructive testing (NDT) is appropriate, this work will be

done by the Contractor in the presence of the Engineer within 45 calendar days from concrete placement. All costs associated with this work will be borne by the Contractor. A complete set of non-destructive tests must be conducted (in accordance with the respective standard test method) at a minimum three randomly selected locations. If NDT is used to estimate the in-situ strength, a calibrated relationship between the project JMF under evaluation and the NDT apparatus must have been established prior to NDT testing according to its respective standard test method.

If the 28-day compressive strength QA test results show that the rejection limit (as specified in Table 1) has not been achieved, the quantity of concrete under evaluation will be rejected and the Engineer will require additional evaluation to decide what further action may be warranted.

Propose an evaluation plan and submit it to the Engineer for approval before proceeding. The results from NDT will be used only to decide what further action is required. This determination will be made by the Engineer, as follows:

A. For non-structural concrete. If no test result from non-destructive testing falls below the lower specification (LSL) 28-day compressive strength, the represented quantity of concrete under evaluation will remain in place and a pay factor for 28-day compressive strength (PFs) of 1.00 will be applied for overall lot pay factor (OLPF) and price adjustment (ADJ) determinations according to subsection d.3 of this special provision.

B. For structural concrete (including overhead sign foundations). If no test result from non-destructive testing falls below the lower specification limit 28-day compressive strength, the represented quantity of concrete under evaluation will remain in place and a pay factor for 28-day compressive strength (PFs) of 0.85 will be applied for overall lot pay factor (OLPF) and price adjustment (ADJ) determinations according to subsection d.3 of this special provision.

C. If one or more of the non-destructive test results fall below the lower specification limit (LSL) 28-day compressive strength, the Engineer may elect to do one of the following:

(1) Require removal and replacement of the entire rejected quantity of concrete, including new initial tests for pay factor (PF) determination and price adjustment conducted according to subsection d.3 of this special provision.

(2) Allow the Contractor to submit a plan for corrective action, for the Engineer's approval, to address the disposition of the rejected concrete. If the Engineer does not approve the plan for corrective action, subsection d.4.C.(1) of this special provision will be applied. All costs associated with plan submittal and corrective action under this subsection will be borne by the Contractor.

(3) Allow the in-situ quantity of concrete under evaluation to remain in place and a pay factor (PFs) of 0.50 will be applied for overall lot pay factor (OLPF) and price adjustment (ADJ) determinations according to subsection d.3 of this special provision.

**e. Measurement and Payment.** If a price adjustment is made for reasons included in this special provision, that adjustment will be made using the base price established for the specific item. If a contract unit price requires adjustment for other reasons not described in this special provision, the adjustments will be made using the unit price and the adjustments will be

cumulative.

Separate payment will not be made for providing, implementing, and maintaining an effective QC program. All costs associated with this work will be included in the applicable unit prices for the concrete items. Failure by the Contractor to maintain the proper curing environment during initial cure will not be basis for claim against the Department.

All costs associated with providing, locating, relocating, maintaining, and securing the adequate number of portable initial curing facilities for both the QC and QA strength test specimens will be included in the applicable unit prices for the concrete items. No additional payment will be permitted. The Contractor is responsible for damage, theft, subsequent replacement, and removal after completion of the work for each curing facility used on the project.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION  
  
SPECIAL PROVISION  
FOR  
**TRAFFIC CONTROL QUALITY AND COMPLIANCE**

OPR:JJG

1 of 2

APPR:CER:DBP:01-20-11  
FHWA:APPR:06-20-11

**Delete the subsection 812.03.C, Deficient Traffic Control Operations on page 601 of the Standard Specifications for Construction in its entirety, and replace with the following.**

**C. Deficient Traffic Control Operations.**

**1. Traffic Control Quality and Compliance.** The following applies to all aspects of the traffic control plan and traffic control devices except the Type D lights on plastic drums which are covered elsewhere in the contract.

**a. Traffic Control not Anticipated in Design.** If at any time during the project, including the time during the seasonal suspension, the Engineer documents that the traffic control requires improvements beyond the scope of the Traffic Control Plan, the Engineer will provide written instructions to the Contractor and traffic control supplier what improvements are required. The Contractor must develop and submit to the Engineer for approval, a written implementation schedule for improvements. If the schedule is not approved, or if the schedule is approved but is not followed, the Department will adjust the contract according to subsection 812.03.C.1.c.iii. If the implementation schedule is not followed, the Engineer will notify the Contractor and traffic control supplier in writing that they are in violation of this subsection. The work of making traffic control improvements directed by the Engineer that are beyond the scope of the Traffic Control Plan will be paid for as extra work.

**b. As Designed Traffic Control.** If at any time during the project, including the time during the seasonal suspension, the Engineer documents that the traffic control is deficient, inadequate or improperly placed, the Engineer will provide written notification with instructions for corrective action to the Contractor and traffic control supplier. Upon receipt of the notification of corrective action, the Contractor has 4 hours to correct the traffic control. If the traffic control cannot be corrected within the 4 hour time period, the Contractor will develop a written implementation schedule for the corrective action and submit the schedule to the Engineer for approval within 1 hour of receiving the written notification. If the schedule is not approved, or if the schedule is approved but is not followed, the Department will adjust the contract according to subsection 812.03.C.1.c.iii. If the implementation schedule is not followed, the Engineer will notify the Contractor and traffic control supplier in writing that they are in violation of this subsection.

**c. Corrective Action.** The Engineer will give written notification to the Contractor as identified above. Failure to make corrections within the timeframe required may result in the following actions by the Engineer:



- i. Stop work on the project until the Contractor completes corrective action,
- ii. Order corrective action by others in accordance with subsection 107.07, subsection 108.02, subsection 812.03.B, and in the interest of public safety.
- iii. A contract price adjustment will be made in the amount of \$100 per hour for every hour or portion thereof the improvements or corrective action remains incomplete as described herein. If improvements or corrections have not been made to the satisfaction of the Department, the contract will be adjusted until the traffic control is acceptable.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**PRICE ADJUSTMENTS FOR AUTHORIZED EXTENSIONS OF TIME**

CFS:MB

1 of 2

APPR:JJG:CRB:02-01-18  
FHWA:APPR:02-02-18

**Delete section 812.04.U, Price Adjustments for Authorized Extensions of Time, on page 631 and 632 of the Standard Specifications for Construction in its entirety and replace with the following.**

**U. Price Adjustments for Authorized Extensions of Time.** The Department will not adjust the unit price for **TS, Temp, Furn** for authorized extensions of time.

The Department will not make price adjustments for temporary traffic control devices, **Minor Traf Devices**, and **Traf Regulator Control** during authorized extensions of time if liquidated damages are assessed in accordance with subsection 108.10. If liquidated damages are not assessed, the Department will adjust unit prices for the following:

1. **TS, Temp, Oper;**
2. **PTS System, Temp, Oper;**
3. Items designated as Furnished, Operated, or Standby, unless otherwise specified;
4. Items paid for as Each or Foot as documented by the Department and maintained on the Department website at:  
[http://www.michigan.gov/mdot/0,4616,7-151-9622\\_11044\\_11367---,00.html](http://www.michigan.gov/mdot/0,4616,7-151-9622_11044_11367---,00.html); and
5. Items measured as lump sum if they are used or required on the worksite during authorized extensions of time except that **Minor Traf Devices** will not be adjusted when conspicuity tape is the only minor traffic control device in service or required during the authorized extension of time.
6. Items not in use reserved by the Engineer as standby.

The Department will use the following formula to calculate the unit price adjustments. The adjustment for **Minor Traf Devices** will be at a daily rate of (A/B) not to exceed \$900.00 per calendar or work day and the adjustment for **Traf Regulator Control** will be at a daily rate of (A/B) not to exceed \$650.00 per calendar or work day. When calculating the adjustment, either calendar or working days will be used for both original contract time and additional days.

$(A/B) \times C = \text{unit price adjustment}$

Formula 812-1

where:

A = Original contract unit price

B = Original contract time

C = Additional days the item was in use or required to be on standby during the authorized extension of time.

The Department will determine the number of additional days the item is on standby or in use in calendar days.

For calendar date projects, the original contract time will be calculated as the number of calendar days from the actual start date to the following order of precedence date as identified within the contract:

- a. The latest Open to Traffic date if removal of all traffic control devices coincides with this date.
- b. The latest interim completion date for each season of work if all contract work must be completed in its entirety except turf establishment and watering and cultivating.
- c. The original contract completion date.

For work day projects if an authorized extension of time extends into the next construction season, including seasonal suspension periods during which a traffic control item is on standby or in use, the original contract time will be the calendar days between the first work day and the expiration of the original contract completion.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**PAYMENT FOR MINOR TRAFFIC DEVICES AND TRAFFIC REGULATOR CONTROL**

OPR:JJG

1 of 1

APPR:BJO:DBP:07-19-11  
FHWA:APPR:07-19-11

**Delete Table 812-1 in subsection 812.04.E, on page 625 of the Standard Specifications for Construction, in its entirety and replace with the following.**

**Table 812-1 Partial Payment Schedule for Minor Traf Devices and Traffic Regulator Control**

| Percent of Original Contract Amount Earned | Total Percent of Unit Price Paid |
|--|----------------------------------|
| First Use                                  | 15                               |
| 25   | 30                               |
| 50   | 55                               |
| 75   | 80                               |
| 90   | 100                              |

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**MEASUREMENT AND PAYMENT OF TEMPORARY TRAFFIC CONTROL DEVICES**

OFS:CRB

1 of 1

APPR:MWB:JJG:02-27-14

FHWA:APPR:03-04-14

**Delete subsection 812.04.A.4, on page 624 of the Standard Specifications for Construction in its entirety.**

**Delete the second paragraph of subsection 812.04.C, on page 624 of the Standard Specifications for Construction in its entirety, and replace with the following:**

The Engineer will measure **Sign, Type \_\_, Temp, Prismatic, Furn** as the total cumulative area of the maximum number of each sign legend that is in use during the course of the project unless previously paid. The unit price for **Sign, Type \_\_, Temp, Prismatic, Furn** includes the cost of portable or driven sign supports.

**Delete the second paragraph of subsection 812.04.D, on page 624 of the Standard Specifications for Construction in its entirety, and replace with the following:**

The Engineer will measure **Sign, Type \_\_, Temp, Prismatic, Oper** as the total cumulative area of the maximum number of each sign legend that is in use during the course of the project unless previously paid.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**TYPE III BARRICADES**

DES:DBP

1 of 1

APPR:MWB:CRB:08-07-15  
FHWA:APPR:08-23-15

**Delete the first sentence for the second paragraph in subsection 812.03.D.8 on page 606 of the Standard Specifications for Construction, and replace with the following:**

Light Type III barricades with two, Type C or Type D warning lights, fastened to the uprights above the top rail, provided these warning lights each weigh 3.3 pounds or less.

**Delete the following pay items from the list in subsection 812.04 on page 622 of the Standard Specifications for Construction.**

|   |      |
|---|------|
| Barricade, Type III, High Intensity, Furn.....                | Each |
| Barricade, Type III, High Intensity, Oper .....               | Each |
| Barricade, Type III, High Intensity, Double Sided, Furn ..... | Each |
| Barricade, Type III, High Intensity, Double Sided, Oper ..... | Each |

**Renumber the existing subsection 812.04.A.5 on page 624 of the Standard Specifications for Construction, as follows:**

4. The manufacturer's invoiced cost for damaged equipment included in a lump sum pay item for maintaining traffic.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**PAYMENT OF TEMPORARY TRAFFIC CONTROL DEVICES**

OFS:CRB

1 of 1

APPR:CGB:MB:08-26-16  
FHWA:APPR:09-13-16

**Delete subsection 812.04.A Damage Compensation, on page 623 of the Standard Specifications for Construction, in its entirety and replace with the following:**

**A. Damage Compensation.** Notify the Engineer of damaged temporary traffic control devices. Before replacement and disposal, allow the Engineer to verify the condition of damaged temporary traffic control devices eligible for payment. Damage will be assumed to have occurred from vehicular traffic unless otherwise documented. The Department will pay as follows, for replacing temporary traffic control devices or equipment that are placed appropriately and damaged by vehicular traffic, other than the Contractor's vehicles and equipment.. Devices will be assumed to be placed appropriately unless otherwise documented. Replacement will be made up to project completion (excluding water and cultivating), as follows:

1. The **Furnished** unit price for temporary traffic control devices paid for as furnished pay items, excluding Plastic Drums and 42 inch channelizing devices;
2. The unit price for devices not paid for as **Furnished**;
  - a. Plastic Drums and 42 inch Channelizing Devices will be paid for at a set rate of \$35 per Plastic Drum and \$18 per damaged 42 inch Channelizer.
    - i. Prior to payment the Plastic Drum or 42 inch Channeling Device must be classified as unacceptable, per the ATSSA Quality Guidelines for Temporary Traffic Control Devices and Features (ATSSA QG), and spray-painted with an X.
    - ii. All Plastic Drums and 42 inch Channelizing Devices that are classified as marginal, per the ATSSA QG, during the project, will have blue survey ribbon tied to the handle. MDOT will be responsible for marking marginal devices. Removal and replacement will take place as defined under the Quality Classifications and Requirements Section of the ATSSA QG and will be at no additional cost to the Department.
      - If at any time, any Contactor, is witnessed tampering with the marginal marking method, the Engineer may require all marginal devices on the project to be upgraded to acceptable outside the timeframes detailed in the ATSSA QG.
3. The manufacturer's invoice cost for devices required by the Engineer and not included in the unit price for other relevant pay items;
4. The manufacturer's invoiced cost for damaged equipment included in a lump sum pay item for maintaining traffic.

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**USE OF 42-INCH CHANNELIZING DEVICES**

OFS:RAL

1 of 1

APPR:CRB:MB:06-30-17  
FHWA:APPR:07-21-17

**Delete subsection 812.03.D.6, on page 605 of the Standard Specifications in its entirety and replace it with the following:**

6. **42-inch Channelizing Devices.** Provide and install 42-inch tall, retro-reflective plastic channelizing devices as shown on the plans, or directed by the Engineer. Do not attach lights.
- a. **Daytime Use.** The Department will allow the daytime use of 42-inch channelizing devices in tapers and tangents for the following:
- i. Capital Preventative Maintenance (CPM) projects, pavement marking, chip seal, microsurface, and crack-filling projects;
  - ii. Any projects where the use of plastic drums restricts proposed lane widths to less than 11 feet, including shy distance; or
  - iii. Work durations of 12 hours or less.

The devices must be placed such that spacing does not exceed the maximum values described in Table 812-1:

| <b>Table 812-1</b>                                      |              |                |
|---|--------------|----------------|
| <b>Maximum Spacing for 42-inch Channelizing Devices</b> |              |                |
| <b>Work Zone Speed Limit</b>                            | <b>Taper</b> | <b>Tangent</b> |
| < 45 mph  | 1.0 S        | 2.0 S          |
| ≥ 45 mph  | 50 feet      | 100 feet       |
| S=Work Zone Speed Limit (mph)                           |              |                |

- b. **Nighttime Use.** The Department will allow the nighttime use of 42-inch channelizing devices in tangents and tapers for the following:
- i. Capital Preventative Maintenance (CPM) projects, pavement marking, chip seal, microsurface, and crack-filling projects;
  - ii. Any projects where the use of plastic drums restricts proposed lane widths to less than 11 feet, including shy distance; or
  - iii. Work durations of 12 hours or less.

Place the devices a maximum distance of 50 feet apart in tangent sections, and a maximum of 25 feet apart in tapers. These spacing requirements apply for all speed limits.



## **SUPPLEMENTAL SPECIFICATIONS**

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SUPPLEMENTAL SPECIFICATION  
FOR  
ERRATA TO THE 2012 STANDARD SPECIFICATIONS

1 of 30

08-01-17

| Page | Subsection | Errata   |
|------|------------|--|
| 3    | 101.02     | Modify the abbreviation reading "AIS" to read "AISI".  |
| 4    | 101.02     | Delete the following abbreviations and the long forms<br>MDELEG<br>MDNRE<br>Add the following abbreviations and the long forms<br>MDNR Michigan Department of Natural Resources<br>MDEQ Michigan Department of Environmental Quality<br>MDLARA Michigan Department of Licensing and Regulatory Affairs<br>NESC National Electrical Safety Code                                       |
| 27   | 103.02.B.2 | Change the last sentence of the first paragraph to read "For decreases below 75 percent, the maximum allowable payment for work performed, including any adjustment, will not exceed an amount equal to 75 percent of the original contract quantity times the contract unit price."   |
| 34   | 104.05     | The first sentence of this subsection should read "If the Contractor performs unauthorized work (work performed without the inspections required by the contract, extra work performed without Department approval, work performed contrary to the inspectors direction, or work performed while under suspension by the inspector), the Engineer may reject the unauthorized work." |
| 46   | 104.12     | Add the following to the end of the first paragraph "The use of right-of-way in wetlands and floodplains, or the crossing of water courses by construction equipment is prohibited."   |
| 53   | 105.09     | Add the following to the end of the second paragraph "Any specifically produced material not purchased by the Department, will remain the Contractors and must be removed from the project prior to final acceptance."   |
| 56   | 107.02.B.2 | This sentence should read "U.S.Army Corps of Engineers' Section 404, Dredge and Fill; and Section 10, Navigable Waterway."   |
| 56   | 107.02.B   | Add the subsection reading as follows:<br>"3. U.S. Coast Guard Section 9, Navigable Waterway."<br><br>Change "MDNRE" to "MDEQ" in this subsection.   |

- 64 107.12 Change the first sentence of the first paragraph to read:  
 “For protection of underground utilities and in accordance with 2013 PA 174, the Contractor must notify Miss Dig at least 3 work days, excluding Saturdays, Sundays and holidays, before beginning each excavation in areas where public utilities have not been previously located.”
- 65 107.15.A Change "MDNRE" to "MDEQ" in four instances in this subsection.
- 66 107.15.A.3 Add the following to the end of the paragraph "Note that a burn permit from the MDNR is required for any open burning whenever the ground is not snow covered. Any individuals that allow a fire to escape will be in violation of the Natural Resources and Environmental Protection Act and will be required to reimburse the costs of suppressing the wild fire."
- 67\* 107.16 The third sentence should read "In State Forests, the Contractor must contact the local Unit Manager, Forest Management Division, MDNR, regarding the work to be performed within or adjacent to the forest land."  
  
 Delete the last sentence of the first paragraph of this subsection.
- 80 108.08.F Delete the second paragraph in its entirety.
- 80 108.08.G Add the following new subsection:  
 “G. The Contractor may propose and the Engineer may approve another equitable method, supported by an acceptable rationale to determine time extensions for any of the excusable delays listed in subsection 108.08.
- 83 108.10.C Change the last sentence of the first paragraph to read:  
 “The liquidated damages may contain one or more components of damages added together.”
- 83 108.10.C.1 In Table 108-1 delete the last row of the table and replace it with the following:  

|             |       |
|-------------|-------|
| ≥50,000,000 | 4,500 |
|-------------|-------|
- 102 109.05.E.1 Change the second sentence of the third paragraph to read:  
 “Provide the content specified in subsection 109.05.D.11 for the applicable items in this statement and as follows:”
- 107 150.04 Change the following pay item reading “Mobilization, Max \_\_\_” to read “Mobilization, Max (dollar)” at nine locations throughout the subsection.
- 112 201.03.A.3.b Change "MDNRE" to "MDNR" in three instances in this subsection.
- 150 208.01 Change "MDNRE" to "MDEQ" in this subsection.
- 180 308.03.A Change the first sentence of the second paragraph to read:

- “Do not operate equipment required to place backfill directly on geotextile products.”
- 185 401.03.A Change the first sentence of the second paragraph to read:  
Where unstable soil conditions, or obstructions other than rock, require excavation of the trench below the elevation detailed on the plans; undercut, backfill, and compact the trench as directed by the Engineer.
- 188 401.03.H Change the second sentence of the paragraph to read “Jack steel pipes in place in accordance with subsection 401.03.G”.
- 189 401.03.N Add the following sentence to the end of the first paragraph "Where possible, maintain the stream flow thru a temporary channel or temporary culvert."  
  
The second sentence of the second paragraph should read "Direct water from the dewatering operations through a filter bag before discharging to an existing drainage facility."
- 189 401.04 Change the fourth pay item from the end of the list to read as follows:  
“Culv, Reinf Conc Ellip, (shape) CI \_\_, (rise) inch x (span) inch”.
- 190 401.04 Change the fourth pay item from the end of the list to read as follows:  
“Steel Casing Pipe, \_\_ inch, Tr Det \_\_.”
- 195 402.03.C Change the third sentence of the first paragraph to read as follows:  
“Wrap pipe joints, with a diameter greater than 24 inches, using geotextile blanket.”
- 200 402.04 Change the third pay item from the top of the list to read as follows:  
“Sewer, CI \_\_, \_\_ inch, Jacked in Place”
- 200 402.04.A Change the last sentence of the subsection to read as follows:  
“The unit price for **Sewer** and **Sewer, Reinf Conc, Ellip** includes the cost of excavation, backfill, geotextile blanket and mandrel testing.”
- 201\* 402.04.H Change the last sentence of the first paragraph to read "The Department will not make an adjustment in the pay items of **Minor Traf Devices** or **Traf Regulator Control**."
- 208 403.04.D.3 Change the sentence to read:  
“Removing and replacing pavement adjacent to the adjusted cover per Standard Plan R-37 Series.”
- 218 406.03.A.2 Change the first sentence of the first paragraph to read:  
“Design precast box culverts less than 10 feet in span length measured along the centerline of the roadway in accordance with current AASHTO LRFD Bridge Design Specifications and ASTM C 1577.”  
  
Add the following sentence to the end of the first paragraph:

|      |            |  |
|------|------------|--|
|      |            | “Design precast box culverts greater than or equal to 10 feet in span length measured along the centerline of the roadway for HL-93 Modified live load.”   |
| 219  | 406.03.B   | Change the first sentence of the first paragraph to read:<br>“Submit shop drawings for culverts greater than or equal to 10 feet in span length measured along the centerline of the roadway to the Engineer, for review and approval in accordance with subsection 104.02.”   |
| 219  | 406.03.C.1 | Change the second sentence of the first paragraph to read:<br>“Before manufacture, perform load ratings on precast three-sided, arch or box culverts greater than or equal to 10 feet in span length measured along the centerline of the roadway, in accordance with the AASHTO Manual of Bridge Evaluation, Section 6, Part A, the Michigan Bridge Analysis Guide current at the time load rating is performed, and the Michigan Structure Inventory and Appraisal Guide.” |
| 223  | 406.03.G   | Add the following after the first sentence of the second paragraph:<br>“Where possible, maintain the stream flow thru the existing channel, temporary channel, or temporary culvert.”  |
| 224  | 406.03.G   | Replace the fifth paragraph of this subsection with the following:<br>“The Contractor may use cast-in-place wing walls, headwalls, and aprons, as alternatives to precast wing walls, headwalls, and aprons. Attach cast-in-place wing walls or headwalls as shown on the shop drawings.”  |
| 225  | 406.03.G.2 | Change the third sentence of the first paragraph to read:<br>“Before placing the open-graded aggregate 34R, compact the coarse aggregate 6A using at least three passes of a vibrating plate compactor.”   |
| 226  | 406.03.G.2 | Change the first sentence of the second paragraph of this subsection to read:<br>"Fill the space between the box culvert joints during placement of box sections with closed-cell rubber extrusion type gaskets in accordance with ASTM C 990."  |
| 226  | 406.04.A.9 | Change the sentence to read:<br>“Providing plan modifications including design, additional plan quantities and pay items to accommodate any changes to the precast units as shown on the plans.”   |
| 226* | 406.04.A   | Add the following paragraph after the last paragraph of the subsection:<br>“The substructure design is specific to the three-sided or arch culvert detailed on the plans. The Contractor must use approved MDOT service vendors qualified in Hydraulics, Geotechnical Engineering Services, and Short and Medium Span Bridges to perform the required design and   |

- plan modifications, as directed by the Engineer, if the Contractor selects a culvert shape different than shown on the plans.”
- 227 406.04.B Add the following new item in the list of items in this subsection:  
2. Headwalls, wingwalls, aprons, and curtain walls, precast or cast-in-place;
- Renumber the exist items 2 through 4 in this list to read 3 through 5.
- Delete existing item numbered 5 and replace with the following:  
6. Inserts for bars and connection hardware; and
- Renumber the existing item 6 in this list to read 7.
- 227 406.04.B Delete the first and second paragraphs following the list of items in this subsection and replace with the following:  
“The Department will pay separately for cast-in-place concrete, other than for culvert segments, wing walls, and headwalls; excavation; protective coating; providing and placing backfill material; by plan quantity in accordance with subsection 109.01.A.”
- 239 501.03.C.6 The first sentence of this subsection should read "Except as specified in subsection 501.03.C.4, removing HMA surface applies to removing HMA overlying a material designated for removal or that is required to remain in place."
- 247 501.03.O Change footnote e in Table 501-5 to read:  
"Flushing severe enough to significantly affect surface friction (Friction Number <35)."
- 249 501.04.H The first sentence of this subsection should read "The Engineer will measure, and the Department will pay for removing HMA surface, no greater than 12 inches thick, overlying a material designated for removal or that is required to remain in place, as **HMA Surface, Rem.**"
- The second paragraph of this subsection should read "The Engineer will measure, and the Department will pay for removing HMA surface, greater than 12 inches thick, overlying a material designated for removal or that is required to remain in place, as **Pavt, Rem** in accordance with subsection 204.04."
- 257 503.03.E Delete this subsection in its entirety.
- 265 504.03.E.3 Delete this subsection in its entirety.
- 269 504.04.A This subsection should read "The unit prices for **Micro-Surface**, regardless of the type required, include cleaning existing pavement; applying a bond coat; temporary pavement markings; stationing; corrective action; and traffic control to complete corrective action."

- 299 601.04 In table 601-2 delete the row for Grade P-NC concrete in its entirety.
- 300 601.04 In table 601-2, the first sentence of footnote b. should read:  
 “Use coarse aggregate 6A, 6AA or 6AAA for Grades P1, P2 and M.”
- In table 601-2, footnote c. should read:  
 “The mix design basis for bulk volume (dry, loose) of course aggregate per unit volume of concrete is 72% for Grade P1; 74% for Grade P2.”
- 308 602.03.F Note c. in Table 602-1 should read "Refer to Section D6 of the Materials Quality Assurance Procedures Manual for inspection procedure."
- 320 602.04.C.3 The last paragraph in this subsection should read "If the Engineer approves a substitution of a higher concrete grade for a lesser grade (e.g., P1 for P2), the Department will pay for the higher grade of concrete using the original bid and pay items of the lesser grade."
- 327 603.02 Change the second material in the list to read:  
 “Concrete, Grade P-NC.....603”
- Change the third material in the list to read:  
 “Base Course Aggregate, 4G, 21AA, 22A.....902”
- 334 603.03.B.10 Change the last sentence of the second paragraph to read "Apply the required curing compound in two coats, at a rate of at least 1 gallon per 25 square yards for each coat."
- 342 603.04.G.3 Change "D1" to "W" in two instances in this subsection.
- 351 701.04 Replace Tables 701-1A and 701-1B with the Table 701-1 below.
- 362 704.03.C Change the last sentence in the first paragraph of this subsection to read: “The Engineer will consider approval after receiving applicable MDEQ permits for the alternate method.”
- 372 705.03.C.1 Add the following sentence after the first paragraph of this subsection:  
 “Do not drive piles within a radius of 25 feet of newly placed concrete until the concrete attains at least 75 percent of its specified minimum strength.”
- 374 705.03.C.2.c Change the last sentence of the second paragraph to read “Drive test piles to the minimum pile length or practical refusal, whichever is greater”.
- 379 705.04 Change the fifth item down the list to read:  
 “Pile, Galv (Structure No.)”
- 380 705.04 Change the last item in the list to read:  
 “Pile Driving Equipment, Furn (Structure No.)”

- 383 706.02 The fourth paragraph following the list of materials should read "Provide AASHTO M 270, Grade 36 steel, meeting the requirements of ASTM A 786, galvanized in accordance with section 707, for expansion joint cover plates. Provide plates at least 3/8 inch thick. Use plates with a slip resistance equal to or greater than those meeting the requirements of ASTM A 786 and must be approved by the Engineer. Provide ASTM F 593 (Type 304) stainless steel, 3/4-inch or 1/2-inch diameter, flathead countersunk screws with 3/4-inch or 1/2-inch diameter inserts for use in expansion joint cover plates."
- 389 706.03.D.4.b Change the first sentence of the fourth paragraph to read "Design forms, form supports, and attachments to carry dead loads, and resultant horizontal loads due to forming of cantilever overhangs."
- 390 706.03.E.4 Change the fourth sentence of the first paragraph to read: "Use wire ties to secure all bar intersections for the top mat. Use wire ties to secure all bar intersections for other mats where the product of the length and width of bar intersection spacing exceeds 120 square inches."
- 391 706.03.E.8 Change the first sentence of the second paragraph of this subsection to read: "Patch sawed or sheared ends and visible defects in accordance with ASTM A 775."
- 392 706.03.E.8 Change the last sentence of the third paragraph of this subsection to read: "Coat mechanical splices after splice installation in accordance with ASTM A 775 for patching damaged epoxy coating."
- 394 706.03.H.1 Delete the last paragraph on page 394 and replace it with the following: "Do not cast sidewalk, curb, or barrier pours until the deck concrete attains at least the minimum specified 7-day flexural or compressive strength, and after completion of the 7-day continuous wet cure. The forming of succeeding portions may occur, provided the wet cure is maintained."
- 406\* 706.03.N.1.b Add the following to the end of the last paragraph of the subsection: "Do not discontinue wet cure nor cast succeeding portions onto the bridge deck prior to completion of the 7-day two-phase continuous wet cure. Ensure excess or ponding cure water is removed prior to casting of succeeding structure portions."
- 416 707.03.C.1 Change the title of the subsection from "Shop Plans to read "Shop Drawings".
- Change the second sentence of this subsection to read: "Do not use design drawings in lieu of shop drawings."



|      |              |   |
|------|--------------|---|
| 426  | 707.03.C.17  | Change the second sentence in the first paragraph of this subsection to read:<br>"Tap oversized galvanized nuts in accordance with ASTM A 563 or AASHTO M 292 and meet Supplementary Requirement S1 of ASTM A 563 or AASHTO M 292."   |
| 430  | 707.03.D.7.b | Delete the first sentence of the last paragraph of this subsection.   |
| 430* | 707.03.D.7.b | Change the title of the Table 707-4 to read:<br>"Minimum Bolt Tension for ASTM F 3125 Grade A 325"  |
| 430  | 707.03.D.7.b | Change "104,000" to "103,000" in the last row under the column titled Minimum Bolt Tension.   |
| 431  | 707.03.D.7.c | Add the following sentence to the end of the first paragraph of this subsection:<br>"If using impact wrenches, provide wrenches sufficient to tighten each bolt in approximately 10 seconds."   |
| 431* | 707.03.D.7.c | Change the first sentence of the second paragraph to read:<br>"Do not reuse ASTM F 3125 Grade A 325 bolts and nuts.."   |
| 434  | 707.04.A     | Change the first sentence of the first paragraph of this subsection to read:<br>"The Engineer will measure structural steel by the calculated weight of metal in the finished structure, excluding filler metal in welding, as shown on the shop drawings or working drawings."                               |
| 438  | 708.03.A.2   | Change the title of the subsection from "Shop Plans to read "Shop Drawings".<br><br>Change the first sentence to read:<br>"Submit shop drawings in accordance with subsection 104.02."<br><br>Change the fourth sentence to read:<br>"Do not start production until the Engineer approves the shop drawings." |
| 441* | 708.03.A.11  | Change the last sentence of the first paragraph to read "Cure concrete at temperatures from 70 °F to 150 °F until concrete attains the release strength shown on the shop drawings".  |
| 441  | 708.03.A.11  | Change the fourth sentence of the fourth paragraph to read "Do not exceed a maximum concrete temperature of 150 °F during the curing cycle."  |
| 458  | 711.03.A     | Change the first sentence in the first paragraph to read:<br>"Shop drawings for structural steel and pipe railings are not required."   |
| 460  | 711.04.A     | Change the second sentence of the first paragraph to read:  |

|      |            |   |
|------|------------|---|
|      |            | “The unit price for <b>Bridge Barrier Railing</b> includes the cost of placing steel reinforcement, providing and placing concrete, constructing joints, and forming, finishing, curing and protecting the concrete.”   |
| 461  | 711.04.F   | The title of this subsection should read " <b>Reflective Marker, Permanent Barrier.</b> "   |
| 467  | 712.03.C   | Add the following to the end of the third paragraph of the subsection:<br>“Notify the Engineer of any saw cuts in the top flange. Saw cuts equal to or less than 1/32 inch deep in steel beams must be repaired by grinding, to a surface roughness no greater than 125 micro-inches per inch rms, and tapering to the original surface using a 1:10 slope. Saw cuts in excess of 1/32 inch deep in steel beams require a welded repair to be submitted to the Engineer for approval. Weld in accordance with subsection 707.03.D.8 and provide adequate notice to allow the Engineer to witness the repair work. Inspect and test all saw cut repairs (including grinding repairs) using ultrasonic testing in accordance with 707.03.D.8.c at no additional cost to the Department.”  |
| 471  | 712.03.J   | Add the following to the end of the second paragraph of the subsection:<br>“Select adhesive anchor systems from the Qualified Products List.”   |
| 471  | 712.03.J.1 | Delete the first paragraph in this subsection and replace it with the following: “Propose complete details of drilling, cleaning, and bonding systems for anchoring reinforcement and submit for the Engineer’s approval before use. The minimum embedment depth must be nine times the anchor diameter for threaded rod or bolt and twelve times the anchor diameter for reinforcing bar. Propose a drilling method that does not cut or damage existing reinforcing steel. Prepare at least three proof tests per anchor diameter and type in the same orientation in which they will be installed on the existing structure, on a separate concrete block, in the presence of the Engineer. The Engineer will proof test the proposed systems. The Engineer will base approval of the anchoring system on the following criteria:” |
| 471  | 712.03.J.2 | Change the third sentence of the first paragraph to read:<br>“Use a tension testing device for unconfined testing, in accordance with ASTM E 488.”  |
| 473  | 712.03.L.2 | Change the first sentence in the second paragraph of this subsection to read:<br>"If using epoxy coated steel reinforcement, epoxy coat mechanical reinforcement splices in accordance with ASTM A 775."  |
| 473  | 712.03.L.3 | Delete the existing first sentence in the first paragraph.  |
| 473  | 712.03.L.3 | Change the third sentence of the first paragraph to read "Provide two test splices on the largest bar size."  |
| 473* | 712.03.L.3 | Change the sentence beginning “Demonstrate to the.... to read:  |

- “Demonstrate to the Engineer that splices have a tensile strength of 125 percent of the bar yield strength and high strength splices have a tensile strength of 150 percent of the bar yield strength.”
- 488      713.02      Add the following as subsection 713.02.C:  
 "C. **Structural Steel for Retrofitting and Welded Repairs.** Structural steel material used for retrofitting and welded repairs of primary members as defined in subsection 707.01.B must meet longitudinal Charpy V-Notch impact test requirements."
- 501      715.02      Add the following material reference above the two existing items:  
 “Sealant for Perimeter of Beam Plates .....713”
- 508      715.03.D.1      Add the following sentence after the second paragraph of the subsection:  
 “Apply sealant for perimeter of beam plates in accordance with subsection 713.03.F.”
- 515      716.03.A      Delete the second paragraph of this subsection in its entirety.  
  
 Change the last sentence of the last paragraph of this subsection to read:  
 “Provide a primer dry film thickness for the top flange between 4 mils and 10 mils.”
- 519      716.04      Change the second sentence of the first paragraph of this subsection to read:  
 "The unit price for **Field Repair of Damaged Coating (Structure No.)** includes the costs of making field repairs to the shop applied coating system; prime coat surfaces and exposed surfaces of bolts, nuts, and washers; and repairing stenciling."
- 521      717.04.B      This subsection should read "The unit price for **Drain Casting Assembly** includes the cost of providing and installing the downspout and, if necessary, the lower bracket to the drain casting."
- 522      718.02      Change the section number "906" in the third material in the list to read "919."
- 533      718.04      Delete the following pay item from the list:  
 Temp Casing .....Foot
- 533      718.04.B.2      Delete this subsection in its entirety.
- 533      718.04.B.3      Renumber this subsection as follows:  
 “2. **Permanent Casing.**”
- 540      802.04      Change "Non reinf" in the last pay item of the list with "Nonreinf".
- 545\*      803.04.E      Change the second sentence of the second paragraph to read:

- “The unit price for **Railing for Steps** includes the cost of providing, fabricating, installing, and grouting the railing.”
- 560 807.04 Delete the following pay item from the list:  
Guardrail Buffered End .....Each
- 560 807.04.B Change the fifth paragraph of this subsection to read:  
“The Engineer will measure **Guardrail Salv** and **Guardrail, Mult, Salv** along the face of the rail (one face for multiple beams), including terminals and end shoes.”
- 567 808.04.C Change the first paragraph of this subsection to read:  
"The Department will not pay separately for protective fence required in accordance with subsection 104.07."
- 569 809.04.A Change the first sentence to read:  
“The unit price for **Field Office, CI** \_\_\_ includes the cost of setup, providing access, grading, maintaining, plowing snow, and utility hook-up charges.”
- 570 809.04.B Delete the existing second and third sentences in the first paragraph and replace them with the following:  
“The unit price for **Field Office, Utility Fees** includes the cost of monthly usage fees for electricity, gas, telephone service and charges, fuel for the stove, monthly water and sanitary service.”
- 570 809.04.B Change the existing fourth sentence in the first paragraph to read:  
“The Department will reimburse the Contractor for monthly usage fees for electricity, gas, telephone, water and sanitary charges incurred by the Department.”
- 575 810.03.K Change the subsection to read  
"K. **Drilled Piles for Cantilever and Truss Foundations.** Construct drilled piles for cantilever and truss foundations in accordance with section 718."
- 578 810.03.N.2 Add the following sentence after the first sentence of the second paragraph on this page:  
"Mark each nut and bolt to reference the required rotation."
- 584 810.04 Delete the last pay item in the list:  
Truss Fdn Anchor Bolts, Replace.....Each
- 585 810.04.B.1 Change the second paragraph to read:  
“The unit prices for **Fdn, Truss Sign Structure Type** \_\_, \_\_ inch Dia, **Cased** and **Fdn, Cantilever Sign Structure Type** \_\_, \_\_ inch Dia, **Cased** include the cost of concrete, slurry, steel reinforcement, permanent casings, anchor bolts, excavation, and disposal of excavated material.”

- 585 810.04.B.2 Change the second sentence of the first paragraph to read:  
 “The unit prices for **Fdn, Truss Sign Structure Type** \_\_, \_\_ inch Dia, **Uncased** and **Fdn, Cantilever Sign Structure Type** \_\_, \_\_ inch Dia, **Uncased** include the cost of concrete, slurry, steel reinforcement, temporary casings, anchor bolts, excavation, and disposal of excavated material.”
- 596 811.03.G Delete this subsection in its entirety.
- 597\* 811.03.H Rename this subsection as follows:  
**“G. Raised Pavement Marker (RPM) Removal.”**
- 597\* 811.04 Change "Crosshatching" in the last pay item of the list on this page to "Cross Hatching".
- 598\* 811.04 Delete the following pay items from the list:  
 Pavt Mrkg, (material), 4 inch, SRSM, (color).....Foot  
 Pavt Mrkg, (material), 4 inch, SRSM, 2<sup>nd</sup> Application, (color).....Foot
- Add the following pay items to the list:  
 “Pavt Mrkg, Polyurea, (legend).....Each  
 Pavt Mrkg, Polyurea, (symbol).....Each”
- Change the sixth item down the list to read:  
 “Pavt Mrkg, Polyurea, \_\_ inch, Cross Hatching, (color)”
- Change the eleventh item down the list to read:  
 “Rem Curing Compound, for Longit Mrkg, \_\_ inch.....Foot”
- 599 811.04.B Delete this subsection in its entirety.
- 599 811.04 Rename the following subsections as follows:  
**“B. Call Back.**  
**C. Pavement Marking Removal.**  
**D. Material Deficiency.”**
- 602 812.03.D Change the first sentence to read "Provide and maintain traffic control devices meeting the requirements in the ATSSA Quality Guidelines for Work Zone Traffic Control Devices and Features."
- 603 812.03.D.1 The last sentence on this page should read "Lay the sign behind the guardrail, with the uprights pointing downstream from the traffic, and place the support stands and ballasts close to the guardrail."
- 604 812.03.D.2 The first sentence of the fourth paragraph should read "Do not use burlap or similar material to cover Department or Local Government owned signs."
- 604 812.03.D.5 The fifth sentence of the first paragraph should read "Do not mix drums and cones within a traffic channeling sequence."

|      |                   |   |
|------|-------------------|---|
| 605  | 812.03.D.6.b      | Change the first sentence of the first paragraph to read:<br>"The Department will allow the nighttime use of 42-inch channelizing devices, in the tangent area only, on CPM and pavement marking of any duration where the use of plastic drums restricts proposed lane widths to less than 11 feet, including shy distance." |
| 605  | 812.03.D.7        | Add the following sentence after the first sentence of the first paragraph:<br>"Place a shoulder closure taper in advance of the lighted arrows placed on the shoulders."   |
| 607  | 812.03.D.9        | Delete the second paragraph of this subsection and replace with the following: "Link sections together to fully engage the connection between sections. Maintain the barrier with end-attachments engaged and within 2 inches of the alignment shown on the plans."   |
| 608  | 812.03.D.10.b     | Delete the second sentence of the second paragraph of this subsection beginning with "Install sand module attenuators..."   |
| 608  | 812.03.D.10.b     | Add the following sentence after the second paragraph of this subsection:<br>"Install impact attenuation devices as shown on the plans, as directed by the Engineer, or both."  |
| 609  | 812.03.D.10.e     | Delete the second paragraph of this subsection.   |
| 613* | 812.03.D.14.a.iii | Change the sentence in this subsection to read "Place a terminal end shoe, in accordance with Standard Plan R-66-Series, and of appropriate type based on existing guardrail, on both blunt guardrail ends."  |
| 615  | 812.03.F          | The second sentence of the second paragraph of this subsection should read: "The Contractor may use a Type R temporary pavement marking cover, per subsection 812.03.D.12 when authorized by the Engineer."   |
| 616  | 812.03.F.2        | The last sentence of the first paragraph should read: "If the removal equipment cannot collect all removal debris, operate a self-propelled sweeper capable of continuously vacuuming up the removal debris immediately behind the removal equipment."  |
| 617  | 812.03.G.3        | The first sentence of the second paragraph should read: "Sweep the shoulder and remove debris prior to placing traffic on the shoulder and throughout the time the shoulder is used to maintain traffic."   |
| 617  | 812.03.G.4.a      | Delete "48 inch by 48 inch" from the first sentence of this subsection.   |
| 618* | 812.03.G.7        | The first sentence of the first paragraph should read: "Clean barrier reflectors, plastic drums, 42 inch channelizing devices, tubular markers, signs, barricades, and attached lights in operation on the project to ensure they meet required luminosity."  |

- 619 812.03.G.8 The second sentence of the third paragraph from the end of the subsection should read: "Illuminate traffic regulator stations at night per subsection 812.03.H."
- 621 812.03.I.6 Delete "48 inch by 48 inch" from the second sentence of this subsection.
- 622\* 812.03.J The second paragraph should read "Apply one 2-inch wide horizontal stripe of red and white conspicuity tape along at least 50 percent of each side of, and across the full width of the rear of the vehicle or equipment."
- 622 812.04 Change the second item down the list to read:  
"Traf Regulator Control"
- Change the sixth item down the list to read:  
"Sign Cover, Type I"
- 626 812.04.I Change the reference "812.04.E" in the first sentence to "812.04.D".
- 628 812.04.M.4 Add the following as the first sentence of this subsection:  
"The Engineer will not measure a temporary barrier ending move as **Conc Barrier Ending, Temp, Relocated** if it involves work defined in subsection 812.04.M.3."
- 629 812.04.N.1 Change the reference "811.04.D" in the second paragraph of this subsection to read "811.04.C".
- 630 812.04.S Change the first sentence to read: "The Department will not make additional payments for traffic regulating, signing, arrow boards, and lighting systems for traffic regulator stations operated at night due to a temporary PTS system failure."
- 634 813.03.C.3 Change the reference "903.07.A" in the paragraph of this subsection to read "907.07.B".
- 646 815.04 Change the first, third and fourth pay items in the list to read:  
"Site Preparation, Max (dollar) ..... Lump Sum  
Watering and Cultivating, First Season, Min (dollar)..... Lump Sum  
Watering and Cultivating, Second Season, Min (dollar) ..... Lump Sum"
- 646 815.04.C.1 Change the following pay item reading: "Watering and Cultivating, First Season, Min. (dollar)" to read "Watering and Cultivating, First Season, Min (dollar)" at two locations throughout the subsection.
- 646 815.04.C.1.b Delete this subsection in its entirety.
- 646 815.04.C.1.c Rename this subsection to read:  
"b. Removal and disposal of unacceptable plants."
- 646 815.04.C.2 Change the following pay item reading: "Watering and Cultivating, Second Season, Min. (dollar)" to read "Watering and Cultivating,

|      |              |   |
|------|--------------|---|
|      |              | Second Season, Min (dollar)” at three locations throughout the subsection.  |
| 647  | 815.04.C.2   | Change the last paragraph of this subsection to read:<br>“For each unacceptable plant identified, the Engineer will calculate a 50 percent reduction in the unit price for the relevant <b>(Botanical Name)</b> pay item, and will process a negative assessment for each unacceptable plant for that amount.”  |
| 650  | 816.03.B     | Delete the first paragraph of this subsection and replace with the following:<br>"Conduct soil tests when called for in the contract or when directed by the Engineer. Provide soils tests results to the Engineer when testing is required. Provide and place fertilizer as indicated below and as indicated in the soils tests, if required."   |
| 650  | 816.03.B.1   | Change the sentence to read: "For Class A fertilizer, evenly apply 176 pounds of chemical fertilizer nutrient per acre on a prepared seed bed."   |
| 650  | 816.03.B.2   | Change the sentence to read: "For Class B fertilizer, evenly apply 120 pounds of chemical fertilizer nutrient per acre on a prepared seed bed."   |
| 650* | 816.03.B.3   | Change the sentence to read: "For Class C fertilizer, evenly apply 80 pounds of chemical fertilizer nutrient per acre on established turf."   |
| 663* | 819.01       | Delete the first paragraph in the subsection and replace it with the following:<br>“This work consists of providing operating electrical and lighting units; removing, salvaging, or disposing of existing electrical and lighting components; excavating, backfilling, restoring the site in accordance with section 816; and disposing of waste excavated materials. Complete this work in accordance with this section, section 820, and the contract and to the requirements of the NEC, the National Electrical Safety Code, and the MDLARA for those items not identified in the contract.”<br><br>Change the third sentence of the second paragraph in this subsection to read:<br>“Contact the MDLARA for electrical service inspection and pay the applicable fees.” |
| 671  | 819.03.F.1   | Change the paragraph to read:<br>“Install light standard foundations as shown on the plans and the standard plans, as applicable.”  |
| 673  | 819.03.G.4.b | Change the last sentence of the first paragraph to read:<br>"Tighten the anchor bolts to a snug tight condition as described in the third paragraph of subsection 810.03.N.2 ensuring the lock washer is completely compressed."  |



- 673 819.03.G.4.b Delete the first two sentences of the second paragraph and replace with the following:  
"Tighten bolts connecting the pole to the frangible base to a snug tight condition. Snug tight is the tightness attained by a few impacts of an impact wrench, or the full effort of a person using an ordinary spud wrench. The lock washers must be fully compressed."
- 678 819.04 Change the ninth pay item in the list to read:  
"DB Cable, 600V, 1/C# (size)..... Foot"
- 678\* 819.04 Delete the last item in the list on this page reading:  
"DB Cable, in Conduit, 600 Volt, (number) 1/C# (size) ..... Foot"
- 679 819.04 Change the first pay item in the list to read:  
"DB Cable, in Conduit, 600V, 1/C# (size)..... Foot"
- 679 819.04 Change the sixth pay item in the list to read:  
"Cable, P.J., 600V, 1, (size) ..... Foot"
- 680 819.04 Change the first paragraph to read:  
"Unless otherwise required, the unit prices for the pay items listed in this subsection include the cost of excavation, granular material, backfill, and disposal of waste excavated material. If the contract does not include pay items for restoring the site in kind in accordance with section 816, the Department will consider the cost of restoration included in the pay items listed in this subsection."
- 680 819.04.A Add the following paragraph after the first paragraph of the subsection.  
"The unit prices for **Conduit, Rem** include the cost of removing the type, number, and size of conduit shown on the plans."  
  
Change the third paragraph of the subsection to read:  
"The unit prices for **Conduit, (type), \_\_ inch** and **Conduit, DB, (number), \_\_ inch** include the cost of installing the type, number, and size of conduit shown on the plans, and installing marking tape."
- 681 819.04.B Change the last paragraph of the subsection to read:  
"The unit price for **DB Cable, in Conduit, Rem** includes the cost of removing all cables from the existing conduit measured per lineal foot of conduit."
- 681 819.04.C Change the first paragraph of the subsection to read:  
"The unit prices for **Cable, Rem** and **Cable, (type), Rem** include the cost of dead ending, circuit cutting, installing guying, work required to leave circuits operable, and disposing of the removed cables, wire, hardware, and other appurtenances."
- 681 819.04.D Change the first paragraph of the subsection to read:  
"The unit price for **Cable, Pole, (type), Disman** includes the cost of dismantling and off-site disposal of the following:"

- 685 820.01.D Change the sentence to read:  
"Excavate, backfill, restore the site in kind in accordance with section 816, and dispose of excess or unsuitable material;"
- 688 820.03.C Change the seventh paragraph of this subsection to read:  
"Tighten top anchor bolt nuts, snug, in accordance with the first four paragraphs of subsection 810.03.N.2, except beeswax will not be required."
- 696 820.04 Add the following pay items to the list:  
"Pedestal, Pushbutton, Alum.....Each  
Pedestal, Pushbutton, Rem.....Each"
- 697 820.04.A.2 Change the sentence to read:  
"If the contract does not include pay items for restoring the site in kind in accordance with section 816, the Department will consider the cost of restoration included in the pay items listed in this subsection."
- 698 820.04.B Delete the second paragraph of this subsection found on this page.
- 698 820.04.C Change "**Fdns**" to read "**Fdn**" in four instances in this subsection.
- 701 820.04.J.3 Change the sentence to read: "Installing wires in the saw slots and to the handholes;"
701. 820.04.J Add the following as a new subsection:  
"7. A 3/4 inch minimum flexible conduit (non-metallic and rated for underground use) from the pavement to the handhole."
- 706 821.01.B Change the website address listed after the second paragraph on this page to read:  
"<http://www.ngs.noaa.gov/heightmod/GuidelinesPublications.shtml>"
- 711 822.03.B Change the second paragraph to read:  
"If corrugations are required on concrete shoulders and the method of installation is not shown on the plans or directed by the Engineer, construct corrugations by grinding, or cutting."
- 718 823.03.U Change "MDNRE" to "MDEQ" in four instances in this subsection.
- 720 823.04 Change the pay item seventh from the bottom of the list to read:  
"Water Shutoff, Adj, Temp, Case \_\_\_"
- 730 824.03.Q Change the third sentence of the fourth paragraph to read:  
"Ensure placement of monumentation in accordance with section 821."
- 730 824.03.Q Change the first sentence of the last paragraph to read:  
"The Department will not pay for work dependent on lost or destroyed stakes until the Contractor replaces the stakes."

|      |                  |   |
|------|------------------|---|
| 732  | 824.04           | Change the first sentence of the first paragraph following the list of pay items to read:<br>"If the Engineer determines the Contractor will perform staking as extra work, the Department will pay for staking in accordance with section 103."  |
| 733  | 824.04           | Change the left column header in Table 824-2 to read:<br><b>"Percent of Original Contract Amount Earned"</b>  |
| 739  | 902.02           | Change the last aggregate testing description to read:<br>"Determining Specific Gravity and Absorption of<br>Fine Aggregates.....MTM 321"   |
| 742  | 902.03.C.1.a     | Change the sentence to read:<br>"Coarse aggregate includes all aggregate particles greater than or retained on the 3/4-inch sieve."   |
| 742  | 902.03.C.2.a     | Change the sentence to read:<br>"Intermediate aggregate includes all aggregate particles passing the 3/4-inch sieve through those retained on the No. 4 sieve."   |
| 742  | 902.03.C.2.b.iii | Change the sentence to read as follows:<br>"Maximum Loss by Washing per MTM 108 of 3.0 percent".  |
| 744  | 902.07           | Delete the fourth paragraph of the subsection and replace it with the following:<br>"The Engineer will only allow the use of granular material produced from crushed portland cement concrete for embankment and as trench backfill for non-metallic culvert and sewer pipes without associated underdrains. However, granular material produced from crushed portland cement concrete is not permitted as swamp backfill, nor within the top 3 feet below subgrade regardless of the application." |
| 746* | 902.11           | Change the Item of Work by Section Number column in Table 902-1 for the 6AA row to read: "406, 601, 602, 706, 708, 806".<br><br>Change the Item of Work by Section Number column in Table 902-1 for the 6A row to read: "206, 401, 402, 406, 601, 602, 603, 706, 806".<br><br>Change the Item of Work by Section Number column in Table 902-1 for the 34R row to read: "401, 404, 406".   |
| 751* | 902.11           | Replace Table 902-6 with the Table 902-6 below.   |
| 751  | Table 902-7      | Under the Material column in the fourth row change the "FA2" to read "2FA".   |
| 751  | Table 902-7      | Under the Material column in the fifth row change the "FA3" to read "3FA".  |

|      |             |   |
|------|-------------|---|
| 752  | Table 902-8 | Under the Material column in the fourth row change the "FA2" to read "2FA".   |
| 752  | Table 902-8 | Under the Material column in the fifth row change the "FA3" to read "3FA".  |
| 761  | Table 904-2 | Delete the footnote f and any other reference to footnote f from the table.   |
| 767  | 905.03      | Change the first sentence of the first paragraph to read: "Deformed bars, must meet the requirements of ASTM A 706, ASTM A 615, or ASTM A 996 (Type R or Type A only) for Grade 60 steel bars, unless otherwise required".  |
| 767* | 905.03      | Change the first sentence of the second paragraph to read: "Unless otherwise specified, spiral reinforcement must meet the requirements of plain or deformed Grade 40 steel bars of ASTM A 615, ASTM A 996 (Type A), or the requirements of cold-drawn wire of ASTM A 1064".  |
| 767  | 905.03      | Change the first sentence of the third paragraph to read: "Bar reinforcement for prestressed concrete beams must meet the requirements of ASTM A 996 (Type R) for Grade 60 steel bars, except the Engineer will allow bar reinforcement that meets the requirements of ASTM A 615 or ASTM A 996 (Type A) for Grade 40 steel bars for stirrups in prestressed concrete beams". |
| 768  | 905.03.C    | Change the first sentence in the subsection to read:<br>"Epoxy coated steel reinforcement, if required, must be coated in accordance with ASTM A 775, with the following exceptions and additions."   |
| 768  | 905.03.C.3  | Change the first sentence of this subsection to read:<br>"Include written certification that the coated reinforcing bars were cleaned, coated, and tested in accordance with ASTM A 775 with the coating applicator."   |
| 768  | 905.05      | Change the first sentence of the first paragraph to read: "Deformed steel bars must meet the requirements of ASTM A 706 or the requirements for Grade 40, Grade 50, or Grade 60 of ASTM A 615 or ASTM A 996 (Type R or Type A only)".   |
| 768  | 905.06      | Delete this subsection in its entirety and replace it with the following:<br>"Deformed wire fabric for prestressed concrete and fabric for concrete pavement reinforcement must meet the requirements of ASTM A 1064 and fabricated as required."   |
| 772* | 906.07      | Change the first paragraph to read:<br>"High-strength bolt fasteners for structural joints must meet the requirements of ASTM F 3125 Grade A 325 Type 1 bolts. High-strength nuts for structural joints must meet the requirements of ASTM A 563  |

Grade DH or AASHTO M 292 Grade 2H. High-strength washers for structural joints must meet the requirements of ASTM F 436 Type 1 for circular, beveled, clipped circular, and clipped beveled washers."

Change the second sentence of the second paragraph of this subsection to read:

"Galvanized nuts must be tapped oversize in accordance with ASTM A 563 and meet Supplementary Requirements S1, Lubricant and Rotational Capacity Test for Coated Nuts and S2, Lubricant Dye."

- 777\* 907.03.D.2.a Change the first sentence of the second paragraph to read:  
"Angle sections must be nominal 2½ inch by 2½ inch by ¼ inch."
- 777\* 907.03.D.2.b Change the first sentence of the first paragraph to read:  
"Angle section braces must be nominal 1¾ inch by 1¾ inch by ¼ inch or nominal 2 inch by 2 inch ³/₁₆ inch."
- 782 908.04 Change the first sentence of the first paragraph of this subsection to read:  
"Steel castings for steel construction must meet the requirements of ASTM A 148 for Grade 60/90 carbon steel castings, as shown on the plans, unless the Engineer approves an alternate in writing."
- 783\* 908.09.A Change the title of this subsection and the first sentence to read  
"A. **Base Plates, Angle, and Non-Tubular Post Elements.** Galvanized base plates, angle, rail splice elements, and non-tubular post elements must meet the requirements of ASTM A 36 and ASTM A 123".
- 783\* 908.09.B Change the title of this subsection and the first sentence to read  
"B. **Rail Elements and Tubular Post Elements.** Rail elements and tubular post elements must meet the requirements of ASTM A 500, for Grade B and subsection 908.09.B and be galvanized in accordance with ASTM A 123".
- 784\* 908.09.C Change this subsection to read:  
"C. **Hardware.** Railing anchor studs must meet the requirements of ASTM A 449 Type 1. Heavy hex nuts must meet the requirements of ASTM A 563. Bolts, used as rail fasteners, must meet the requirements of ASTM F 3125 Grade A 325, Type 1. Where called for, round head bolts must meet the requirements of ASTM A 449 Type 1. The material for the railing hand hole screws must meet the requirements of ASTM A 276, Type 304. All nuts must meet the requirements of ASTM A 563 Grade DH or AASHTO M 292 Grade 2H. All flat washers must meet the requirements of ASTM F 436. Lock washers must be steel, regular, helical spring washers meeting the requirements of ANSI B18.21.1 - 1972. Bolts, nuts, washers and other hardware must be hot-dip galvanized in accordance with AASHTO M 232. Galvanized nuts must be tapped oversize in accordance with ASTM A 563, and meet

Supplementary Requirements S1, Lubricant and Rotational Capacity Test for Coated Nuts, and S2, Lubricant Dye.”

- 784 908.11.A Change the first sentence of the first paragraph to read:  
“Steel beam sections, backup elements, terminal end shoes, and special end shoes must meet the requirements of AASHTO M 180, for Class A guardrail.”
- 785\* 908.11.B Change the second paragraph to read:  
"Bolts, nuts, and round washers for guardrail, other than at bridge barrier railings, must meet the requirements of ASTM A 307 (Grade A), ASTM A 563 (Grade A with Supplementary Requirements S1 of ASTM A 563), and ASTM F 436, respectively."  
  
Change the third paragraph to read:  
"Washers, other than round washers, for guardrail must meet the requirements for circular washers in ASTM F 436 except that the dimensions must be as shown on the plans."  
  
Change the fifth paragraph to read:  
"Bolts, nuts, and washers for connections at bridge barrier railings must conform to ASTM F 3125 Grade A 325 Type 1 galvanized high-strength structural bolts with suitable nuts and hardened washers."
- 787 908.14.B Add the following sentence to the end of the third paragraph of this subsection:  
"Exposed threaded ends of anchor bolts must be galvanized a minimum of 20 inches."  
  
Change the sixth paragraph in this subsection to read:  
"Provide washers meeting the requirements of ASTM F 436 for circular washers."
- 787 908.14.B Change the second sentence of the fourth paragraph to read “After coating, the maximum limit of pitch and major diameter for bolts with a diameter no greater than 1 inch may exceed the Class 2A limit by no greater than 0.021 inch, and by no greater than 0.031 inch for bolts greater than 1 inch in diameter”.
- 787\* 908.14.C Change the first paragraph to read "Provide either four or six high strength anchor bolts per the contract plans, meeting the mechanical requirements of ASTM F 1554, for Grade 105, with each standard. Anchor bolts for traffic signal strain poles must meet the requirements of subsection 908.14.B with the following exceptions and additions:"
- 789 909.03 Change the second sentence of the second paragraph to read:  
"As an alternative to the AASHTO M 36 requirements for metal pipe, the Contractor may use gasket material meeting the low temperature flexibility and elevated temperature flow test requirements of ASTM C

|      |             |  |
|------|-------------|--|
|      |             | 990, excluding the requirements for softening point, flashpoint and fire point."   |
| 793  | 909.06      | Change the first sentence of the second paragraph of this subsection to read:<br>"Provide Corrugated Polyvinyl Chloride Pipe (CPV) and required fittings meeting the requirements of AASHTO M 304."  |
| 793* | 909.05.D    | Change the second sentence of the paragraph to read "Provide a continuous welded joint to create a watertight casing that is capable of withstanding handling and installation stresses. Perform field welding by the SMAW process using E7018 electrodes."  |
| 794* | 909.08.A    | Change the first sentence to read:<br>"Provide bridge deck downspouts of PE pipe meeting the requirements of ASTM F 714, PE 4710, DR 26."  |
| 804  | Table 909-9 | In the note area at the bottom of the table change the designation of the second note from "c." to "b."  |
| 811  | 910.04      | Add the following sentence to the end of this subsection:<br>"Fabricate silt fence according to subsection 916.02."  |
| 814  | Table 911-1 | In the 4 <sup>th</sup> row of the 5 rows in the table change the Property listed as "Total Organic Content (TOC)" to read "Total Organic Carbon (TOC)".  |
| 829* | 912.08.K    | Replace Table 912-10 with the Table 912-10 below.  |
| 833* | 913.03.B    | Change the first sentence of the first paragraph to read:<br>"Clay brick, to construct manholes, catch basins, and similar structures, must meet the requirements of ASTM C 32, for Grade MS."   |
| 837* | 914.04      | Add the following as subsection 914.04.C:<br><b>"C. Lubricant-Adhesive for Neoprene Joint Seals.</b> The lubricant-adhesive must be a single-component moisture-curing polyurethane and aromatic hydrocarbon solvent mixture meeting ASTM D 2835, Type I. Ship in containers plainly marked with the lot or batch number of the material and date of manufacture. Store at temperatures between 58 and 80°F. Do not exceed 12 months shelf-life prior to use." |
| 840  | 914.08      | Change the first sentence of the second paragraph to read: "Straight tie bars for end-of-pour joints must consist of bars of the diameter and length shown on the plans meeting the requirements of ASTM A 615, ASTM A 706, or ASTM A 996 (Type R or Type A only)".  |
| 840* | 914.09.A    | Change the first sentence of the first paragraph to read: "Straight tie bars for longitudinal pavement joints must consist of bars of the diameter and length shown on the plans meeting the requirements of ASTM A 615, ASTM A 706, or ASTM A 996 (Type R or Type A only)".   |

|      |            |  |
|------|------------|--|
| 840  | 914.09.B   | Change the first sentence of the first paragraph to read: "Bent tie bars for bulkhead joints must consist of bars of the diameter and length shown on the plans."  |
| 841  | 914.12     | In the first sentence of this subsection change "AASHTO Division II" to read "AASHTO LRFD Bridge Construction Specifications".   |
| 841* | 914.13     | In the first sentence of this subsection change "ASTM D 1248, for Type III, Class B" to read "ASTM D 4976, Group 2, Class 4, Grade 4".   |
| 844  | 916.01.A   | Change the first sentence to read: "Cobblestone must consist of rounded or semi-rounded rock fragments with an average dimension from 3 inches to 10 inches."  |
| 845  | 916.01.D.1 | Change the second sentence to read: "Checkdams for ditch grades 2 percent or greater must be constructed using cobblestone or broken concrete ranging from 3 inches to 10 inches in size."   |
| 851* | 917.10.B.1 | Delete the paragraph and replace it with the following:<br>"1. <b>Class A.</b> Provide and apply Class A chemical nutrient fertilizer either according to MSU Soil Testing Lab Recommendations for Phosphorus Applications to Turfgrass, except the maximum single application rate of nutrient will be 48 pounds per acre, when soil tests are required or as indicated in subsections 917.10.B.1.a and 917.10.B.1.b."  |
| 851  | 917.10.B.1 | Add the MSU Soil Testing Lab Recommendations for Phosphorus Applications to Turfgrass, found below, after the first paragraph of this subsection.  |
| 853  | 917.15.B.1 | Change the second sentence of the subsection to read:<br>"The net must meet the requirements of subsection 917.15.D and be capable of reinforcing the blanket to prevent damage during shipping, handling, and installation."  |
| 857  | 918.01     | Add the following two paragraphs following the first paragraph of this subsection:<br>"Wall thickness and outside diameter dimensions must conform to ASTM D 1785 for smooth-wall schedule 40 and 80 PVC conduit material. The Department will allow no more than 3 percent deviation from the minimum wall thickness specified.<br><br>Wall thickness range must be within 12 percent in accordance with ASTM D 3035 for smooth-wall coilable schedule 40 and 80 PE conduit." |
| 858  | 918.01.E   | Delete the first three sentences of the second paragraph shown on page 858.  |
| 863  | 918.06.F.1 | Delete the third paragraph in this subsection in its entirety and replace it with the following:   |



|      |          |   |
|------|----------|---|
|      |          | "Provide smooth or deformed welded wire fabric in accordance with ASTM A 1064."   |
| 864  | 918.07.C | Change the first sentence of the first paragraph to read:<br>"Provide anchor bolts, nuts, and washers meeting the requirements of subsection 908.14.A and subsection 908.14.B."   |
| 864  | 918.07.C | Delete the second sentence of the second paragraph.   |
| 864  | 918.07.C | Change the third sentence to read:<br>"Provide anchor bolts threaded 4 inches beyond the anchor bolt projection shown on the plans."  |
| 867  | 918.08.C | Change the last sentence of the first paragraph on this page to read:<br>"Galvanize bolts, nuts, washers, and lock washers as specified in subsection 908.14.B."  |
| 867  | 918.08.C | Change the last sentence of the subsection to read:<br>"Provide each frangible base with manufacturer access covers as shown on the plans."   |
| 867* | 918.08.D | Delete this subsection in its entirety and replace with the following:<br>"Provide galvanized anchor bolts, studs, nuts, couplings, and washers in accordance with subsection 908.14."  |
| 879  | 918.10.J | Change the third sentence of the second paragraph of this subsection to read:<br>"Provide anchor bolts and associated nuts, washers, and hardware meeting the requirements of subsection 908.14."   |
| 887  | 919.06   | Change the second paragraph to read:<br>"Shims must be fabricated from brass shim stock or brass strip meeting the requirements of ASTM B 36, for copper alloy UNS No. C26000, half-hard rolled temper, or fabricated from galvanized sheeting meeting the requirements of ASTM A 653, for Coating Designation G 90." |
| 887  | 919.07.C | Change the sentence to read:<br>"Galvanized high-strength steel bolts, nuts, and washers for connecting arm connection flanges must meet the requirements of subsection 906.07."  |
| 903  | 921.03.D | Delete the last three sentences of the first paragraph of this subsection.  |
| 914  | 921.05.D | Change the first sentence of this subsection to read:<br>"Provide anchor bolts meeting the requirements of subsection 908.14.C, including elongation and reduction of area requirements."   |
| 916  | 921.07   | Change the first sentence of the first paragraph to read: "Provide LED case signs internally illuminated by LEDs and changeable message case signs internally illuminated with LED light sources."  |

|      |                |   |
|------|----------------|---|
| 936  | 922.04.B       | In the first sentence of the first paragraph change the "R-52" to "R-126".  |
| 936  | 922.04.B       | Add the following to the end of the first paragraph:<br>"Hardware used to connect the end section to the barrier must meet the requirements of NCHRP 350 or MASH (Test Level 3 or higher)."   |
| 936  | 922.04.B       | In the first sentence of the second paragraph delete "R-52".  |
| 936  | 922.04.B       | Change the fourth paragraph of this subsection to read as follows:<br>For all endings requiring impact attenuators provide a NCHRP-350 Test Level 3 or MASH Test Level 3 approved impact attenuation system, unless otherwise approved by the Engineer.   |
| 953* | Pay Item Index | Delete the following pay item reading:<br>"DB Cable, in Conduit, 600 Volt, (number) 1/C# (size) .....678 819"   |
| 957  | Pay Item Index | Delete the following pay item from the list:<br>Guardrail Buffered End .....560 807   |
| 960  | Pay Item Index | Change the following pay item to read:<br>"Mobilization, Max (dollar) .....107 150"   |
| 961  | Pay item Index | Delete the following pay items from the list:<br>Pavt Mrkg, (material), 4 inch, SRSM, (color).....598.....811<br>Pavt Mrkg, (material), 4 inch, SRSM, 2 <sup>nd</sup> Application, (color).....598.....811  |
| 961  | Pay Item Index | Change the following pay items in the list to read:<br>Pavt Mrkg, Ovly Cold Plastic, 12 inch, Cross Hatching, (color)<br>Pavt Mrkg, Polyurea, __ inch, Cross Hatching, (color)<br><br>Add the following pay items to the list:<br>"Pavt Mrkg, Polyurea, (legend).....598.....811<br>Pavt Mrkg, Polyurea, (symbol).....598.....811<br>Pedestal, Pushbutton, Alum.....696.....820<br>Pedestal, Pushbutton, Rem.....696.....820" |
| 962  | Pay Item Index | Change the following pay items in the list to read:<br>"Pile Driving Equipment, Furn (Structure No.)<br>Pile, Galv (Structure No.)"   |
| 963  | Pay Item Index | Change the following pay item to read:<br>"Rem Curing Compound, for Longit Mrkg, __ inch .....598 811"  |
| 964  | Pay Item Index | Change the following pay item to read:<br>"Sewer, CI __, __ inch, Jacked in Place .....200 402"<br>"Sign Cover, Type I .....622 812"  |
| 965* | Pay Item Index | Change the following pay item in the list to read:  |

|      |                |  |            |             |
|------|----------------|--|------------|-------------|
|      |                | “Steel Casing Pipe, __ inch, Tr Det __<br>Site Preparation, Max (dollar) .....   | 646        | 815”        |
| 966  | Pay Item Index | Delete the following pay item form the list;<br>Temp Casing.....   | 533.....   | 718         |
| 967* | Pay Item Index | Delete the following pay item from the list;<br>Truss Fdn Anchor Bolts, Replace.....   | 584.....   | 810         |
| 967  | Pay Item Index | Change the following pay item in the list to read:<br>“Traf Regulator Control”   |            |             |
| 968* | Pay item Index | Change the following pay item in the list to read:<br>“Water Shutoff, Adj, Temp, Case __<br>Watering and Cultivating, First Season, Min (dollar).....<br>Watering and Cultivating, Second Season, Min (dollar) ..... | 646<br>646 | 815<br>815” |
| 993  | General Index  | Change “Shop Plans (see Plans and Working Drawings)” to read “Shop<br>Drawings (see Plans and Working Drawings)”.  |            |             |

**Table 701-1  
Concrete Structure Mixtures**

| Concrete Grade (e,h) | Section Number Reference (i)                | Cement Content per cyd (b,c) |      | Type A, D or no Admixture | Slump (inches)                  |                           |                               | Minimum Strength of Concrete (f) |        |                                |                   |        |                                |
|----------------------|---|------------------------------|------|---------------------------|---------------------------------|---------------------------|-------------------------------|----------------------------------|--------|--------------------------------|-------------------|--------|--------------------------------|
|                      |   | lb                           | sack |                           | Type MR, F, or G Admixtures (g) |                           |                               | Flexural (psi)                   |        |                                | Compressive (psi) |        |                                |
|                      |   |                              |      |                           | Before Admixture                | After Admixture (Type MR) | After Admixture (Type F or G) | 7 Day                            | 14 Day | 28 Day (Class Design Strength) | 7 Day             | 14 Day | 28 Day (Class Design Strength) |
| D (a)                | 706, 711, 712                               | 658 (d)                      | 7.0  | 0 - 3                     | 0 - 3                           | 0 - 6                     | 0 - 7                         | 625                              | 700    | 725                            | 3,200             | 4,000  | 4,500                          |
| S1                   | 705   | 611                          | 6.5  | 3 - 5                     | 0 - 3                           | 3 - 6                     | 3 - 7                         | 600                              | 650    | 700                            | 3,000             | 3,500  | 4,000                          |
| T                    | 705, 706                                    | 611                          | 6.5  | 3 - 7                     | 0 - 4                           | 3 - 7                     | 3 - 8                         | 550                              | 600    | 650                            | 2,600             | 3,000  | 3,500                          |
| S2 (a)               | 401, 705, 706, 712, 713, 801, 802, 803, 810 | 564                          | 6.0  | 0 - 3                     | 0 - 3                           | 0 - 6                     | 0 - 7                         | 550                              | 600    | 650                            | 2,600             | 3,000  | 3,500                          |
|                      |   | 526 (d)                      | 5.6  |                           |                                 |                           |                               |                                  |        |                                |                   |        |                                |
| S3                   | 402, 403, 803, 804, 806                     | 517                          | 5.5  | 0 - 3                     | 0 - 3                           | 0 - 6                     | 0 - 7                         | 500                              | 550    | 600                            | 2,200             | 2,600  | 3,000                          |
|                      |   | 489 (d)                      | 5.2  |                           |                                 |                           |                               |                                  |        |                                |                   |        |                                |

- a. Unless otherwise required, use Coarse Aggregate 6AA or 17A for exposed structural concrete in bridges, retaining walls, and pump stations.
- b. Do not place concrete mixtures containing supplemental cementitious materials unless the local average minimum temperature for the next 10 consecutive days is forecast to be above 40 °F. Adjustments to the time required for opening to construction or vehicular traffic may be necessary. Cold weather protection may be required, as described in the quality control plan. The restriction does not apply to Grade S1 concrete in foundation piling below ground level or Grade T concrete in tremie construction.
- c. Type III cement is not permitted
- d. Use admixture quantities specified by the Qualified Products Lists to reduce mixing water. Admixture use is required for Grade D, Grade S2, and Grade S3, concrete with a reduced cement content. Use a water-reducing retarding admixture at the required dosage for Grade D concrete to provide the setting retardation required. When the maximum air temperature is not forecast to exceed 60 °F for the day, the Contractor may use a water-reducing admixture or a water-reducing retarding admixture. Ensure Grade D concrete in concrete diaphragms contains a water-reducing admixture, or a water-reducing retarding admixture. For night casting, the Contractor may use a water-reducing admixture in lieu of water-reducing retarding admixture, provided that the concrete can be placed and finished prior to initial set.
- e. The mix design basis for bulk volume (dry, loose) of coarse aggregate per unit volume of concrete is 68% for Grade S1, and 70% for Grade D, Grade S2, Grade T, and Grade S3.
- f. The Contractor may use flexural strength to determine form removal. Use compressive strength for acceptance in other situations.
- g. MR = Mid-range.
- h. The Engineer will allow the use of an optimized aggregate gradation as specified in section 604.
- i. Section Number Reference:
- |     |                                  |     |                                    |     |  |
|-----|----------------------------------|-----|------------------------------------|-----|--|
| 401 | Culverts                         | 711 | Bridge Railings                    | 803 | Concrete Sidewalk, Sidewalk Ramps, and Steps |
| 402 | Storm Sewers                     | 712 | Bridge Rehabilitation-Concrete     | 804 | Concrete Barriers and Glare Screens          |
| 403 | Drainage Structures              | 713 | Bridge Rehabilitation-Steel        | 806 | Bicycle Paths                                |
| 705 | Foundation Piling                | 801 | Concrete Driveways                 | 810 | Permanent Traffic Signs and Supports         |
| 706 | Structural Concrete Construction | 802 | Concrete Curb, Gutter and Dividers |     |  |

**Table 902-6  
Superpave Final Aggregate Blend Physical Requirements**

| Est. Traffic<br>(million<br>ESAL) | Mix<br>Type | Percent Crushed<br>Minimum Criteria |                | Fine Aggregate<br>Angularity Minimum<br>Criteria |                | % Sand Equivalent<br>Minimum Criteria |                | Los Angeles Abrasion<br>% Loss Maximum<br>Criteria |                | % Soft Particles<br>Maximum Criteria<br>(b) |                | % Flat and<br>Elongated Particles<br>Maximum Criteria<br>(c) |                |
|-----------------------------------|-------------|-------------------------------------|----------------|--|----------------|---------------------------------------|----------------|--|----------------|---|----------------|--|----------------|
|                                   |             | Top &<br>Leveling<br>Courses        | Base<br>Course | Top &<br>Leveling<br>Courses                     | Base<br>Course | Top &<br>Leveling<br>Courses          | Base<br>Course | Top &<br>Leveling<br>Courses                       | Base<br>Course | Top &<br>Leveling<br>Courses                | Base<br>Course | Top &<br>Leveling<br>Courses                                 | Base<br>Course |
| < 0.3                             | LVSP        | 55/—                                | —              | —  | —              | 40                                    | 40             | 45   | 45             | 10  | 10             | —  | —              |
| < 0.3                             | E03         | 55/—                                | —              | —  | —              | 40                                    | 40             | 45   | 45             | 10  | 10             | —  | —              |
| ≥0.3 - <1.0                       | E1          | 65/—                                | —              | 40   | —              | 40                                    | 40             | 40   | 45             | 10  | 10             | —  | —              |
| ≥1.0 - <3                         | E3          | 75/—                                | 50/—           | 40(a)  | 40(a)          | 40                                    | 40             | 35   | 40             | 5   | 5              | 10   | 10             |
| ≥3 - <10                          | E10         | 85/80                               | 60/—           | 45   | 40             | 45                                    | 45             | 35   | 40             | 5   | 5              | 10   | 10             |
| ≥10 - <30                         | E30         | 95/90                               | 80/75          | 45   | 40             | 45                                    | 45             | 35   | 35             | 3   | 4.5            | 10   | 10             |
| ≥30 - <100                        | E50         | 100/10<br>0                         | 95/90          | 45   | 45             | 50                                    | 50             | 35   | 35             | 3   | 4.5            | 10   | 10             |

- (a) For an E3 mixture type that enters the restricted zone as defined in Table 902-5, the minimum is 43. If these criteria are satisfied, acceptance criteria and associated incentive/disincentive or pay adjustment tied to this gradation restricted zone requirement included in contract, do not apply. Otherwise, final gradation blend must be outside of the restricted zone.
- (b) Soft particles maximum is the sum of the shale, siltstone, ochre, coal, clay-ironstone and particles that are structurally weak or are non-durable in service.
- (c) Maximum by weight with a 1 to 5 aspect ratio.

Note: "85/80" denotes that 85 percent of the coarse aggregate has one fractured face and 80 percent has at least two fractured faces.

| <b>Table 912-10<br/>Minimum Retention Requirements</b>   |  |                   |  |                      |
|--|--|-------------------|--|----------------------|
| <b>Preservative</b>  | <b>Minimum Retention, (pcf)</b>                            |                   |  | <b>AWPA Standard</b> |
|  | <b>Guardrail Posts</b>                                     | <b>Sign Posts</b> | <b>Blocks</b>  |                      |
| Pentachlorophenol  | 0.60   | 0.50              | 0.40   | A6                   |
| CCA, ACZA  | 0.60   | 0.50              | 0.40   | A11                  |
| ACQ (a)  | 0.60   | Not Allowed       | 0.40   | A11                  |
| CA-B (a)   | 0.31   | Not Allowed       | 0.21   | A11                  |
| CA-A (a)   | 0.31   | Not Allowed       | 0.15   | A11                  |
| Other Waterborne preservatives   | AWPA Commodity Specification A, Table 3.0, Use Category 4B | Not Allowed       | AWPA Commodity Specification A, Table 3.0, Use Category 4A | A11                  |
| a. Non-Metallic washers or spacers are required for timber and lumber treated with ACQ or CA placed in direct contact with aluminum. Do not use with sign posts. |  |                   |  |                      |







MSU Soil Testing Lab Recommendations for Phosphorus Applications to Turfgrass  
3/8/2012

|  |                                    | Sand based rootzone establishment   | Golf greens and tees est. or mature; Kentucky bluegrass or perennial ryegrass athletic fields est. or mature; sand based rootzone mature | Lawns, golf course fairways; establishment or mature                        | Establishment without soil test   |
|--|------------------------------------|---|--|---|---|
| Bray P1, Mehlich 3 Soil Test Value (ppm): pH<7.4 | Olsen Soil Test Value (ppm) pH>7.4 | Recommendation (lbs. P <sub>2</sub> O <sub>5</sub> /1000 ft. <sup>2</sup> ) | Recommendation (lbs. P <sub>2</sub> O <sub>5</sub> /1000 ft. <sup>2</sup> )  | Recommendation (lbs. P <sub>2</sub> O <sub>5</sub> /1000 ft. <sup>2</sup> ) | Recommendation (lbs. P <sub>2</sub> O <sub>5</sub> /1000 ft. <sup>2</sup> ) |
| 0  | 0                                  | 4.4   | 3.4  | 2.5   | 2.5 lbs. year (Maximum single application of 1.5 lbs.)                      |
| 2  | 1.3                                | 4.1   | 3.1  | 2.2   |   |
| 4  | 2.7                                | 3.9   | 2.7  | 1.9   |   |
| 6  | 4                                  | 3.6   | 2.4  | 1.6   |   |
| 8  | 5.3                                | 3.4   | 2.0  | 1.3   |   |
| 10   | 6.7                                | 3.1   | 1.7  | 1.0   |   |
| 12   | 8                                  | 2.8   | 1.4  | 0.7   |   |
| 14   | 9.3                                | 2.6   | 1.0  | 0.4   |   |
| 16   | 10.7                               | 2.3   | 0.7  | 0.1   |   |
| 18   | 12                                 | 2.1   | 0.3  | 0.0   |   |
| 20   | 13.3                               | 1.8   | 0.0  |   |   |
| 22   | 14.7                               | 1.5   |  |   |   |
| 24   | 16                                 | 1.3   |  |   |   |
| 26   | 17.3                               | 1.0   |  |   |   |
| 28   | 18.7                               | 0.8   |  |   |   |
| 30   | 20                                 | 0.5   |  |   |   |
| 32   | 21.3                               | 0.2   |  |   |   |
| 34   | 22.7                               | 0.0   |  |   |   |

Web resources: [www.turf.msu.edu](http://www.turf.msu.edu) or [www.bephosphorusmart.msu.edu](http://www.bephosphorusmart.msu.edu)

● APPLICABLE SOIL EROSION AND SEDIMENTATION CONTROL MEASURES  
 ( COMPREHENSIVE DETAILS ARE LOCATED IN SECTION 6 OF  
 THE SOIL EROSION & SEDIMENTATION CONTROL MANUAL )

- A = SLOPES
- B = STREAMS AND WATERWAYS
- C = SURFACE DRAINAGEWAYS
- D = ENCLOSED DRAINAGE (INLET & OUTFALL CONTROL)
- E = LARGE FLAT SURFACE AREAS
- F = BORROW AND STOCKPILE AREAS
- G = DNRE PERMIT MAY BE REQUIRED

| KEY | DETAIL  | CHARACTERISTICS   | A | B | C | D | E | F | G |
|-----|---|---|---|---|---|---|---|---|---|
| 1   | <br>TURBIDITY CURTAIN            | A Turbidity Curtain is used when slack water area is necessary to isolate construction activities from the watercourse. The still water area contains the sediments within the construction limits.   |   | ● |   |   |   |   |   |
| 2   | <br>GRUBBING OMITTED             | Retains existing root mat which assists in stabilizing slopes. Assists in the revegetation process by providing sprout growth. Reduces sheet flow velocities preventing rilling and gulying. Discourages off-road vehicle use.                            | ● |   |   |   | ● |   |   |
| 3   | <br>PERMANENT/TEMPORARY SEEDING | Inexpensive but effective erosion control measure to stabilize flat areas and mild slopes. Permits runoff to infiltrate soil, reducing runoff volumes. Proper preparation of the seed bed, fertilizing, mulching and watering is critical to its success. | ● |   | ● |   | ● | ● |   |
| 4   | <br>DUST CONTROL               | Dust control can be accomplished by watering, and/or applying calcium chloride. The disturbed areas should be kept to a minimum. PERMANENT/TEMPORARY SEEDING (KEY 3) should be applied as soon as possible.   | ● |   |   |   | ● | ● |   |
| 5   | <br>SODDING                    | Provides immediate vegetative cover such as at spillways and ditch bottoms. Proper preparation of the topsoil, placement of the sod, and watering is critical to its success.   | ● |   |   |   | ● | ● |   |
| 6   | <br>VEGETATED BUFFER STRIPS    | Reduces sheet flow velocities preventing rilling and gulying. Assists in the collection of sediments by filtering runoff. Assists in the establishment of a permanent vegetative cover.   | ● |   |   |   | ● |   |   |




PREPARED BY  
DESIGN DIVISION

DRAWN BY: B.L.T.

CHECKED BY: W.K.P.

DEPARTMENT DIRECTOR  
Kirk T. Stuedle

APPROVED BY:   
ENGINEER OF DELIVERY

APPROVED BY:   
ENGINEER OF DEVELOPMENT

MICHIGAN DEPARTMENT OF TRANSPORTATION  
BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR

SOIL EROSION & SEDIMENTATION  
CONTROL MEASURES









9-10-2010  
F.H.W.A. APPROVAL

6-3-2010  
PLAN DATE

R-96-E

SHEET  
31 OF 6



| KEY | DETAIL   | CHARACTERISTICS  | A | B | C | D | E | F | G |
|-----|--|--|---|---|---|---|---|---|---|
| 7   |  <p>RIPRAP</p>                                  | <p>Used where vegetation cannot be established.<br/>Very effective in protecting against high velocity flows.<br/>Should be placed over a geotextile liner.</p>  | • | • | • | • |   |   | • |
| 8   |  <p>AGGREGATE COVER</p>                         | <p>Can be used in any area where a stable condition is needed for construction operations, equipment storage or in heavy traffic areas.<br/>Reduces potential soil erosion and fugitive dust by stabilizing raw areas.</p>   | • |   |   |   | • | • |   |
| 9   |  <p>BENCHES</p>                                 | <p>Reduces sheet flow velocities preventing rilling and gulying.<br/>Assists in the collection and filtering of sediments.<br/>Provides access for stabilizing slopes.</p>   | • |   |   |   |   | • |   |
| 10  |  <p>DIVERSION DIKE</p>                          | <p>Assists in the diversion of runoff to a stable outlet or sediment control device.<br/>Reduces sheet flow velocities preventing rilling and gulying.<br/>Collects and diverts runoff to properly stabilized drainage ways.<br/>Works well with INTERCEPTING DITCH (KEY 11)</p> | • |   |   |   | • | • |   |
| 11  |  <p>INTERCEPTING DITCH</p>                     | <p>Assists in the diversion of runoff to a stable outlet or sediment control device.<br/>Reduces sheet flow velocities preventing rilling and gulying.<br/>Works well with DIVERSION DIKE (KEY 10)</p>   | • |   |   |   | • | • |   |
| 12  |  <p>INTERCEPTING DITCH AND DIVERSION DIKE</p> | <p>Assists in the diversion of runoff to a stable outlet or sediment control device.<br/>Reduces sheet flow velocities preventing rilling and gulying.</p>   | • |   |   |   | • | • |   |
| 13  |  <p>GRAVEL FILTER BERM</p>                    | <p>Useful in filtering flow prior to its reentry into a lake, stream or wetland.<br/>Works well with SEDIMENT TRAP (KEY 20) and TEMPORARY BYPASS CHANNEL (KEY 35).<br/>Not to be used in lieu of a CHECK DAM (KEY 37) in a ditch.</p>  | • |   | • |   |   | • |   |
| 14  |  <p>GRAVEL ACCESS APPROACH</p>                | <p>Provides a stable access to roadways minimizing fugitive dust and tracking of materials onto public streets and highways.</p>   |   |   |   |   |   | • | • |

MICHIGAN DEPARTMENT OF TRANSPORTATION  
BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR









SOIL EROSION & SEDIMENTATION  
CONTROL MEASURES

9-10-2010  
F.H.W.A. APPROVAL

6-3-2010  
PLAN DATE

R-96-E

SHEET  
32 OF 6

| KEY | DETAIL  | CHARACTERISTICS  | A | B | C | D | E | F | G |
|-----|---|--|---|---|---|---|---|---|---|
| 15  |  <p>SLOPE DRAIN SURFACE</p>                | <p>Excellent device for carrying water down slopes without creating an erosive condition.</p> <p>Generally used in conjunction with DIVERSION DIKE (KEY 10), INTERCEPTING DIKE (KEY 11) and INTERCEPTING DIKE AND DIVERSION DIKE (KEY 12) to direct flow to a stable discharge area or SEDIMENT TRAP (KEY 20).</p>   | • |   | • |   |   |   |   |
| 16  |  <p>TREES, SHRUBS AND PERENNIALS</p>       | <p>Trees, shrubs and perennials can provide low maintenance long term erosion protection. These plants may be particularly useful where site aesthetics are important along the roadside slopes.</p>   | • |   |   |   | • |   |   |
| 17  |  <p>PIPE DROP</p>                          | <p>Effective way to allow water to drop in elevation very rapidly without causing an erosive condition.</p> <p>Also works as a sediment collector device.</p> <p>May be left in place as a permanent erosion control device.</p>   | • |   | • |   |   |   |   |
| 18  |  <p>DEWATERING WITH FILTER BAG</p>         | <p>It may be necessary to dewater from behind a cofferdam or construction dam to create a dry work site.</p> <p>Discharged water must be pumped to a filter bag.</p> <p>A GRAVEL FILTER BERM (KEY 13) may be placed downslope of the filter bag to provide additional filtration prior to entering any stream or wetland.</p>                                  |   | • |   |   |   |   | • |
| 19  |  <p>ENERGY DISSIPATORS</p>                | <p>A device to prevent the erosive force of water from eroding soils.</p> <p>Used at outlets of culverts, drainage pipes or other conduits to reduce the velocity of the water.</p> <p>Prevents structure scouring and undermining.</p>  | • | • | • | • |   |   |   |
| 20  |  <p>SEDIMENT TRAP</p>                    | <p>Used to intercept concentrated flows and prevent sediments from being transported off site or into a watercourse or wetland.</p> <p>The size of a Sediment Trap is 5 cubic yards or less.</p> <p>Works well when used with CHECK DAM (KEY 37).</p>  | • |   | • | • |   |   |   |
| 21  |  <p>SEDIMENT BASIN</p>                   | <p>A Sediment Basin is used to trap sediments from an upstream construction site.</p> <p>Requires periodic inspections, repairs, and maintenance.</p> <p>Where practical, sediments should be contained on site.</p> <p>A Sediment Basin should be the last choice of sediment control.</p> <p>The size of a Sediment Basin is greater than 5 cubic yards.</p> |   | • |   |   |   |   | • |
| 22  |  <p>VEGETATIVE BUFFER AT WATERCOURSE</p> | <p>This practice is used to maintain a vegetative buffer adjacent to a watercourse.</p> <p>When utilized with SILT FENCE (KEY 26) it will, under normal circumstances, prevent sediment from leaving the construction site.</p>  | • | • | • |   | • | • |   |

MICHIGAN DEPARTMENT OF TRANSPORTATION  
BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR









SOIL EROSION & SEDIMENTATION  
CONTROL MEASURES

9-10-2010  
F.H.W.A. APPROVAL

6-3-2010  
PLAN DATE

R-96-E

SHEET  
33 OF 6

| KEY | DETAIL  | CHARACTERISTICS   | A | B | C | D | E | F | G |
|-----|---|---|---|---|---|---|---|---|---|
| 23  |  <p><b>STREAM RELOCATION</b></p>                       | <p>A detail depicting the proper procedures for stream relocation. Maintains same width, depth, and flow velocity as the natural stream. Revegetate banks with PERMANENT/TEMPORARY SEEDING (KEY 3), MULCHING AND MULCH ANCHORING (KEY 28), MULCH BLANKETS AND HIGH VELOCITY MULCH BLANKETS (KEY 33) and woody plants to shade the stream.</p> |   | • |   |   |   |   | • |
| 24  |  <p><b>SAND AND STONE BAGS</b></p>                     | <p>Sand and stone bags are a useful tool in the prevention of erosion. Can be used to divert water around a construction site by creating a DIVERSION DIKE (KEY 10). Works well for creating a CONSTRUCTION DAM (KEY 36) and temporary culvert end fill.</p>  | • | • | • | • | • | • | • |
| 25  |  <p><b>SAND FENCE AND DUNE STABILIZATION</b></p>       | <p>A Sand Fence traps blowing sand by reducing wind velocities. Can be used to prevent sand from blowing onto roads. Must be maintained until sand source is stabilized.</p>  | • |   |   |   | • | • |   |
| 26  |  <p><b>SILT FENCE</b></p>                              | <p>A permeable barrier erected below disturbed areas to capture sediments from sheet flow. Can be used to divert small volumes of water to stable outlets. Ineffective as a filter and should never be placed across streams or ditches where flow is concentrated.</p>   | • |   |   |   | • | • |   |
| 27  |  <p><b>PLASTIC SHEETS OR GEOTEXTILE COVER</b></p>     | <p>Plastic Sheets can be used to create a liner in temporary channels. Can also be used to create a temporary cover to prevent erosion of stockpiled materials.</p>   | • | • | • |   |   | • |   |
| 28  |  <p><b>MULCHING AND MULCH ANCHORING</b></p>          | <p>Anchored mulch provides erosion protection against rain and wind. Mulch must be used on seeded areas to promote water retention and growth. Should be inspected after every rainstorm and repaired as necessary until vegetation is well established.</p>  | • |   | • |   | • | • |   |
| 29  |  <p><b>INLET PROTECTION FABRIC DROP</b></p>          | <p>Provides settling and filtering of silt laden water prior to its entry into the drainage system. Can be used in median and side ditches where vegetation will be disturbed. Allows for early use of drainage systems prior to project completion.</p>  |   |   | • |   | • |   |   |
| 30  |  <p><b>INLET PROTECTION GEOTEXTILE AND STONE</b></p> | <p>Provides settling and filtering of silt laden water prior to its entry into the drainage system. Should be used in paved areas where drainage structures are existing or proposed. Allows for early use of drainage systems prior to project completion.</p>   |   |   | • |   | • |   |   |

MICHIGAN DEPARTMENT OF TRANSPORTATION  
BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR








**SOIL EROSION & SEDIMENTATION  
CONTROL MEASURES**

9-10-2010  
F.H.W.A. APPROVAL

6-3-2010  
PLAN DATE

**R-96-E**

SHEET  
34 OF 6

| KEY | DETAIL   | CHARACTERISTICS   | A | B | C | D | E | F | G |
|-----|--|---|---|---|---|---|---|---|---|
| 31  |  <p>INLET PROTECTION SEDIMENT TRAP</p>                  | <p>An Inlet Protection Sediment Trap is a temporary device that can be used in areas where medium flows are anticipated. Effective in trapping small quantities of sediments prior to water entering the drainage system. Can be used in areas such as median and side ditches.</p>   |   |   | • |   | • |   |   |
| 32  |  <p>SLOPE ROUGHENING AND SCARIFICATION</p>              | <p>A simple and economical way to reduce soil erosion by wind and water. Can be accomplished by harrowing with a disk, back blading, or tracking with a dozer perpendicular to the slope.</p>   | • |   |   |   | • | • |   |
| 33  |  <p>MULCH BLANKETS AND HIGH VELOCITY MULCH BLANKETS</p> | <p>Mulch blankets provide an immediate and effective cover over raw erodible slopes affording excellent protection against rain and wind erosion. High velocity mulch blankets work well for stabilizing the bottom of ditches in waterways.</p>  | • |   | • |   | • | • |   |
| 34  |  <p>COFFERDAM</p>                                       | <p>Used to create a dry construction area and protect the stream from raw erodible areas. Must be pumped dry or dewatered according to DEWATERING WITH FILTER BAG (KEY 18).</p>   |   | • |   |   |   |   | • |
| 35  |  <p>TEMPORARY BYPASS CHANNEL</p>                       | <p>Utilized when a dry construction area is needed. Isolates stream flows from raw erodible areas minimizing erosion and subsequent siltation. Can incorporate SEDIMENT BASIN (KEY 21), CHECK DAM (KEY 37), and GRAVEL FILTER BERM (KEY 13) to remove sediments from water. Construction sequence of events may be necessary.</p> |   | • |   |   |   |   | • |
| 36  |  <p>CONSTRUCTION DAM</p>                              | <p>Used to create a dry or slack water area for construction. Isolates the stream from raw erodible areas. Can be created out of any non-erodible materials such as SAND AND STONE BAGS (KEY 24), a gravel dike with clay core or plastic liner, steel plates or plywood.</p>   |   | • |   |   |   |   | • |
| 37  |  <p>CHECK DAM</p>                                     | <p>Can be constructed across ditches or any area of concentrated flow. Protects vegetation in early stages of growth. A Check Dam is intended to reduce water velocities and capture sediment. A Check Dam is not a filtering device.</p>   | • |   | • |   |   | • |   |

MICHIGAN DEPARTMENT OF TRANSPORTATION  
BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR

SOIL EROSION & SEDIMENTATION  
CONTROL MEASURES

9-10-2010  
F.H.W.A. APPROVAL

6-3-2010  
PLAN DATE

R-96-E

SHEET  
35 OF 6

NOTES:

THIS STANDARD PLAN WILL SERVE AS A KEY IN THE SELECTION OF THE APPROPRIATE SOIL EROSION AND SEDIMENTATION CONTROL DETAILS. THIS PLAN ALSO PROVIDES THE KEY TO THE NUMBERED EROSION CONTROL ITEMS SPECIFIED ON THE CONSTRUCTION PLANS. REFER TO THE MDOT SOIL EROSION & SEDIMENTATION CONTROL MANUAL, SECTION 6 FOR SPECIFIC DETAILS, CONTRACT ITEMS (PAY ITEMS), AND PAY UNITS.

COLLECTED SILT AND SEDIMENT SHALL BE REMOVED PERIODICALLY TO MAINTAIN THE EFFECTIVENESS OF THE SEDIMENT TRAP, SEDIMENT BASIN, AND SILT FENCE. AGGREGATES PLACED IN STREAMS SHOULD CONTAIN A MINIMUM OF FINES.

TEMPORARY EROSION AND SEDIMENTATION CONTROL PROVISIONS SHALL BE COORDINATED WITH THE PERMANENT CONTROL MEASURES TO ASSURE EFFECTIVE CONTROL OF SEDIMENTS DURING CONSTRUCTION OF THE PROJECT.

ALL TEMPORARY EROSION CONTROL DEVICES SHALL BE REMOVED AFTER VEGETATION ESTABLISHMENT OR AT THE DISCRETION OF THE ENGINEER. CARE SHALL BE TAKEN DURING REMOVAL TO MINIMIZE SILTATION IN NEARBY DRAINAGE COURSES.

MICHIGAN DEPARTMENT OF TRANSPORTATION  
BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR

SOIL EROSION & SEDIMENTATION  
CONTROL MEASURES

9-10-2010  
F.H.W.A. APPROVAL

6-3-2010  
PLAN DATE

R-96-E

SHEET  
36 OF 6