Miller Road Bridge & Roundabout Project

October 15, 2019



Celebrating

100 years

serving the people of Washtenaw County







- 1. Project Background
- 2. Project Details
 - 1. Roundabout
 - 2. Bridge
 - 3. Resurfacing
- 3. Construction Schedule





Celebrating

100 years

serving the people of Washtenaw County

PROJECT BACKGROUND

Miller Road at Wagner Rd





- Intersection of two primary roads
- Congestion
 - Miller Road: 9,000 vehicles/day
 - Wagner Road: 7,200 vehicles/day

In "Top 5" busiest un-signalized intersections

Potential Solutions



VS.



Signalized Intersection Concept



TREES REMOVED FOR SIGNAL OPTION BUT NOT REMOVED FOR ROUNDABOUT OPTION

8

NORTH (THIS CONCEPT WAS CONSIDERED, BUT WAS DISMISSED AND IS NOT BEING ADVANCED)





Benefits of Roundabouts

- Higher level of service
- Improved mobility
- Enhanced safety
- Improved air quality
- Smaller footprint

Examples of Success



Before v. After: Textile Road @ Hitchingham Road





ROUNDABOUT OPERATIONS

Celebrating

100 years

serving the people of Washtenaw County

Roundabout

- Entering traffic yields
- Counterclockwise
 movement
- Islands control speed



Trucks and Large Vehicles







Celebrating

ROUNDABOUT PROJECT

100 years serving the people of Washtenaw County

The Plan

- Single-lane roundabout
- Concrete curb and gutter
- Stamped concrete
- Potential landscaping in central island
- Street lights
- Improved drainage

Nighttime Illumination



Final Product







BRIDGE PROJECT

Celebrating

100 years

serving the people of Washtenaw County

Miller Road over Honey Creek Bridge



Current State

- Built in 1930s
- Structurally deficient weight restricted
- Functionally obsolete
 - Narrow
 - Compound, horizontal curve

Current State



Miller Road over Honey Creek Bridge Correction of Horizontal Curve











RESURFACING PROJECT

Celebrating

100 years

serving the people of Washtenaw County

Current State

Existing pavement in poor condition



Miller Road Resurfacing

Between Bridge and Roundabout



Potential Solutions

Pulverize and Resurface

- Keep road width within current footprint
- Fix pavement problems
- Minimal tree removal and impact to property

Pulverize, Widen and Resurface

- Re-ditching, new culverts and driveway approaches
- Widen paved shoulders
- Significant tree removal
- Need for grading permits from property owners

Tree Removal

Project Segment	Initial Design	Current Design
Roundabout	~81 trees	~72 trees
Bridge	~37 trees	~21 trees
Resurfacing	~76 trees	0 trees
Totals	~194 trees	~93 trees



 Pulverize and resurface 1/3 mile between bridge and intersection

• Funding source: local funds





TIMELINE & DETOUR

100 years

Celebrating

serving the people of Washtenaw County

Proposed Construction Schedule

- Tree removal: Spring
- Utilities relocation: Spring
- Roundabout: May July
- Bridge and road resurfacing: July August

Impacts to Traffic

- Roundabout Construction
 - Intersection will be closed to ALL traffic
 - Property owners will be provided access during construction
 - Detour will be posted

Posted Detour - Roundabout



Impacts to Traffic

- Bridge Construction and Road Resurfacing
 - 3 legs of intersection will be reopened
 - Bridge closed to ALL traffic
 - Property owners will be provided access during construction
 - Detour will be posted

Posted Detour – Bridge & Resurfacing



Connect with WCRC!

- Visit <u>wcroads.org</u>
- Subscribe to receive updates via email
- Contacts:

Matt MacDonell, PE <u>macdonellm@wcroads.org</u> 734.327.6688 Nate Murphy, PE <u>murphyn@wcroads.org</u> 734.327.6647

Follow @WashtenawRoads on Facebook and Twitter

