

2026 AUGUSTA TOWNSHIP AGREEMENT

THIS AGREEMENT, made and entered into this 25 day of March, 2026, by and between the Township Board of Augusta Township ("Augusta Township"), Washtenaw County, and the Board of Washtenaw County Road Commissioners ("WCRC").

WHEREAS, Augusta Township desires that certain improvements be made upon the local roads in the Township of Augusta, and

WHEREAS, proper authority is provided to the parties of the agreement under the provisions in Act 51 of Public Acts of 1951 as amended,

IT IS NOW THEREFORE AGREED, the WCRC will accomplish the improvements as specified herein, all in accordance with the standards of the Board of Washtenaw County Road Commissioners,

IT IS FURTHER AGREED, Augusta Township shall pay WCRC for the actual project costs incurred for the project; and

IT IS FURTHER AGREED, the WCRC will submit an invoice to the Township on July 1, 2026, for 50% of the estimated project costs. Following project completion and final accounting of the project costs, WCRC will submit the final invoice for the actual remaining unpaid costs. The final invoice shall provide supporting detail and information, which reasonably identifies the actual project costs incurred by WCRC. The Township agrees to remit payment within 30 days from receipt of WCRC invoices.

Bunton Road, Liss Road to Willow Road (1.27 Miles)

Work to include forestry, shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 2,900 tons) with associated dust control and project restoration.

Estimated total project cost: \$ 76,000.00

Tuttle Hill Road, Willow Road to County Line (2.04 Miles)

Work to include forestry, shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 4,800 tons) with associated dust control and project restoration.

Estimated project cost: \$ 125,000.00

Judd Road, Bunton Road to Tuttle Hill Road (1.33 Miles)

Work to include forestry, shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 3,000 tons) with associated dust control and project restoration.

Estimated project cost: \$ 89,000.00

Judd Road, Hitchingham Road to Whittaker Road (1.02 Miles)

Work to include forestry, shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 2,400 tons) with associated dust control and project restoration.

Estimated project cost: \$ 65,000.00

Judd Road, Hitchingham Road to Pitman Road (.50 Miles)

Work to include shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 1,600 tons) with associated dust control and project restoration.

Estimated project cost: \$ 38,000.00

AGREEMENT SUMMARY

2026 LOCAL ROAD PROGRAM

Bunton Road, Liss Road to Willow Road (1.27 Miles)	\$	76,000.00
Tuttle Hill Road, Willow Road to County Line (2.04 Miles)	\$	125,000.00
Judd Road, Bunton Road to Tuttle Hill Road (1.33 Miles)	\$	89,000.00
Judd Road, Hitchingham Road to Whittaker Road (1.02 Miles)	\$	65,000.00
Judd Road, Hitchingham Road to Pitman Road (.50 Miles)	\$	38,000.00

Subtotal \$ 393,000.00

Less WCRC 2026 Local Matching Funds \$ 190,052.00

ESTIMATED AMOUNT TO BE PAID BY AUGUSTA TOWNSHIP UNDER THIS AGREEMENT DURING 2026: \$ 202,948.00

AUGUSTA TOWNSHIP:



Todd Waller, Supervisor



Kimberly Gonczy, Clerk

WASHTENAW COUNTY ROAD COMMISSION:

Barbara Ryan Fuller, Chair

Matthew MacDonell, Managing Director