

2026 SCIO TOWNSHIP AGREEMENT

THIS AGREEMENT, made and entered into this 28 day of April, 2026, by and between the Township Board of Scio Township ("Scio Township"), Washtenaw County, and the Board of Washtenaw County Road Commissioners ("WCRC").

WHEREAS, Scio Township desires that certain improvements be made upon the local roads in the Township of Scio, and

WHEREAS, proper authority is provided to the parties of the agreement under the provisions in Act 51 of Public Acts of 1951 as amended,

IT IS NOW THEREFORE AGREED, the WCRC will accomplish the improvements as specified herein, all in accordance with the standards of the Board of Washtenaw County Road Commissioners,

IT IS FURTHER AGREED, Scio Township shall pay WCRC for the actual project costs incurred for the project; and

IT IS FURTHER AGREED, the WCRC will submit an invoice to the township on July 1, 2026, for 50% of the estimated project Costs. WCRC will submit the final invoice for the actual remaining unpaid costs. The final invoice shall provide supporting detail and information, which reasonably identifies the actual project costs incurred by WCRC. The Township agrees to remit payment within 30 days from receipt of WCRC invoices.

West Delhi Road, Miller Road to Railroad Street(1.27mi)

Work to include drainage improvements, forestry, shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 3,700 tons) with associated dust control and project restoration.

Estimated total project cost: \$ 111,000.00

Craig Road, Wagner Road to Thornapple Drive(.28mi)

Work to include forestry, shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 400 tons) with associated dust control and project restoration.

Estimated project cost: \$ 18,000.00

Craig Road, Maple Road to Walnut Road(.42mi)

Work to include shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 1,000 tons) with associated dust control and project restoration.

Estimated project cost: \$ 25,000.00

Liberty Road, Stags Leap to Zeeb Road(.8mi)

Work to include drainage improvements, forestry, shaping the existing surface, and the application of 6" of 23A Limestone (C.I.P.) (approximately 2,800 tons) with associated dust control and project restoration.

Estimated project cost: \$ 89,000.00

Morrison Road, Dexter Ann Arbor Rd to End of Road(.6mi)

Work to include drainage improvements, forestry, shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 300 tons) with associated dust control and project restoration.

Estimated project cost: \$ 18,000.00

West Street, Railroad Street to End of Road(370ft)

Work to include forestry, shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 100 tons) with associated dust control and project restoration.

Estimated project cost: \$ 7,000.00

Riverbend Drive, N. Maple Road to Pavement(.42mi)

Work to include drainage improvements, forestry, shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 300 tons) with associated dust control and project restoration.

Estimated project cost: \$ 26,000.00

Bandera Drive, West Liberty Road to West Liberty Road(.51mi)

Work to include drainage improvements, shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately 300 tons) with associated dust control and project restoration.

Estimated project cost: \$ 14,000.00

Shevchenko Drive, Bandera Drive to Bandera Drive(.43mi)

Work to include drainage improvements, shaping the existing surface, and the application of 3" of 23A Limestone (C.I.P.) (approximately 200 tons) with associated dust control and project restoration.

Estimated project cost: \$ 11,000.00

Elizabeth Road, N. Wagner Road to End of Road(.23mi)

Work to include drainage improvements, forestry, shaping the existing surface, and the application of 4" of 23A Limestone (C.I.P.) (approximately (200 tons) with associated dust control and project restoration.

Estimated project cost: \$ 15,000.00

Marshall Road, Baker Road to End of Pavement(.32mi)

Work to include Chipseal and Fogseal.

Estimated project cost: \$ 17,000.00

Tubbs Road, Huron River Drive Approach

Work to include shaping the existing surface, replacement of the paved approach by HMA cold milling, the placement of 3" HMA pavement, aggregate shoulders, and project restoration.

Estimated project cost: \$ 75,000.00

Roseland Drive, Laurentide Drive to Craig Road(.4mi)

Work to include drainage improvements, forestry, heavy brushing, shaping the existing surface, and the application of 6" of 23A Limestone (C.I.P.) (approximately (1400 tons) with associated dust control and project restoration.

Estimated project cost: \$ 140,000.00

AGREEMENT SUMMARY

2026 LOCAL ROAD PROGRAM

West Delhi Road, Miller Road to Railroad Street	\$	111,000.00
Craig Road, Wagner Road to Thornapple Drive	\$	18,000.00
Craig Road, Maple Road to Walnut Road	\$	25,000.00
Liberty Road, Stags Leap to Zeeb Road	\$	89,000.00
Morrison Road, Dexter Ann Arbor Rd to End of Road	\$	18,000.00
West Street, Railroad Street to End of Road	\$	7,000.00
Riverbend Drive, N. Maple Road to Pavement	\$	26,000.00
Bandera Drive, West Liberty Road to West Liberty Road	\$	14,000.00
Shevchenko Drive, Bandera Drive to Bandera Drive	\$	11,000.00
Elizabeth Road, N. Wagner Road to End of Road	\$	15,000.00
Marshall Road, Baker Road to End of Pavement	\$	17,000.00
Tubbs Road, Huron River Drive Approach	\$	75,000.00
Roseland Drive, Laurentide Drive to Craig Road	\$	140,000.00
Subtotal	\$	566,000.00
Less WCRC 2026 Local Matching Funds	\$	266,528.00

